

**COVER SHEET**

**Proposal Submitted By:**

Contractor's Name

Contractor's Address

City

State

Zip Code

STATE OF ILLINOIS

Local Public Agency

County

Section Number

Route(s) (Street/Road Name)

Type of Funds

Proposal Only    Proposal and Plans    Proposal only, plans are separate

Submitted/Approved

**For Local Public Agency:**

**For a County and Road District Project**

Submitted/Approved

Highway Commissioner Signature

Date

Submitted/Approved

County Engineer/Superintendent of Highways

Date

**County Engineer  
on behalf of IDOT pursuant to  
Agreement of Understanding  
Dated August 7, 2012**

**For a Municipal Project**

Submitted/Approved/Passed

Signature

Date

Official Title

**Department of Transportation**

Released for bid based on limited review

Regional Engineer Signature

Date

Note: All proposal documents, including Proposal Guaranty Checks or Proposal Bid Bonds, should be stapled together to prevent loss when bids are processed.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
County of DuPage	DuPage	23-PVMKG-11-GM	2023 Pavement Marking Maintenance

### NOTICE TO BIDDERS

Sealed proposals for the project described below will be received at the office of the DuPage County Division of Transportation

<u>421 N. County Farm Road, 2nd Floor, Wheaton, IL 60187</u>	until	<u>2:00 PM</u>	on	<u>03-14-23</u>
Address		Time		Date

Sealed proposals will be opened and read publicly at the office of the DuPage County Division of Transportation

<u>421 N. County Farm Road, 2nd Floor, Wheaton, IL 60187</u>	at	<u>2:00 PM</u>	on	<u>03-14-23</u>
Address		Time		Date

### DESCRIPTION OF WORK

Location	Project Length
Various County Routes	

Proposed Improvement

Removal of existing pavement markings and installation of thermoplastic, urethane, and spray thermoplastic pavement markings, and recessed pavement markers.

1. Plans and proposal forms will be available in the office of

on line at <http://www.dupageco.org/dot/doingbusiness>  
or by contacting the Division of Transportation at (630) 407-6900.

2. ■ Prequalification  
If checked, the 2 apparent as read low bidders must file within 24 hours after the letting an "Affidavit of Availability" (Form BC 57) in triplicate, showing all uncompleted contracts awarded to them and all low bids pending award for Federal, State, County, Municipal and private work. One original shall be filed with the Awarding Authority and two originals with the IDOT District Office.
3. The Awarding Authority reserves the right to waive technicalities and to reject any or all proposals as provided in BLRS Special Provision for Bidding Requirements and Conditions for Contract Proposals.
4. The following Forms shall be returned by the bidder to the Awarding Authority:
  - a. Local Public Agency Formal Contract Proposal (BLR 12200)
  - b. Schedule of Prices (DuPage County version of BLR 12201)
  - c. Proposal Bid Bond (BLR 12230)
  - d. **DuPage County Apprenticeship or Training Program Certification (all Apprenticeship/Training Registration Number(s) and/or Certificate(s) need to be included with this form)**
  - e. Affidavit of Illinois Business Office (BLR 12326) (do not use for project with Federal funds)
  - f. **DuPage County - Required Vendor Ethics Disclosure Statement**
  - g. **IRS Form W-9: Request for Taxpayer Identification Number and Certification**
  - h. **Three (3) References Form**
  - i. **Joint Purchasing Authorization**
5. The quantities appearing in the bid schedule are approximate and are prepared for the comparison of bids. Payment to the Contractor will be made only for the actual quantities of work performed and accepted or materials furnished according to the contract. The scheduled quantities of work to be done and materials to be furnished may be increased, decreased or omitted as hereinafter provided.
6. Submission of a bid shall be conclusive assurance and warranty the bidder has examined the plans and understands all requirements for the performance of work. The bidder will be responsible for all errors in the proposal resulting from failure or neglect to conduct an in depth examination. The Awarding Authority will, in no case, be responsible for any costs, expenses, losses or changes in anticipated profits resulting from such failure or neglect of the bidder.
7. The bidder shall take no advantage of any error or omission in the proposal and advertised contract.
8. If a special envelope is supplied by the Awarding Authority, each proposal should be submitted in that envelope furnished by the Awarding Agency and the blank spaces on the envelope shall be filled in correctly to clearly indicate its contents. When an envelope other than the special one furnished by the Awarding Authority is used, it shall be marked to clearly indicate its contents. When sent by mail, the sealed proposal shall be addressed to the Awarding Authority at the address and in care of the official in whose office the bids are to be received. All proposals shall be filed prior to the time and at the place specified in the Notice to Bidders. Proposals received after the time specified will be returned to the bidder unopened.
9. Permission will be given to a bidder to withdraw a proposal if the bidder makes the request in writing or in person before the time for opening proposals.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
County of DuPage	DuPage	23-PVMKG-11-GM	2023 Pavement Marking Maintenance

**PROPOSAL**

1. Proposal of \_\_\_\_\_ Contractor's Name \_\_\_\_\_  
 \_\_\_\_\_ Contractor's Address \_\_\_\_\_
2. The plans for the proposed work are those prepared by DuPage County Division of Transportation and approved by the Department of Transportation on \_\_\_\_\_.
3. The specifications referred to herein are those prepared by the Department of Transportation and designated as "Standard Specifications for Road and Bridge Construction" and the " Supplemental Specifications and Recurring Special Provisions" thereto, adopted and in effect on the date of invitation for bids.
4. The undersigned agrees to accept, as part of the contract, the applicable Special Provisions indicated on the "Check Sheet for Recurring Special Provisions" contained in this proposal.
5. The undersigned agrees to complete the work within \_\_\_\_\_ working days or by 8/11/23\* & 11/30/23\*\* unless additional time is granted in accordance with the specifications.
6. The successful bidder at the time of execution of the contract will be required to deposit a contract bond for the full amount of the award. When a contract bond is not required, the proposal guaranty check will be held in lieu thereof. If this proposal is accepted and the undersigned fails to execute a contract and contract bond as required, it is hereby agreed that the Bid Bond of check shall be forfeited to the Awarding Authority.
7. Each pay item should have a unit price and a total price. If no total price is shown or if there is a discrepancy between the products of the unit price multiplied by the quantity, the unit price shall govern. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price. A bid may be declared unacceptable if neither a unit price nor a total price is shown.
8. The undersigned submits herewith the schedule of prices on BLR 12201 covering the work to be performed under this contract.
9. The undersigned further agrees that if awarded the contract for the sections contained in the combinations on BLR 12201, the work shall be in accordance with the requirements of each individual proposal for the multiple bid specified in the Schedule for Multiple Bids below.
10. A proposal guaranty in the proper amount, as specified in BLRS Special Provision for Bidding Requirements and Conditions for Contract Proposals, will be required. Bid Bonds will be allowed as a proposal guaranty. Accompanying this proposal is either a bid bond, if allowed, on Department form BLR 12230 or a proposal guaranty check, complying with the specifications, made payable to: County Treasurer of DuPage.  
 The amount of the check is \_\_\_\_\_ ( \_\_\_\_\_ ).

**Attach Cashier's Check or Certified Check Here**

In the event that one proposal guaranty check is intended to cover two or more bid proposals, the amount must be equal to the sum of the proposal guaranties which would be required for each individual bid proposal. If the proposal guaranty check is placed in another bid proposal, state below where it may be found.

The proposal guaranty check will be found in the bid proposal for: Section Number \_\_\_\_\_ .

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
County of DuPage	DuPage	23-PVMKG-11-GM	2023 Pavement Marking Maintenance

## CONTRACTOR CERTIFICATIONS

The certifications hereinafter made by the bidder are each a material representation of fact upon which reliance is placed should the Department enter into the contract with the bidder.

- Debt Delinquency.** The bidder or contractor or subcontractor, respectively, certifies that it is not delinquent in the payment of any tax administered by the Department of Revenue unless the individual or other entity is contesting, in accordance with the procedure established by the appropriate Revenue Act, its liability for the tax or the amount of the tax. Making a false statement voids the contract and allows the Department to recover all amounts paid to the individual or entity under the contract in a civil action.
- Bid-Rigging or Bid Rotating.** The bidder or contractor or subcontractor, respectively, certifies that it is not barred from contracting with the Department by reason of a violation of either 720 ILCS 5/33E-3 or 720 ILCS 5/33E-4.

A violation of section 33E-3 would be represented by a conviction of the crime of bid-rigging which, in addition to Class 3 felony sentencing, provides that any person convicted of this offense, or any similar offense of any state or the United States which contains the same elements as this offense shall be barred for 5 years from the date of conviction from contracting with any unit of State or local government. No corporation shall be barred from contracting with any unit of State or local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

A violation of Section 33E-4 would be represented by a conviction of the crime of bid-rotating which, in addition to Class 2 felony sentencing, provides that any person convicted of this offense or any similar offense of any state or the United States which contains the same elements as this offense shall be permanently barred from contracting with any unit of State of Local government. No corporation shall be barred from contracting with any unit of State or Local government as a result of a conviction under this Section of any employee or agent of such corporation if the employee so convicted is no longer employed by the corporation and: (1) it has been finally adjudicated not guilty or (2) if it demonstrates to the governmental entity with which it seeks to contract and that entity finds that the commission of the offense was neither authorized, requested, commanded, nor performed by a director, officer or a high managerial agent on behalf of the corporation.

- Bribery.** The bidder or contractor or subcontractor, respectively, certifies that, it has not been convicted of bribery or attempting to bribe an officer or employee of the State of Illinois or any unit of local government, nor has the firm made an admission of guilt of such conduct which is a matter or record, nor has an official, agent, or employee of the firm committed bribery or attempted bribery on behalf of the firm and pursuant to the direction or authorization of a responsible official of the firm.
- Interim Suspension or Suspension.** The bidder or contractor or subcontractor, respectively, certifies that it is not currently under a suspension as defined in Subpart I of Title 44 Subtitle A Chapter III Part 6 of the Illinois Administrative code. Furthermore, if suspended prior to completion of this work, the contract or contracts executed for the completion of this work may be canceled.

Local Public Agency	County	Section Number	Route(s) (Street/Road Name)
County of DuPage	DuPage	23-PVMKG-11-GM	2023 Pavement Marking Maintenance

**SIGNATURES**

(If an individual)

Signature of Bidder	Date	
<input type="text"/>	<input type="text"/>	
Business Address		
<input type="text"/>		
City	State	Zip Code
<input type="text"/>	<input type="text"/>	<input type="text"/>

(If a partnership)

Firm Name		
<input type="text"/>		
Signature	Date	
<input type="text"/>	<input type="text"/>	
Title		
<input type="text"/>		
Business Address		
<input type="text"/>		
City	State	Zip Code
<input type="text"/>	<input type="text"/>	<input type="text"/>

Insert the Names and Addresses of all Partners

<input type="text"/>
----------------------

(If a corporation)

Corporate Name		
<input type="text"/>		
Signature	Date	
<input type="text"/>	<input type="text"/>	
Title		
<input type="text"/>		
Business Address		
<input type="text"/>		
City	State	Zip Code
<input type="text"/>	<input type="text"/>	<input type="text"/>

Insert Names of Officers

President
<input type="text"/>

Attest:

Secretary

Secretary

Treasurer

**RETURN WITH BID**



**SCHEDULE OF PRICES  
(TOTAL BID: BASE BID PLUS ALL ALTERNATIVES)**

Contractor's Name:

Local Public Agency: County of DuPage

County: DuPage

Section: 23-PVMKG-11-GM

Route: 2023 Pavement Marking  
Maintenance

**Schedule for Multiple Bids**

Combination Letter	Sections included in Combinations	Total

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	19100		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18100		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	63100		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	16700		
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	35100		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	7000		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	650000		
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	7800		
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	28100		
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	14700		
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	2340		
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	960		
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	650		
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	4200		
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	136100		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	500		

**RETURN WITH BID**

17	REPLACEMENT REFLECTOR	EACH	500		
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT	800		
Bidder's Proposal for making entire improvements (Base + All Alternatives)					

1. Each pay item should have a unit price and a total price.
2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.
3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.
4. A bid may be declared unacceptable if neither a unit price or total price is shown.



**RETURN WITH BID**

**SCHEDULE OF PRICES  
(BASE BID)**

Contractor's Name:

Local Public Agency: County of DuPage

County: DuPage

Section: 23-PVMKG-11-GM

Route: 2023 Pavement Marking  
Maintenance

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	14183		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12308		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	48648		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	16346		
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	26884		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	5174		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	396488		
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	718		
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19476		
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	3442		
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	54		
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	440		
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	180		
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	3687		
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	92603		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	500		
17	REPLACEMENT REFLECTOR	EACH	500		
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT	800		
Bidder's Proposal for making entire improvements (Base Bid only)					

**RETURN WITH BID**

**SCHEDULE OF PRICES  
(ALT. A)**

Contractor's Name:   
 Local Public Agency: County of DuPage  
 County: DuPage  
 Section: 23-PVMKG-11-GM  
 Route: 2023 Pavement Marking  
Maintenance

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	525		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	699		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2066		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	904		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	109160		
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2506		
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	4418		
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	2074		
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	664		
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	270		
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	355		
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	122		
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	9342		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH			
17	REPLACEMENT REFLECTOR	EACH			
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT			
Bidder's Proposal for making entire improvements (Alt. A)					

**RETURN WITH BID**

**SCHEDULE OF PRICES  
(ALT. B)**

Contractor's Name:

Local Public Agency: County of DuPage

County: DuPage

Section: 23-PVMKG-11-GM

Route: 2023 Pavement Marking  
Maintenance

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	832		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	705		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2914		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	250		
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1849		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	188		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	104700		
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255		
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2051		
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	5271		
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT			
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT			
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT			
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	178		
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	8222		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH			
17	REPLACEMENT REFLECTOR	EACH			
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT			
Bidder's Proposal for making entire improvements (Alt. B)					

**RETURN WITH BID**

**SCHEDULE OF PRICES  
(ALT. C)**

Contractor's Name:   
 Local Public Agency: County of DuPage  
 County: DuPage  
 Section: 23-PVMKG-11-GM  
 Route: 2023 Pavement Marking  
Maintenance

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	801		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1306		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1098		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	199		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	39652		
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT			
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT			
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT			
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT			
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT			
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT			
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT			
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	2440		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH			
17	REPLACEMENT REFLECTOR	EACH			
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT			
Bidder's Proposal for making entire improvements (Alt. C)					

**RETURN WITH BID**

**SCHEDULE OF PRICES  
(ALT. D)**

Contractor's Name:

Local Public Agency: County of DuPage

County: DuPage

Section: 2023 Pavement Marking

Route: Maintenance

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Item No.	Items	Unit	Quantity	Unit Price	Total
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3269		
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3587		
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8166		
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	104		
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4365		
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1334		
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT			
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4321		
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2155		
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	3913		
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1622		
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	250		
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	115		
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	213		
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	23493		
16	RECESSED REFLECTIVE PAVEMENT MARKER	EACH			
17	REPLACEMENT REFLECTOR	EACH			
18	TEMPORARY PAVEMENT MARKING REMOVAL	FOOT			
Bidder's Proposal for making entire improvements (Alt. D)					

**RETURN WITH BID**

**SCHEDULE OF PRICES  
(BID SUMMARY)**

Contractor's Name:   
Local Public Agency: County of DuPage  
County: DuPage  
Section: 23-PVMKG-11-GM  
Route: 2023 Pavement Marking  
Maintenance

**BID SUMMARY**

BASE BID TOTAL	
ALT. A TOTAL	
BASE BID + ALT. A	
ALT. B TOTAL	
BASE BID + ALT. A + ALT. B	
ALT. C TOTAL	
BASE BID + ALT. A + ALT. B + ALT. C	
ALT. D TOTAL	
BASE BID + ALT. A + ALT. B + ALT. C + ALT. D	



Local Public Agency Proposal Bid Bond



Local Public Agency	County	Section Number
County of DuPage	DuPage	23-PVMKG-11-GM

WE, \_\_\_\_\_ as PRINCIPAL, and \_\_\_\_\_ as SURETY, are held jointly, severally and firmly bound unto the above Local Public Agency (hereafter referred to as "LPA") in the penal sum of 5% of the total bid price, or for the amount specified in the proposal documents in effect on the date of invitation for bids, whichever is the lesser sum. We bind ourselves, our heirs, executors, administrators, successors, and assigns, jointly pay to the LPA this sum under the conditions of this instrument.

WHEREAS THE CONDITION OF THE FOREGOING OBLIGATION IS SUCH that, the said PRINCIPAL is submitting a written proposal to the LPA acting through its awarding authority for the construction of the work designated as the above section.

THEREFORE if the proposal is accepted and a contract awarded to the PRINCIPAL by the LPA for the above designated section and the PRINCIPAL shall within fifteen (15) days after award enter into a formal contract, furnish surety guaranteeing the faithful performance of the work, and furnish evidence of the required insurance coverage, all as provided in the "Standard Specifications for Road and Bridge Construction" and applicable Supplemental Specifications, then this obligation shall become void; otherwise it shall remain in full force and effect.

IN THE EVENT the LPA determines the PRINCIPAL has failed to enter into a formal contract in compliance with any requirements set forth in the preceding paragraph, then the LPA acting through its awarding authority shall immediately be entitled to recover the full penal sum set out above, together with all court costs, all attorney fees, and any other expense of recovery.

IN TESTIMONY WHEREOF, the said PRINCIPAL and the said SURETY have caused this instrument to be signed by their respective officers this \_\_\_\_\_ of \_\_\_\_\_ Day Month and Year

Principal

Company Name

Signature  Date

By:

Title

Company Name

Signature  Date

By:

Title

(If Principal is a joint venture of two or more contractors, the company names, and authorized signatures of each contractor must be affixed.)

Surety

Name of Surety

Signature of Attorney-in-Fact  Date

By:

STATE OF IL  
 COUNTY OF

I \_\_\_\_\_, a Notary Public in and for said county do hereby certify that

(Insert names of individuals signing on behalf of PRINCIPAL & SURETY)

who are each personally known to me to be the same persons whose names are subscribed to the foregoing instrument on behalf of PRINCIPAL and SURETY, appeared before me this day in person and acknowledged respectively, that they signed and delivered said instruments as their free and voluntary act for the uses and purposes therein set forth.

Given under my hand and notarial seal this \_\_\_\_\_ day of \_\_\_\_\_ Month and Year.

(SEAL)

Notary Public Signature

Date commission expires \_\_\_\_\_

Local Public Agency

County

Section Number

County of DuPage

DuPage

23-PVMKG-11-GM

ELECTRONIC BID BOND

**Electronic bid bond is allowed (box must be checked by LPA if electronic bid bond is allowed)**

The Principal may submit an electronic bid bond, in lieu of completing the above section of the Proposal Bid Bond Form. By providing an electronic bid bond ID code and signing below, the Principal is ensuring the identified electronic bid bond has been executed and the Principal and Surety are firmly bound unto the LPA under the conditions of the bid bond as shown above. (If PRINCIPAL is a joint venture of two or more contractors, an electronic bid bond ID code, company/Bidder name title and date must be affixed for each contractor in the venture.)

Electronic Bid Bond ID Code

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

Company/Bidder Name

--

Signature

--

Date

--

Title

--





# Apprenticeship and Training Program Certification

RETURN WITH BID

Local Public Agency	County	Street Name/Road Name	Section Number
County of DuPage	DuPage	Various County Routes	23-PVMKG-11-GM

**All contractors are required to complete the following certification**

- For this contract proposal or for all bidding groups in this deliver and install proposal.
- For the following deliver and install bidding groups in this material proposal.

The County of DuPage policy, adopted in accordance with DuPage County, Illinois County Code, requires this contract to be awarded to the lowest responsive and responsible bidder. The award decision is subject to approval by the Department. In addition to all other responsibility factors, this contract or deliver and install proposal requires all bidders and all bidder's subcontractors to disclose participation in apprenticeship or training programs that are (1) approved by and registered with the United States Department of Labor's Bureau of Apprenticeship and Training, and (2) applicable to the work of the above indicated proposals or groups. Therefore, all bidders are required to complete the following certification:

1. Except as provided in paragraph 4 below, the undersigned bidder certifies that it is a participant, either as an individual or as part of a group program, in an approved apprenticeship or training program applicable to each type of work or craft that the bidder will perform with its own employees.
2. The undersigned bidder further certifies, for work to be performed by subcontract, that each of its subcontractors either (A) is, at the time of such bid, participating in an approved, applicable apprenticeship or training program; or (B) will, prior to commencement of performance of work pursuant to this contract, establish participation in an approved apprenticeship or training program applicable to the work of the subcontract.
3. The undersigned bidder, by inclusion in the list in the space below, certifies the official name of each program sponsor holding the Certificate of Registration for all of the types of work or crafts in which the bidder is a participant and that will be performed with the bidder's employees. Types of work or craft that will be subcontracted shall be included and listed as subcontract work.

4. Except for any work identified above, if any bidder or subcontractor shall perform all or part of the work of the contract or deliver and install proposal solely by individual owners, partners or members and not by employees to whom the payment of prevailing rates of wages would be required, check the following box, and identify the owner/operator workforces and positions of ownership.

The requirements of this certification and disclosure are a material part of the contract, and the contractor shall require this certification provision to be included in all approved subcontracts. The bidder is responsible for making a complete report and shall make certain that each type of work or craft job category that will be utilized on the project is accounted for and listed. The Department at any time before or afterward may require the production of a copy of each applicable Certificate of Registration issued by the United States Department of Labor evidencing such participation by the contractor and any or all of its subcontractors. In order to fulfill the participation requirement, it shall not be necessary that any applicable program sponsor be currently taking or that it will take applications for apprenticeship, training or employment during the performance of the work of this contract or deliver and install proposal.

Bidder	Signature	Date	
<div style="border: 1px solid black; height: 20px;"></div>	<div style="border: 1px solid black; height: 40px;"></div>	<div style="border: 1px solid black; height: 40px;"></div>	
Title			
<div style="border: 1px solid black; height: 20px;"></div>			
Address	City	State	Zip Code
<div style="border: 1px solid black; height: 20px;"></div>	<div style="border: 1px solid black; height: 20px;"></div>	<div style="border: 1px solid black; height: 20px;"></div>	<div style="border: 1px solid black; height: 20px;"></div>



Affidavit of Illinois Business Office



Local Public Agency	County	Street Name/Road Name	Section Number
County of DuPage	DuPage	2023 Pavement Marking Maintenance	23-PVMKG-11-GM

I, \_\_\_\_\_ of \_\_\_\_\_, \_\_\_\_\_,  
Name of Affiant City of Affiant State of Affiant

being first duly sworn upon oath, state as follows:

1. That I am the \_\_\_\_\_ of \_\_\_\_\_.  
Officer or Position Bidder
2. That I have personal knowledge of the facts herein stated.
3. That, if selected under the proposal described above, \_\_\_\_\_, will maintain a business office in the  
Bidder  
 State of Illinois, which will be located in \_\_\_\_\_ County, Illinois.  
County
4. That this business office will serve as the primary place of employment for any persons employed in the construction contemplated by this proposal.
5. That this Affidavit is given as a requirement of state law as provided in Section 30-22(8) of the Illinois Procurement Code.

Signature	Date
Print Name of Affiant	

**Notary Public**

State of IL

County \_\_\_\_\_

Signed (or subscribed or attested) before me on \_\_\_\_\_ by  
(date)

\_\_\_\_\_, authorized agent(s) of  
(name/s of person/s)

\_\_\_\_\_  
Bidder

Signature of Notary Public

(SEAL)

My commission expires \_\_\_\_\_



Bureau of Construction  
2300 South Dirksen Parkway/Room 322  
Springfield, IL 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

**Part I. Work Under Contract**

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

**Part II. Awards Pending and Uncompleted Work to be done with your own forces.**

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

Earthwork						
Portland Cement Concrete Paving						
HMA Plant Mix						
HMA Paving						
Clean & Seal Cracks/Joints						
Aggregate Bases, Surfaces						
Highway, R.R., Waterway Struc.						
Drainage						
Electrical						
Cover and Seal Coats						
Concrete Construction						
Landscaping						
Fencing						
Guardrail						
Painting						
Signing						
Cold Milling, Planning, Rotomilling						
Demolition						
Pavement Markings (Paint)						
Other Construction (List)						
Totals						

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

**Part III. Work Subcontracted to Others.**

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
<b>Total Uncompleted</b>					

**Notary**

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director

Title

Signature

Date

Company

Address

City

State

Zip Code

Subscribed and sworn to before me

this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_

\_\_\_\_\_  
(Signature of Notary Public)

My commission expires \_\_\_\_\_

(Notary Seal)

Add pages for additional contracts



**Affidavit of Availability**  
For the Letting of 03/14/23

Bureau of Construction  
2300 South Dirksen Parkway/Room 322  
Springfield, IL 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

**Part I. Work Under Contract**

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

**Part II. Awards Pending and Uncompleted Work to be done with your own forces.**

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

Earthwork						
Portland Cement Concrete Paving						
HMA Plant Mix						
HMA Paving						
Clean & Seal Cracks/Joints						
Aggregate Bases, Surfaces						
Highway, R.R., Waterway Struc.						
Drainage						
Electrical						
Cover and Seal Coats						
Concrete Construction						
Landscaping						
Fencing						
Guardrail						
Painting						
Signing						
Cold Milling, Planning, Rotomilling						
Demolition						
Pavement Markings (Paint)						
Other Construction (List)						
Totals						

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

**Part III. Work Subcontracted to Others.**

For each contract described in Part I, list all the work you have subcontracted to others.

	2	3	4	Awards Pending	1
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Total Uncompleted					

**Notary**

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director

Title

Signature

Date

Company

Address

City

State

Zip Code

Subscribed and sworn to before me  
this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_

\_\_\_\_\_  
(Signature of Notary Public)

My commission expires \_\_\_\_\_

(Notary Seal)

Add pages for additional contracts



**Affidavit of Availability**

For the Letting of 03/14/23

Bureau of Construction  
2300 South Dirksen Parkway/Room 322  
Springfield, IL 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

**Part I. Work Under Contract**

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

**Part II. Awards Pending and Uncompleted Work to be done with your own forces.**

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

Earthwork						
Portland Cement Concrete Paving						
HMA Plant Mix						
HMA Paving						
Clean & Seal Cracks/Joints						
Aggregate Bases, Surfaces						
Highway, R.R., Waterway Struc.						
Drainage						
Electrical						
Cover and Seal Coats						
Concrete Construction						
Landscaping						
Fencing						
Guardrail						
Painting						
Signing						
Cold Milling, Planning, Rotomilling						
Demolition						
Pavement Markings (Paint)						
Other Construction (List)						
Totals						

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

**Part III. Work Subcontracted to Others.**

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
<b>Total Uncompleted</b>					

**Notary**

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director

Title

Signature

Date

Company

Address

City

State

Zip Code

Subscribed and sworn to before me

this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_

\_\_\_\_\_  
(Signature of Notary Public)

My commission expires \_\_\_\_\_

(Notary Seal)

Add pages for additional contracts





Bureau of Construction  
2300 South Dirksen Parkway/Room 322  
Springfield, IL 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

**Part I. Work Under Contract**

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

**Part II. Awards Pending and Uncompleted Work to be done with your own forces.**

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

Earthwork						
Portland Cement Concrete Paving						
HMA Plant Mix						
HMA Paving						
Clean & Seal Cracks/Joints						
Aggregate Bases, Surfaces						
Highway, R.R., Waterway Struc.						
Drainage						
Electrical						
Cover and Seal Coats						
Concrete Construction						
Landscaping						
Fencing						
Guardrail						
Painting						
Signing						
Cold Milling, Planning, Rotomilling						
Demolition						
Pavement Markings (Paint)						
Other Construction (List)						
Totals						

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

**Part III. Work Subcontracted to Others.**

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Total Uncompleted					

**Notary**

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director

Title

Signature

Date

Company

Address

City

State

Zip Code

Subscribed and sworn to before me

this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_

\_\_\_\_\_  
(Signature of Notary Public)

My commission expires \_\_\_\_\_

(Notary Seal)

Add pages for additional contracts



**Affidavit of Availability**  
For the Letting of 03/14/23

Bureau of Construction  
2300 South Dirksen Parkway/Room 322  
Springfield, IL 62764

Instructions: Complete this form by either typing or using black ink. "Authorization to Bid" will not be issued unless both sides of this form are completed in detail. Use additional forms as needed to list all work.

**Part I. Work Under Contract**

List below all work you have under contract as either a prime contractor or a subcontractor. It is required to include all pending low bids not yet awarded or rejected. In a joint venture, list only that portion of the work which is the responsibility of your company. The uncompleted dollar value is to be based upon the most recent engineer's or owners estimate, and must include work subcontracted to others. If no work is contracted, show NONE.

	1	2	3	4	Awards Pending	Accumulated Totals
Contract Number						
Contract With						
Estimated Completion Date						
Total Contract Price						
Uncompleted Dollar Value if Firm is the Prime Contractor						
Uncompleted Dollar Value if Firm is the Subcontractor						
Total Value of All Work						

**Part II. Awards Pending and Uncompleted Work to be done with your own forces.**

List below the uncompleted dollar value of work for each contract and awards pending to be completed with your own forces. All work subcontracted to others will be listed on the reverse of this form. In a joint venture, list only that portion of the work to be done by your company. If no work is contracted, show NONE.

Earthwork						
Portland Cement Concrete Paving						
HMA Plant Mix						
HMA Paving						
Clean & Seal Cracks/Joints						
Aggregate Bases, Surfaces						
Highway, R.R., Waterway Struc.						
Drainage						
Electrical						
Cover and Seal Coats						
Concrete Construction						
Landscaping						
Fencing						
Guardrail						
Painting						
Signing						
Cold Milling, Planning, Rotomilling						
Demolition						
Pavement Markings (Paint)						
Other Construction (List)						
Totals						

Disclosure of this information is REQUIRED to accomplish the statutory purpose as outlined in the "Illinois Procurement Code." Failure to comply will result in non-issuance of an "Authorization To Bid." This form has been approved by the State Forms Management Center.

**Part III. Work Subcontracted to Others.**

For each contract described in Part I, list all the work you have subcontracted to others.

	1	2	3	4	Awards Pending
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Subcontractor					
Type of Work					
Subcontract Price					
Amount Uncompleted					
Total Uncompleted					

**Notary**

I, being duly sworn, do hereby declare this affidavit is a true and correct statement relating to ALL uncompleted contracts of the undersigned for Federal, State, County, City and private work, including ALL subcontract work, ALL pending low bids not yet awarded or rejected and ALL estimated completion dates.

Officer or Director

Title

Signature

Date

Company

Address

City

State

Zip Code

Subscribed and sworn to before me

this \_\_\_\_\_ day of \_\_\_\_\_, \_\_\_\_\_

\_\_\_\_\_  
(Signature of Notary Public)

My commission expires \_\_\_\_\_

(Notary Seal)



# Required Vendor Ethics Disclosure Statement

Failure to complete and return this form may result in delay or cancellation of the County's Contractual Obligation.

Date: \_\_\_\_\_

Bid/Contract/PO #: 23-PVMKG-11-GM

Company Name:	Company Contact:
Contact Phone:	Contact Email:

### The DuPage County Procurement Ordinance requires the following written disclosures prior to award:

1. Every contractor, union, or vendor that is seeking or has previously obtained a contract, change orders to one (1) or more contracts, or two (2) or more individual contracts with the county resulting in an aggregate amount at or in excess of \$25,000, shall provide to Procurement Services Division a written disclosure of all political campaign contributions made by such contractor, union, or vendor within the current and previous calendar year to any incumbent county board member, county board chairman, or countywide elected official whose office the contract to be awarded will benefit. The contractor, union or vendor shall update such disclosure annually during the term of a multi-year contract and prior to any change order or renewal requiring approval by the county board. For purposes of this disclosure requirement, "contractor or vendor" includes owners, officers, managers, lobbyists, agents, consultants, bond counsel and underwriters counsel, subcontractors and corporate entities under the control of the contracting person, and political action committees to which the contracting person has made contributions.

**NONE (check here) - If no contributions have been made**

Recipient	Donor	Description (e.g. cash, type of item, in-kind services, etc.)	Amount/Value	Date Made

2. All contractors and vendors who have obtained or are seeking contracts with the county shall disclose the names and contact information of their lobbyists, agents and representatives and all individuals who are or will be having contact with county officers or employees in relation to the contractor bid and shall update such disclosure with any changes that may occur.

**NONE (check here) - If no contacts have been made**

Lobbyists, Agents and Representatives and all individuals who are or will be having contact with county officers or employees in relation to the contract or bid	Telephone	Email

A contractor or vendor that knowingly violates these disclosure requirements is subject to penalties which may include, but are not limited to, the immediate cancellation of the contract and possible disbarment from future county contracts.

### Continuing disclosure is required, and I agree to update this disclosure form as follows:

- If information changes, within five (5) days of change, or prior to county action, whichever is sooner
- 30 days prior to the optional renewal of any contract
- Annual disclosure for multi-year contracts on the anniversary of said contract
- With any request for change order except those issued by the county for administrative adjustments

### The full text for the county's ethics and procurement policies and ordinances are available at:

<http://www.dupageco.org/CountyBoard/Policies/>

**I hereby acknowledge that I have received, have read, and understand these requirements.**

Authorized Signature

\_\_\_\_\_

Printed Name

\_\_\_\_\_

Title

\_\_\_\_\_

Date

\_\_\_\_\_

**Attach additional sheets if necessary. Sign each sheet and number each page. Page \_\_\_\_\_ of \_\_\_\_\_ (total number of pages)**

# Request for Taxpayer Identification Number and Certification

Give Form to the  
requester. Do not  
send to the IRS.

► Go to [www.irs.gov/FormW9](http://www.irs.gov/FormW9) for instructions and the latest information.

Print or type.  
See Specific Instructions on page 3.

1 Name (as shown on your income tax return). Name is required on this line; do not leave this line blank.	
2 Business name/disregarded entity name, if different from above	
3 Check appropriate box for federal tax classification of the person whose name is entered on line 1. Check only <b>one</b> of the following seven boxes. <input type="checkbox"/> Individual/sole proprietor or single-member LLC <input type="checkbox"/> Limited liability company. Enter the tax classification (C=C corporation, S=S corporation, P=Partnership) ► _____ <b>Note:</b> Check the appropriate box in the line above for the tax classification of the single-member owner. Do not check LLC if the LLC is classified as a single-member LLC that is disregarded from the owner unless the owner of the LLC is another LLC that is <b>not</b> disregarded from the owner for U.S. federal tax purposes. Otherwise, a single-member LLC that is disregarded from the owner should check the appropriate box for the tax classification of its owner. <input type="checkbox"/> Other (see instructions) ► _____	4 Exemptions (codes apply only to certain entities, not individuals; see instructions on page 3): Exempt payee code (if any) _____ Exemption from FATCA reporting code (if any) _____ <small>(Applies to accounts maintained outside the U.S.)</small>
5 Address (number, street, and apt. or suite no.) See instructions.	Requester's name and address (optional)
6 City, state, and ZIP code	
7 List account number(s) here (optional)	

## Part I Taxpayer Identification Number (TIN)

Enter your TIN in the appropriate box. The TIN provided must match the name given on line 1 to avoid backup withholding. For individuals, this is generally your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the instructions for Part I, later. For other entities, it is your employer identification number (EIN). If you do not have a number, see *How to get a TIN*, later.

**Note:** If the account is in more than one name, see the instructions for line 1. Also see *What Name and Number To Give the Requester* for guidelines on whose number to enter.

<b>Social security number</b>											
				-			-				
<b>or</b>											
<b>Employer identification number</b>											
					-						

## Part II Certification

Under penalties of perjury, I certify that:

1. The number shown on this form is my correct taxpayer identification number (or I am waiting for a number to be issued to me); and
2. I am not subject to backup withholding because: (a) I am exempt from backup withholding, or (b) I have not been notified by the Internal Revenue Service (IRS) that I am subject to backup withholding as a result of a failure to report all interest or dividends, or (c) the IRS has notified me that I am no longer subject to backup withholding; and
3. I am a U.S. citizen or other U.S. person (defined below); and
4. The FATCA code(s) entered on this form (if any) indicating that I am exempt from FATCA reporting is correct.

**Certification instructions.** You must cross out item 2 above if you have been notified by the IRS that you are currently subject to backup withholding because you have failed to report all interest and dividends on your tax return. For real estate transactions, item 2 does not apply. For mortgage interest paid, acquisition or abandonment of secured property, cancellation of debt, contributions to an individual retirement arrangement (IRA), and generally, payments other than interest and dividends, you are not required to sign the certification, but you must provide your correct TIN. See the instructions for Part II, later.

<b>Sign Here</b>	Signature of U.S. person ►	Date ►

## General Instructions

Section references are to the Internal Revenue Code unless otherwise noted.

**Future developments.** For the latest information about developments related to Form W-9 and its instructions, such as legislation enacted after they were published, go to [www.irs.gov/FormW9](http://www.irs.gov/FormW9).

## Purpose of Form

An individual or entity (Form W-9 requester) who is required to file an information return with the IRS must obtain your correct taxpayer identification number (TIN) which may be your social security number (SSN), individual taxpayer identification number (ITIN), adoption taxpayer identification number (ATIN), or employer identification number (EIN), to report on an information return the amount paid to you, or other amount reportable on an information return. Examples of information returns include, but are not limited to, the following.

- Form 1099-INT (interest earned or paid)

- Form 1099-DIV (dividends, including those from stocks or mutual funds)
- Form 1099-MISC (various types of income, prizes, awards, or gross proceeds)
- Form 1099-B (stock or mutual fund sales and certain other transactions by brokers)
- Form 1099-S (proceeds from real estate transactions)
- Form 1099-K (merchant card and third party network transactions)
- Form 1098 (home mortgage interest), 1098-E (student loan interest), 1098-T (tuition)
- Form 1099-C (canceled debt)
- Form 1099-A (acquisition or abandonment of secured property)

Use Form W-9 only if you are a U.S. person (including a resident alien), to provide your correct TIN.

*If you do not return Form W-9 to the requester with a TIN, you might be subject to backup withholding. See What is backup withholding, later.*

By signing the filled-out form, you:

1. Certify that the TIN you are giving is correct (or you are waiting for a number to be issued),
2. Certify that you are not subject to backup withholding, or
3. Claim exemption from backup withholding if you are a U.S. exempt payee. If applicable, you are also certifying that as a U.S. person, your allocable share of any partnership income from a U.S. trade or business is not subject to the withholding tax on foreign partners' share of effectively connected income, and
4. Certify that FATCA code(s) entered on this form (if any) indicating that you are exempt from the FATCA reporting, is correct. See *What is FATCA reporting*, later, for further information.

**Note:** If you are a U.S. person and a requester gives you a form other than Form W-9 to request your TIN, you must use the requester's form if it is substantially similar to this Form W-9.

**Definition of a U.S. person.** For federal tax purposes, you are considered a U.S. person if you are:

- An individual who is a U.S. citizen or U.S. resident alien;
- A partnership, corporation, company, or association created or organized in the United States or under the laws of the United States;
- An estate (other than a foreign estate); or
- A domestic trust (as defined in Regulations section 301.7701-7).

**Special rules for partnerships.** Partnerships that conduct a trade or business in the United States are generally required to pay a withholding tax under section 1446 on any foreign partners' share of effectively connected taxable income from such business. Further, in certain cases where a Form W-9 has not been received, the rules under section 1446 require a partnership to presume that a partner is a foreign person, and pay the section 1446 withholding tax. Therefore, if you are a U.S. person that is a partner in a partnership conducting a trade or business in the United States, provide Form W-9 to the partnership to establish your U.S. status and avoid section 1446 withholding on your share of partnership income.

In the cases below, the following person must give Form W-9 to the partnership for purposes of establishing its U.S. status and avoiding withholding on its allocable share of net income from the partnership conducting a trade or business in the United States.

- In the case of a disregarded entity with a U.S. owner, the U.S. owner of the disregarded entity and not the entity;
- In the case of a grantor trust with a U.S. grantor or other U.S. owner, generally, the U.S. grantor or other U.S. owner of the grantor trust and not the trust; and
- In the case of a U.S. trust (other than a grantor trust), the U.S. trust (other than a grantor trust) and not the beneficiaries of the trust.

**Foreign person.** If you are a foreign person or the U.S. branch of a foreign bank that has elected to be treated as a U.S. person, do not use Form W-9. Instead, use the appropriate Form W-8 or Form 8233 (see Pub. 515, *Withholding of Tax on Nonresident Aliens and Foreign Entities*).

**Nonresident alien who becomes a resident alien.** Generally, only a nonresident alien individual may use the terms of a tax treaty to reduce or eliminate U.S. tax on certain types of income. However, most tax treaties contain a provision known as a "saving clause." Exceptions specified in the saving clause may permit an exemption from tax to continue for certain types of income even after the payee has otherwise become a U.S. resident alien for tax purposes.

If you are a U.S. resident alien who is relying on an exception contained in the saving clause of a tax treaty to claim an exemption from U.S. tax on certain types of income, you must attach a statement to Form W-9 that specifies the following five items.

1. The treaty country. Generally, this must be the same treaty under which you claimed exemption from tax as a nonresident alien.
2. The treaty article addressing the income.
3. The article number (or location) in the tax treaty that contains the saving clause and its exceptions.
4. The type and amount of income that qualifies for the exemption from tax.
5. Sufficient facts to justify the exemption from tax under the terms of the treaty article.

**Example.** Article 20 of the U.S.-China income tax treaty allows an exemption from tax for scholarship income received by a Chinese student temporarily present in the United States. Under U.S. law, this student will become a resident alien for tax purposes if his or her stay in the United States exceeds 5 calendar years. However, paragraph 2 of the first Protocol to the U.S.-China treaty (dated April 30, 1984) allows the provisions of Article 20 to continue to apply even after the Chinese student becomes a resident alien of the United States. A Chinese student who qualifies for this exception (under paragraph 2 of the first protocol) and is relying on this exception to claim an exemption from tax on his or her scholarship or fellowship income would attach to Form W-9 a statement that includes the information described above to support that exemption.

If you are a nonresident alien or a foreign entity, give the requester the appropriate completed Form W-8 or Form 8233.

## Backup Withholding

**What is backup withholding?** Persons making certain payments to you must under certain conditions withhold and pay to the IRS 24% of such payments. This is called "backup withholding." Payments that may be subject to backup withholding include interest, tax-exempt interest, dividends, broker and barter exchange transactions, rents, royalties, nonemployee pay, payments made in settlement of payment card and third party network transactions, and certain payments from fishing boat operators. Real estate transactions are not subject to backup withholding.

You will not be subject to backup withholding on payments you receive if you give the requester your correct TIN, make the proper certifications, and report all your taxable interest and dividends on your tax return.

**Payments you receive will be subject to backup withholding if:**

1. You do not furnish your TIN to the requester,
2. You do not certify your TIN when required (see the instructions for Part II for details),
3. The IRS tells the requester that you furnished an incorrect TIN,
4. The IRS tells you that you are subject to backup withholding because you did not report all your interest and dividends on your tax return (for reportable interest and dividends only), or
5. You do not certify to the requester that you are not subject to backup withholding under 4 above (for reportable interest and dividend accounts opened after 1983 only).

Certain payees and payments are exempt from backup withholding. See *Exempt payee code*, later, and the separate Instructions for the Requester of Form W-9 for more information.

Also see *Special rules for partnerships*, earlier.

## What is FATCA Reporting?

The Foreign Account Tax Compliance Act (FATCA) requires a participating foreign financial institution to report all United States account holders that are specified United States persons. Certain payees are exempt from FATCA reporting. See *Exemption from FATCA reporting code*, later, and the Instructions for the Requester of Form W-9 for more information.

## Updating Your Information

You must provide updated information to any person to whom you claimed to be an exempt payee if you are no longer an exempt payee and anticipate receiving reportable payments in the future from this person. For example, you may need to provide updated information if you are a C corporation that elects to be an S corporation, or if you no longer are tax exempt. In addition, you must furnish a new Form W-9 if the name or TIN changes for the account; for example, if the grantor of a grantor trust dies.

## Penalties

**Failure to furnish TIN.** If you fail to furnish your correct TIN to a requester, you are subject to a penalty of \$50 for each such failure unless your failure is due to reasonable cause and not to willful neglect.

**Civil penalty for false information with respect to withholding.** If you make a false statement with no reasonable basis that results in no backup withholding, you are subject to a \$500 penalty.

**Criminal penalty for falsifying information.** Willfully falsifying certifications or affirmations may subject you to criminal penalties including fines and/or imprisonment.

**Misuse of TINs.** If the requester discloses or uses TINs in violation of federal law, the requester may be subject to civil and criminal penalties.

## Specific Instructions

### Line 1

You must enter one of the following on this line; **do not** leave this line blank. The name should match the name on your tax return.

If this Form W-9 is for a joint account (other than an account maintained by a foreign financial institution (FFI)), list first, and then circle, the name of the person or entity whose number you entered in Part I of Form W-9. If you are providing Form W-9 to an FFI to document a joint account, each holder of the account that is a U.S. person must provide a Form W-9.

a. **Individual.** Generally, enter the name shown on your tax return. If you have changed your last name without informing the Social Security Administration (SSA) of the name change, enter your first name, the last name as shown on your social security card, and your new last name.

**Note: ITIN applicant:** Enter your individual name as it was entered on your Form W-7 application, line 1a. This should also be the same as the name you entered on the Form 1040/1040A/1040EZ you filed with your application.

b. **Sole proprietor or single-member LLC.** Enter your individual name as shown on your 1040/1040A/1040EZ on line 1. You may enter your business, trade, or “doing business as” (DBA) name on line 2.

c. **Partnership, LLC that is not a single-member LLC, C corporation, or S corporation.** Enter the entity’s name as shown on the entity’s tax return on line 1 and any business, trade, or DBA name on line 2.

d. **Other entities.** Enter your name as shown on required U.S. federal tax documents on line 1. This name should match the name shown on the charter or other legal document creating the entity. You may enter any business, trade, or DBA name on line 2.

e. **Disregarded entity.** For U.S. federal tax purposes, an entity that is disregarded as an entity separate from its owner is treated as a “disregarded entity.” See Regulations section 301.7701-2(c)(2)(iii). Enter the owner’s name on line 1. The name of the entity entered on line 1 should never be a disregarded entity. The name on line 1 should be the name shown on the income tax return on which the income should be reported. For example, if a foreign LLC that is treated as a disregarded entity for U.S. federal tax purposes has a single owner that is a U.S. person, the U.S. owner’s name is required to be provided on line 1. If the direct owner of the entity is also a disregarded entity, enter the first owner that is not disregarded for federal tax purposes. Enter the disregarded entity’s name on line 2, “Business name/disregarded entity name.” If the owner of the disregarded entity is a foreign person, the owner must complete an appropriate Form W-8 instead of a Form W-9. This is the case even if the foreign person has a U.S. TIN.

### Line 2

If you have a business name, trade name, DBA name, or disregarded entity name, you may enter it on line 2.

### Line 3

Check the appropriate box on line 3 for the U.S. federal tax classification of the person whose name is entered on line 1. Check only one box on line 3.

IF the entity/person on line 1 is a(n) . . .	THEN check the box for . . .
• Corporation	Corporation
• Individual • Sole proprietorship, or • Single-member limited liability company (LLC) owned by an individual and disregarded for U.S. federal tax purposes.	Individual/sole proprietor or single-member LLC
• LLC treated as a partnership for U.S. federal tax purposes, • LLC that has filed Form 8832 or 2553 to be taxed as a corporation, or • LLC that is disregarded as an entity separate from its owner but the owner is another LLC that is not disregarded for U.S. federal tax purposes.	Limited liability company and enter the appropriate tax classification. (P= Partnership; C= C corporation; or S= S corporation)
• Partnership	Partnership
• Trust/estate	Trust/estate

### Line 4, Exemptions

If you are exempt from backup withholding and/or FATCA reporting, enter in the appropriate space on line 4 any code(s) that may apply to you.

#### Exempt payee code.

- Generally, individuals (including sole proprietors) are not exempt from backup withholding.
- Except as provided below, corporations are exempt from backup withholding for certain payments, including interest and dividends.
- Corporations are not exempt from backup withholding for payments made in settlement of payment card or third party network transactions.
- Corporations are not exempt from backup withholding with respect to attorneys’ fees or gross proceeds paid to attorneys, and corporations that provide medical or health care services are not exempt with respect to payments reportable on Form 1099-MISC.

The following codes identify payees that are exempt from backup withholding. Enter the appropriate code in the space in line 4.

- 1—An organization exempt from tax under section 501(a), any IRA, or a custodial account under section 403(b)(7) if the account satisfies the requirements of section 401(f)(2)
- 2—The United States or any of its agencies or instrumentalities
- 3—A state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities
- 4—A foreign government or any of its political subdivisions, agencies, or instrumentalities
- 5—A corporation
- 6—A dealer in securities or commodities required to register in the United States, the District of Columbia, or a U.S. commonwealth or possession
- 7—A futures commission merchant registered with the Commodity Futures Trading Commission
- 8—A real estate investment trust
- 9—An entity registered at all times during the tax year under the Investment Company Act of 1940
- 10—A common trust fund operated by a bank under section 584(a)
- 11—A financial institution
- 12—A middleman known in the investment community as a nominee or custodian
- 13—A trust exempt from tax under section 664 or described in section 4947



The following chart shows types of payments that may be exempt from backup withholding. The chart applies to the exempt payees listed above, 1 through 13.

IF the payment is for . . .	THEN the payment is exempt for . . .
Interest and dividend payments	All exempt payees except for 7
Broker transactions	Exempt payees 1 through 4 and 6 through 11 and all C corporations. S corporations must not enter an exempt payee code because they are exempt only for sales of noncovered securities acquired prior to 2012.
Barter exchange transactions and patronage dividends	Exempt payees 1 through 4
Payments over \$600 required to be reported and direct sales over \$5,000 <sup>1</sup>	Generally, exempt payees 1 through 5 <sup>2</sup>
Payments made in settlement of payment card or third party network transactions	Exempt payees 1 through 4

<sup>1</sup> See Form 1099-MISC, Miscellaneous Income, and its instructions.

<sup>2</sup> However, the following payments made to a corporation and reportable on Form 1099-MISC are not exempt from backup withholding: medical and health care payments, attorneys' fees, gross proceeds paid to an attorney reportable under section 6045(f), and payments for services paid by a federal executive agency.

**Exemption from FATCA reporting code.** The following codes identify payees that are exempt from reporting under FATCA. These codes apply to persons submitting this form for accounts maintained outside of the United States by certain foreign financial institutions. Therefore, if you are only submitting this form for an account you hold in the United States, you may leave this field blank. Consult with the person requesting this form if you are uncertain if the financial institution is subject to these requirements. A requester may indicate that a code is not required by providing you with a Form W-9 with "Not Applicable" (or any similar indication) written or printed on the line for a FATCA exemption code.

A—An organization exempt from tax under section 501(a) or any individual retirement plan as defined in section 7701(a)(37)

B—The United States or any of its agencies or instrumentalities

C—A state, the District of Columbia, a U.S. commonwealth or possession, or any of their political subdivisions or instrumentalities

D—A corporation the stock of which is regularly traded on one or more established securities markets, as described in Regulations section 1.1472-1(c)(1)(i)

E—A corporation that is a member of the same expanded affiliated group as a corporation described in Regulations section 1.1472-1(c)(1)(i)

F—A dealer in securities, commodities, or derivative financial instruments (including notional principal contracts, futures, forwards, and options) that is registered as such under the laws of the United States or any state

G—A real estate investment trust

H—A regulated investment company as defined in section 851 or an entity registered at all times during the tax year under the Investment Company Act of 1940

I—A common trust fund as defined in section 584(a)

J—A bank as defined in section 581

K—A broker

L—A trust exempt from tax under section 664 or described in section 4947(a)(1)

M—A tax exempt trust under a section 403(b) plan or section 457(g) plan

**Note:** You may wish to consult with the financial institution requesting this form to determine whether the FATCA code and/or exempt payee code should be completed.

## Line 5

Enter your address (number, street, and apartment or suite number). This is where the requester of this Form W-9 will mail your information returns. If this address differs from the one the requester already has on file, write NEW at the top. If a new address is provided, there is still a chance the old address will be used until the payor changes your address in their records.

## Line 6

Enter your city, state, and ZIP code.

## Part I. Taxpayer Identification Number (TIN)

**Enter your TIN in the appropriate box.** If you are a resident alien and you do not have and are not eligible to get an SSN, your TIN is your IRS individual taxpayer identification number (ITIN). Enter it in the social security number box. If you do not have an ITIN, see *How to get a TIN* below.

If you are a sole proprietor and you have an EIN, you may enter either your SSN or EIN.

If you are a single-member LLC that is disregarded as an entity separate from its owner, enter the owner's SSN (or EIN, if the owner has one). Do not enter the disregarded entity's EIN. If the LLC is classified as a corporation or partnership, enter the entity's EIN.

**Note:** See *What Name and Number To Give the Requester*, later, for further clarification of name and TIN combinations.

**How to get a TIN.** If you do not have a TIN, apply for one immediately. To apply for an SSN, get Form SS-5, Application for a Social Security Card, from your local SSA office or get this form online at [www.SSA.gov](http://www.SSA.gov). You may also get this form by calling 1-800-772-1213. Use Form W-7, Application for IRS Individual Taxpayer Identification Number, to apply for an ITIN, or Form SS-4, Application for Employer Identification Number, to apply for an EIN. You can apply for an EIN online by accessing the IRS website at [www.irs.gov/Businesses](http://www.irs.gov/Businesses) and clicking on Employer Identification Number (EIN) under Starting a Business. Go to [www.irs.gov/Forms](http://www.irs.gov/Forms) to view, download, or print Form W-7 and/or Form SS-4. Or, you can go to [www.irs.gov/OrderForms](http://www.irs.gov/OrderForms) to place an order and have Form W-7 and/or SS-4 mailed to you within 10 business days.

If you are asked to complete Form W-9 but do not have a TIN, apply for a TIN and write "Applied For" in the space for the TIN, sign and date the form, and give it to the requester. For interest and dividend payments, and certain payments made with respect to readily tradable instruments, generally you will have 60 days to get a TIN and give it to the requester before you are subject to backup withholding on payments. The 60-day rule does not apply to other types of payments. You will be subject to backup withholding on all such payments until you provide your TIN to the requester.

**Note:** Entering "Applied For" means that you have already applied for a TIN or that you intend to apply for one soon.

**Caution:** A disregarded U.S. entity that has a foreign owner must use the appropriate Form W-8.

## Part II. Certification

To establish to the withholding agent that you are a U.S. person, or resident alien, sign Form W-9. You may be requested to sign by the withholding agent even if item 1, 4, or 5 below indicates otherwise.

For a joint account, only the person whose TIN is shown in Part I should sign (when required). In the case of a disregarded entity, the person identified on line 1 must sign. Exempt payees, see *Exempt payee code*, earlier.

**Signature requirements.** Complete the certification as indicated in items 1 through 5 below.

**1. Interest, dividend, and barter exchange accounts opened before 1984 and broker accounts considered active during 1983.**

You must give your correct TIN, but you do not have to sign the certification.

**2. Interest, dividend, broker, and barter exchange accounts opened after 1983 and broker accounts considered inactive during 1983.**

You must sign the certification or backup withholding will apply. If you are subject to backup withholding and you are merely providing your correct TIN to the requester, you must cross out item 2 in the certification before signing the form.

**3. Real estate transactions.**

You must sign the certification. You may cross out item 2 of the certification.

**4. Other payments.** You must give your correct TIN, but you do not have to sign the certification unless you have been notified that you have previously given an incorrect TIN. "Other payments" include payments made in the course of the requester's trade or business for rents, royalties, goods (other than bills for merchandise), medical and health care services (including payments to corporations), payments to a nonemployee for services, payments made in settlement of payment card and third party network transactions, payments to certain fishing boat crew members and fishermen, and gross proceeds paid to attorneys (including payments to corporations).

**5. Mortgage interest paid by you, acquisition or abandonment of secured property, cancellation of debt, qualified tuition program payments (under section 529), ABLE accounts (under section 529A), IRA, Coverdell ESA, Archer MSA or HSA contributions or distributions, and pension distributions.** You must give your correct TIN, but you do not have to sign the certification.

**What Name and Number To Give the Requester**

For this type of account:	Give name and SSN of:
1. Individual	The individual
2. Two or more individuals (joint account) other than an account maintained by an FFI	The actual owner of the account or, if combined funds, the first individual on the account <sup>1</sup>
3. Two or more U.S. persons (joint account maintained by an FFI)	Each holder of the account
4. Custodial account of a minor (Uniform Gift to Minors Act)	The minor <sup>2</sup>
5. a. The usual revocable savings trust (grantor is also trustee)	The grantor-trustee <sup>1</sup>
b. So-called trust account that is not a legal or valid trust under state law	The actual owner <sup>1</sup>
6. Sole proprietorship or disregarded entity owned by an individual	The owner <sup>3</sup>
7. Grantor trust filing under Optional Form 1099 Filing Method 1 (see Regulations section 1.671-4(b)(2)(i)(A))	The grantor*
For this type of account:	Give name and EIN of:
8. Disregarded entity not owned by an individual	The owner
9. A valid trust, estate, or pension trust	Legal entity <sup>4</sup>
10. Corporation or LLC electing corporate status on Form 8832 or Form 2553	The corporation
11. Association, club, religious, charitable, educational, or other tax-exempt organization	The organization
12. Partnership or multi-member LLC	The partnership
13. A broker or registered nominee	The broker or nominee

For this type of account:	Give name and EIN of:
14. Account with the Department of Agriculture in the name of a public entity (such as a state or local government, school district, or prison) that receives agricultural program payments	The public entity
15. Grantor trust filing under the Form 1041 Filing Method or the Optional Form 1099 Filing Method 2 (see Regulations section 1.671-4(b)(2)(i)(B))	The trust

<sup>1</sup> List first and circle the name of the person whose number you furnish. If only one person on a joint account has an SSN, that person's number must be furnished.

<sup>2</sup> Circle the minor's name and furnish the minor's SSN.

<sup>3</sup> You must show your individual name and you may also enter your business or DBA name on the "Business name/disregarded entity" name line. You may use either your SSN or EIN (if you have one), but the IRS encourages you to use your SSN.

<sup>4</sup> List first and circle the name of the trust, estate, or pension trust. (Do not furnish the TIN of the personal representative or trustee unless the legal entity itself is not designated in the account title.) Also see *Special rules for partnerships*, earlier.

\*Note: The grantor also must provide a Form W-9 to trustee of trust.

Note: If no name is circled when more than one name is listed, the number will be considered to be that of the first name listed.

**Secure Your Tax Records From Identity Theft**

Identity theft occurs when someone uses your personal information such as your name, SSN, or other identifying information, without your permission, to commit fraud or other crimes. An identity thief may use your SSN to get a job or may file a tax return using your SSN to receive a refund.

To reduce your risk:

- Protect your SSN,
- Ensure your employer is protecting your SSN, and
- Be careful when choosing a tax preparer.

If your tax records are affected by identity theft and you receive a notice from the IRS, respond right away to the name and phone number printed on the IRS notice or letter.

If your tax records are not currently affected by identity theft but you think you are at risk due to a lost or stolen purse or wallet, questionable credit card activity or credit report, contact the IRS Identity Theft Hotline at 1-800-908-4490 or submit Form 14039.

For more information, see Pub. 5027, Identity Theft Information for Taxpayers.

Victims of identity theft who are experiencing economic harm or a systemic problem, or are seeking help in resolving tax problems that have not been resolved through normal channels, may be eligible for Taxpayer Advocate Service (TAS) assistance. You can reach TAS by calling the TAS toll-free case intake line at 1-877-777-4778 or TTY/TDD 1-800-829-4059.

**Protect yourself from suspicious emails or phishing schemes.**

Phishing is the creation and use of email and websites designed to mimic legitimate business emails and websites. The most common act is sending an email to a user falsely claiming to be an established legitimate enterprise in an attempt to scam the user into surrendering private information that will be used for identity theft.

The IRS does not initiate contacts with taxpayers via emails. Also, the IRS does not request personal detailed information through email or ask taxpayers for the PIN numbers, passwords, or similar secret access information for their credit card, bank, or other financial accounts.

If you receive an unsolicited email claiming to be from the IRS, forward this message to [phishing@irs.gov](mailto:phishing@irs.gov). You may also report misuse of the IRS name, logo, or other IRS property to the Treasury Inspector General for Tax Administration (TIGTA) at 1-800-366-4484. You can forward suspicious emails to the Federal Trade Commission at [spam@uce.gov](mailto:spam@uce.gov) or report them at [www.ftc.gov/complaint](http://www.ftc.gov/complaint). You can contact the FTC at [www.ftc.gov/idtheft](http://www.ftc.gov/idtheft) or 877-IDTHEFT (877-438-4338). If you have been the victim of identity theft, see [www.IdentityTheft.gov](http://www.IdentityTheft.gov) and Pub. 5027.

Visit [www.irs.gov/IdentityTheft](http://www.irs.gov/IdentityTheft) to learn more about identity theft and how to reduce your risk.

## Privacy Act Notice

Section 6109 of the Internal Revenue Code requires you to provide your correct TIN to persons (including federal agencies) who are required to file information returns with the IRS to report interest, dividends, or certain other income paid to you; mortgage interest you paid; the acquisition or abandonment of secured property; the cancellation of debt; or contributions you made to an IRA, Archer MSA, or HSA. The person collecting this form uses the information on the form to file information returns with the IRS, reporting the above information. Routine uses of this information include giving it to the Department of Justice for civil and criminal litigation and to cities, states, the District of Columbia, and U.S. commonwealths and possessions for use in administering their laws. The information also may be disclosed to other countries under a treaty, to federal and state agencies to enforce civil and criminal laws, or to federal law enforcement and intelligence agencies to combat terrorism. You must provide your TIN whether or not you are required to file a tax return. Under section 3406, payers must generally withhold a percentage of taxable interest, dividend, and certain other payments to a payee who does not give a TIN to the payer. Certain penalties may also apply for providing false or fraudulent information.

## REFERENCES

All bidders must provide three (3) projects of a similar nature as being performed in the immediate past five (5) years with the name, address and telephone number of the contact person having knowledge of the project or three (3) references (name, address, and telephone number) with knowledge of the integrity and business practices of the contractor.

<b>PROJECT</b>	
<b>FIRM</b>	
<b>ADDRESS</b>	
<b>CONTACT</b>	
<b>TELEPHONE</b>	

<b>PROJECT</b>	
<b>FIRM</b>	
<b>ADDRESS</b>	
<b>CONTACT</b>	
<b>TELEPHONE</b>	

<b>PROJECT</b>	
<b>FIRM</b>	
<b>ADDRESS</b>	
<b>CONTACT</b>	
<b>TELEPHONE</b>	

**RETURN WITH BID**

**Joint Purchasing Authorization**

County	<u>DuPage</u>
Local Public Agency	<u>DuPage County D.O.T</u>
Section Number	<u>23-PVMKG-11-GM</u>
Route	<u>2023 Pavement Marking Maintenance</u>

**JOINT PURCHASING:**  
**OTHER TAXING BODIES: Based on County Board Resolution IR-084-76.**

**Would your firm be willing to extend your bid to other taxing bodies in DuPage County such as school districts, townships, cities and villages, etc.?  
The approximate quantity usage is unknown.**

**YES \_\_\_\_\_ NO \_\_\_\_\_ \*\***

**\*\* Failure to complete this form will result in a default assumption of a "NO" response.**

**State any other requirements that they would have to meet beyond that of our Bid Invitation and Specifications.**

---

---

---

**NOTE: The County of DuPage would not be involved in purchasing by any other taxing body other than to receive a copy of their purchase order that would reference the County of DuPage contract number. The invoicing and payments would be entirely between the other taxing bodies and the Contractor. If the County of DuPage accepts this bid, the procedure to handle joint purchases would be developed by the County of DuPage with the Contractor and distributed to the taxing bodies by the County of DuPage.**



**TABLE OF CONTENTS**

**PROPOSAL DOCUMENTS**

- BLR 12200 Local Public Agency Formal Contract Proposal
  - COVER SHEET
  - NOTICE TO BIDDERS
  - PROPOSAL
  - CONTRACTOR CERTIFICATIONS
  - SIGNATURES
- BLR 12201 Schedule of Prices
- BLR 12230 Local Agency Proposal Bid Bond
- DuPage County Apprenticeship or Training Program Certification
- BLR 12326 Affidavit of Illinois Business Office
- BC 57 Affidavit of Availability
- DuPage County – Required Vendor Ethics Disclosure Statement
- IRS Form W-9: Request for Taxpayer Identification Number and Certification
- Three (3) references form
- Joint Purchasing Authorization

**PAGE**

**PLANS** ..... **A**

    GENERAL NOTES..... A

    SUMMARY OF QUANTITIES..... D

    SCHEDULES OF QUANTITIES ..... E

**SPECIAL PROVISIONS** ..... **1**

    DESCRIPTION OF WORK..... 1

    BIDDING DETAILS..... 1

    BIDDING REQUIREMENTS AND CONDITIONS FOR CONTRACT PROPOSALS..... 2

**ADDED ALTERNATIVE BIDDING** ..... 2

**ADD ALTERNATIVE BIDDING – LOW BIDDER DETERMINATION EXAMPLES** ..... 3

    SECTION 107 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC ..... 4

    SECTION 108 PROSECUTION AND PROGRESS ..... 5

    SECTION 109 MEASUREMENT AND PAYMENT ..... 6

    SECTION 671 MOBILIZATION ..... 6

    SECTION 1105 PAVEMENT MARKING EQUIPMENT ..... 6

    CALENDAR DAY REQUIREMENTS ..... 6

    TRAFFIC CONTROL AND PROTECTION ..... 6

    TRAFFIC CONTROL PLAN ..... 7

    RECESSED REFLECTIVE PAVEMENT MARKERS ..... 8

    45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING ..... 8

    MODIFIED URETHANE PAVEMENT MARKING – RAISED MEDIAN ..... 16

    TEMPORARY PAVEMENT MARKING REMOVAL ..... 16

- Index For Supplemental Specifications And Recurring Special Provisions
- Check Sheet For Recurring Special Provisions
- Check Sheet For Recurring Local Roads And Streets Special Provisions

DuPage County Prevailing Wage effective January 18, 2023 (for use with LRS Check Sheet #12)

Local Roads and Streets Special Provisions

LR 702 Construction and Maintenance Signs

BDE Special Provisions

- Compensable Delay Costs
- Construction Air Quality – Diesel Retrofit
- Subcontractor and DBE Payments
- Subcontractor Mobilization Payments
- Work Zone Traffic Control Devices

Metra

- Application for Right of Entry
- Exhibit C – Metra’s Insurance Requirements

**Highway Standard Drawings**

- 701201 Lane Closure, 2L, 2W, Day Only, for Speeds > 45 MPH
  - 701301 Lane Closure, 2L, 2W, Short Time Operations
  - 701306 Lane Closure, 2L, 2W, Slow Moving Operations Day Only, for Speeds > 45 MPH
  - 701311 Lane Closure, 2L, 2W, Moving Operations - Day Only
  - 701336 Lane Closure, 2L, 2W, Work Areas in Series, for Speeds > 45 MPH
  - 701421 Lane Closure, Multilane, Day Operations Only, for Speeds > 45 MPH to 55 MPH
  - 701422 Lane Closure, Multilane, for Speeds > 45 MPH to 55 MPH
  - 701426 Lane Closure, Multilane, Intermittent or Moving Operation, for Speeds > 45 MPH
  - 701427 Lane Closure, Multilane, Intermittent or Moving Operation, for Speeds ≤ 40 MPH
  - 701431 Lane Closure, Multilane, Undivided with Crossover, for Speeds > 45 MPH to 55 MPH
  - 701501 Urban Lane Closure, 2L, 2W, Undivided
  - 701502 Urban Lane Closure, 2L, 2W, with Bidirectional Left Turn Lane
  - 701601 Urban Lane Closure, Multilane, 1W or 2W with Nontraversable Median
  - 701602 Urban Lane Closure, Multilane, 2W with Bidirectional Left Turn Lane
  - 701606 Urban Single Lane Closure, Multilane, 2W with Mountable Median
  - 701611 Urban Half Road Closure, Multilane, 2W with Mountable Median
  - 701701 Urban Lane Closure, Multilane Intersection
  - 701801 Lane Closure, Multilane 1W or 2W Crosswalk or Sidewalk Closure
  - 701901 Traffic Control Devices
  - 781001 Typical Applications Raised Reflective Pavement Markers
  - TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
  - TC-11 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOWPLOW RESISTANT)
  - TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
  - TC-14 TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
- RECESSED PAVEMENT MARKER





**PLANS**

**GENERAL NOTES**

**GENERAL**

DESCRIPTIONS OF THE PL AND LOR WORK CATEGORIES ARE PROVIDED IN THE PROJECT SPECIAL PROVISIONS.

NO WORK SHALL COMMENCE UNTIL TRAFFIC CONTROL REQUIREMENTS ARE MET.

UNLESS AUTHORIZED BY THE ENGINEER, ALL EXISTING ACCESS POINTS SHALL BE MAINTAINED AT ALL TIMES BY THE CONTRACTOR.

ALL PAVEMENT MARKING ON COUNTY HIGHWAYS SHALL BE INSTALLED COMPLETELY AND TO LOGICAL TERMINII, UNLESS OTHERWISE DIRECTED BY THE ENGINEER. PL QUANTITIES IN THE SCHEDULE OF QUANTITIES ARE ESTIMATED AND THE ACTUAL QUANTITIES MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER ACCORDING TO FIELD CONDITIONS OR THE NEEDS OF THE DUPAGE COUNTY DIVISION OF TRANSPORTATION. PAYMENT WILL BE MADE BASED ON ACTUAL INSTALLED QUANTITIES.

ALL MARKINGS SHALL BE INSTALLED ACCORDING TO THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), 2009 EDITION AND THE SPECIAL PROVISIONS AND NOTES HEREIN REGARDLESS OF THE EXISTING CONFIGURATION. ANY NON-CONFORMING MARKINGS INSTALLED WITHOUT PRIOR APPROVAL OF THE TRAFFIC ENGINEER SHALL BE REMOVED AND CONFORMING MARKINGS INSTALLED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE COUNTY.

THE CONTRACTOR SHALL SUBMIT AN ESTIMATED WORK SCHEDULE TO THE ENGINEER BEFORE BEGINNING WORK. THE CONTRACTOR'S SCHEDULE SHALL INCLUDE NO MORE THAN SEVEN (7) CALENDAR DAYS BETWEEN SCHEDULED WORK ACTIVITIES.

THE CONTRACTOR SHALL NOTE THAT MANDATORY TURN LANE LINES SHALL BE MARKED WITH TRANSVERSE SKIP DASHES IN ACCORDANCE WITH MUTCD FIGURE 3B.24. TAPERED OR DIAGONAL SKIP DASHES APPROACHING MANDATORY TURN LANES WILL NOT BE ALLOWED UNLESS DIRECTED BY THE TRAFFIC ENGINEER.

THE CONTRACTOR SHALL NOTE THAT ALL CROSSWALKS SHALL BE IN CONTINENTAL (BAR) CONFIGURATION EXCEPT AS DIRECTED BY THE ENGINEER.

"LOCATION ON REQUEST (LOR)" QUANTITIES WILL BE USED FOR INSTALLING MARKINGS AT ADDITIONAL LOCATIONS NOT OTHERWISE INCLUDED IN THIS CONTRACT AS DIRECTED BY THE ENGINEER. THESE QUANTITIES WILL BE USED AS NECESSARY COUNTY-WIDE TO MEET THE NEEDS OF THE DUPAGE COUNTY DIVISION OF TRANSPORTATION. THE LOCATION, TIMING, AND GROUPING OF PROJECT ASSIGNMENTS SHALL BE AT THE DISCRETION OF THE ENGINEER. WORK PERFORMED UNDER LOR QUANTITIES SHALL BE COMPLETED BY THE CONTRACTOR UPON REQUEST OF THE ENGINEER. THE CONTRACTOR SHALL BEGIN ASSIGNED LOR WORK WITHIN 14 CALENDAR DAYS OF NOTIFICATION BY THE ENGINEER. THE COST TO MOBILIZE OR OTHERWISE PERFORM WORK AT SMALL OR DISTANT PROJECT SITES, OR UNDER UNANTICIPATED CIRCUMSTANCES, SHALL NOT BE PAID FOR SEPARATELY BUT SHALL BE INCLUDED IN THE UNIT PRICES PAY ITEMS.

**TRAFFIC CONTROL AND PROTECTION**

TRAFFIC CONTROL AND PROTECTION SHALL BE PERFORMED IN ACCORDANCE WITH THE TRAFFIC CONTROL PLAN, TRAFFIC SIGNAL PLANS, THESE NOTES, APPLICABLE SPECIAL PROVISIONS, AND SECTION 701 OF THE STANDARD SPECIFICATIONS AS AMENDED BY THE SPECIAL PROVISION FOR WORK ZONE TRAFFIC CONTROL (CHECK SHEET LRS 3).

THE TYPE III BARRICADES ARE TO BE PLACED IN ACCORDANCE WITH STANDARD 701901 UNLESS AUTHORIZED BY THE ENGINEER TO USE AN ALTERNATE ARRANGEMENT.

TYPE I OR TYPE II BARRICADES, DRUMS, OR VERTICAL PANELS WITH MONODIRECTIONAL STEADY-BURN LIGHTS SHALL BE REQUIRED ALONG TEMPORARY ROADS, DETOURS, AND SIDE STREETS TO DELINEATE THE TRAVELED WAY WITHIN THE CONSTRUCTION ZONE. THE MAXIMUM SPACING FOR THESE DEVICES SHALL BE 100 FEET CENTER TO CENTER.

BARRICADES THAT MUST BE PLACED IN EXCAVATED AREAS SHALL HAVE LEG EXTENSIONS INSTALLED SUCH THAT THE TOP OF THE BARRICADE IS IN COMPLIANCE WITH THE HEIGHT REQUIREMENTS OF STANDARD 701901.

TYPE I OR TYPE II BARRICADES WITH TWO-WAY FLASHING LIGHTS SHALL BE REQUIRED AT ALL OPEN TRENCHES, EXCAVATIONS, OPEN OR EXPOSED SEWER STRUCTURES, TRANSVERSE PAVEMENT JOINTS, MATERIALS OR EQUIPMENT WITHIN THE RIGHT-OF-WAY (NUMBER AND SPACING DEPENDS ON THE CONDITIONS); AND AT LOCATIONS DESIGNATED BY THE ENGINEER OR LOCAL LAW ENFORCEMENT AGENCIES.

TYPE I, II AND / OR III BARRICADES WITH TWO-WAY FLASHING LIGHTS WILL BE REQUIRED TO GUIDE TRAFFIC AWAY FROM PAVEMENT AREAS CLOSED FOR CONSTRUCTION.


WHERE REQUIRED, TRAFFIC SIGNS SHALL BE RELOCATED FOR EACH STAGE OF CONSTRUCTION.

ARROW BOARDS WILL BE REQUIRED WHEN IMPLEMENTING ALL LANE CLOSURES.

SPECIAL PROVISIONS  
2023 PAVEMNT MARKING MAINTENANCE  
SEC. 23-PVMKG-11-GM

THE FOLLOWING TRAFFIC CONTROL STANDARDS ARE THE MINIMUM REQUIREMENTS FOR THE TRAFFIC CONTROL FOR THIS PROJECT:

- 701201 Lane Closure, 2L, 2W, Day Only, for Speeds > 45 MPH
- 701301 Lane Closure, 2L, 2W, Short Time Operations
- 701306 Lane Closure, 2L, 2W, Slow Moving Operations Day Only, for Speeds > 45 MPH
- 701311 Lane Closure, 2L, 2W, Moving Operations - Day Only
- 701336 Lane Closure, 2L, 2W, Work Areas in Series, for Speeds > 45 MPH
- 701421 Lane Closure, Multilane, Day Operations Only, for Speeds > 45 MPH to 55 MPH
- 701422 Lane Closure, Multilane, for Speeds > 45 MPH to 55 MPH
- 701426 Lane Closure, Multilane, Intermittent or Moving Operation, for Speeds > 45 MPH
- 701427 Lane Closure, Multilane, Intermittent or Moving Operation, for Speeds ≤ 40 MPH
- 701431 Lane Closure, Multilane, Undivided with Crossover, for Speeds > 45 MPH to 55 MPH
- 701501 Urban Lane Closure, 2L, 2W, Undivided
- 701502 Urban Lane Closure, 2L, 2W, with Bidirectional Left Turn Lane
- 701601 Urban Lane Closure, Multilane, 1W or 2W with Nontraversable Median
- 701602 Urban Lane Closure, Multilane, 2W with Bidirectional Left Turn Lane
- 701606 Urban Single Lane Closure, Multilane, 2W with Mountable Median
- 701611 Urban Half Road Closure, Multilane, 2W with Mountable Median
- 701701 Urban Lane Closure, Multilane Intersection
- 701801 Lane Closure, Multilane 1W or 2W Crosswalk or Sidewalk Closure
- 701901 Traffic Control Devices
- 781001 Typical Applications Raised Reflective Pavement Markers
- TC-10 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
- TC-11 TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOWPLOW RESISTANT)
- TC-13 DISTRICT ONE TYPICAL PAVEMENT MARKINGS
- TC-14 TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)  
RECESSED PAVEMENT MARKER

- **SUMMARY OF QUANTITIES**
  - **SCHEDULES OF QUANTITIES**
- 

BASE BID

**SUMMARY OF QUANTITIES**

Section: **23-PVMKG-11-GM**

Route: **Various**

Item No.	Items	Unit	Quantity	REMOVE & REPLACE	REMOVAL ONLY	NEW MARKINGS	NOMINAL Δ
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	14183	13336.4			847.0
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12308	8976		85	3247
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	48648	45429		102	3117
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	16346	15315			1031
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	26884	22213		283	4388
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	5174	5040			134
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	396488	336363			60125
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	718	556.4			161.2
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	19476	18488			988
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	3442	3217			225
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	54				54
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	440	284			156
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	180	131			49
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	3687	3117			570
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	92603	88416.3	110.5		4076.2
16	RECESSED REFLECTIVE PAVMENT MARKER	EACH	500				500
17	REPLACEMENT REFLECTOR	EACH	500				500
18	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	800				800

\* DESIGNATES SPECIALTY ITEM ( NONE DESIGNATED )

TOTAL QUANTITIES MAY BE ROUNDED

Δ - NOMINAL QUANTITY FOR OVERAGES AND BIDDING PURPOSES

ALTERNATIVE A

**SUMMARY OF QUANTITIES**

Section: **23-PVMKG-11-GM**

Route: **Various**

Item No.	Items	Unit	Quantity	REMOVE & REPLACE	REMOVAL ONLY	NEW MARKINGS	NOMINAL Δ
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	525	525.2			
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	699	699		-	
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2066	2066			
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		-			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	904	904		-	
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	105	105			
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	109160	109160			
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2506	2506.4			
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	4418	4418			
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	2074	2074			
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	664	664			
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	270	270			
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	355	355			
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	122	122			
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	9342	9341.6			
16	RECESSED REFLECTIVE PAVMENT MARKER	EACH					
17	REPLACEMENT REFLECTOR	EACH					
18	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT					

\* DESIGNATES SPECIALTY ITEM ( NONE DESIGNATED )

TOTAL QUANTITIES MAY BE ROUNDED

Δ - NOMINAL QUANTITY FOR OVERAGES AND BIDDING PURPOSES

ALTERNATIVE B

**SUMMARY OF QUANTITIES**

Section: **23-PVMKG-11-GM**

Route: **Various**

Item No.	Items	Unit	Quantity	REMOVE & REPLACE	REMOVAL ONLY	NEW MARKINGS	NOMINAL Δ
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	832	728		104	
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	705	705		-	
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2914	2914			
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	250	250			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1849	1849		-	
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	188	188			
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	104700	104700			
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	255	254.8			
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2051	2051			
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	5271	5271			
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT					
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT					
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT					
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	178	178			
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	8222	8221.8			
16	RECESSED REFLECTIVE PAVMENT MARKER	EACH					
17	REPLACEMENT REFLECTOR	EACH					
18	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT					

\* DESIGNATES SPECIALTY ITEM ( NONE DESIGNATED )

TOTAL QUANTITIES MAY BE ROUNDED

Δ - NOMINAL QUANTITY FOR OVERAGES AND BIDDING PURPOSES



ALTERNATIVE C

**SUMMARY OF QUANTITIES**

Section: **23-PVMKG-11-GM**

Route: **Various**

Item No.	Items	Unit	Quantity	REMOVE & REPLACE	REMOVAL ONLY	NEW MARKINGS	NOMINAL Δ
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291.2			
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	801	801		-	
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1306	1306			
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT		-			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1098	1004		94	
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	199	199			
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT	39652	39652			
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT					
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT					
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT					
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT					
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT					
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT					
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT					
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	2440	2439.5			
16	RECESSED REFLECTIVE PAVMENT MARKER	EACH					
17	REPLACEMENT REFLECTOR	EACH					
18	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT					

\* DESIGNATES SPECIALTY ITEM ( NONE DESIGNATED )

TOTAL QUANTITIES MAY BE ROUNDED

Δ - NOMINAL QUANTITY FOR OVERAGES AND BIDDING PURPOSES

ALTERNATIVE D

**SUMMARY OF QUANTITIES**

Section: **23-PVMKG-11-GM**

Route: **Various**

Item No.	Items	Unit	Quantity	REMOVE & REPLACE	REMOVAL ONLY	NEW MARKINGS	NOMINAL Δ
1	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3269	3268.6			
2	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3587	3587		-	
3	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8166	8100		66	
4	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	104	104			
5	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4365	4026		339	
6	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1334	1334			
7	HOT SPRAY THERMOPLASTIC PAVEMENT MARKING LINE - 4 INCH	FOOT					
8	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4321	4321.2			
9	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2155	2155			
10	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	3913	3913			
11	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	1622	1622			
12	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	250	250			
13	MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	FOOT	115	115			
14	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	213	213			
15	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	23493	23298.3	195		
16	RECESSED REFLECTIVE PAVMENT MARKER	EACH					
17	REPLACEMENT REFLECTOR	EACH					
18	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT					

\* DESIGNATES SPECIALTY ITEM ( NONE DESIGNATED )

TOTAL QUANTITIES MAY BE ROUNDED

Δ - NOMINAL QUANTITY FOR OVERAGES AND BIDDING PURPOSES

BASE BID

NO.	HIGHWAY	INTERSECTION	2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																		
			LF	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.
			24" S.W.	12" S.W.	8" S.W.	6" SW CROSSWALK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.	
<b>BASE BID</b>																					
3	WARRENVILLE RD.	NAPERVILLE RD TO FINLEY RD																			
3	WARRENVILLE RD.	CENTRAL PARK OF LISLE	W		37	270															72
3	WARRENVILLE RD.	CENTRAL PARK OF LISLE	N	18																	
3	WARRENVILLE RD.	CENTRAL PARK OF LISLE	S	32																	
3	WARRENVILLE RD.	CENTRAL PARK OF LISLE	E		69	413															334
3	WARRENVILLE RD.	NAVISTAR DR.	W	40				186													
3	WARRENVILLE RD.	NAVISTAR DR.	E	36	150			155													45
3	WARRENVILLE RD.	FORBES DR.	W					150													39
3	WARRENVILLE RD.	FORBES DR.	E					151													40
3	WARRENVILLE RD.	CORPORATE WEST DR. / CABOT DR.	W	50	168	302		220		24											
3	WARRENVILLE RD.	CORPORATE WEST DR. / CABOT DR.	N	26	162																
3	WARRENVILLE RD.	CORPORATE WEST DR. / CABOT DR.	S	24	156																
3	WARRENVILLE RD.	CORPORATE WEST DR. / CABOT DR.	E	52	168	598		160		60											149
3	WARRENVILLE RD.	ARBORETUM VILLAGE	W																		
3	WARRENVILLE RD.	ARBORETUM VILLAGE	E					200													40
		SKIP LEASK LN																			
3	WARRENVILLE RD.	YACKLEY AVE.	W	123	50	336				672											110
3	WARRENVILLE RD.	YACKLEY AVE.	E	35	138			144													
3	WARRENVILLE RD.	PINE RD.	W	48						168											
3	WARRENVILLE RD.	PINE RD.	E																		35
3	WARRENVILLE RD.	WHITE BIRCH DR.	W					190													
3	WARRENVILLE RD.	WHITE BIRCH DR.	E																		100
3	WARRENVILLE RD.	RTE. 53	W	70	32	234	44	1456													
3	WARRENVILLE RD.	RTE. 53	E	69	110	225		990													
3	WARRENVILLE RD.	MAIN ST (LISLE)	W	46																	233
3	WARRENVILLE RD.	MAIN ST (LISLE)	S	26	156																
3	WARRENVILLE RD.	MAIN ST (LISLE)	E	40					277	30											156
3	WARRENVILLE RD.	901 WARRENVILLE ROAD	W	36				170													
3	WARRENVILLE RD.	901 WARRENVILLE ROAD	E	36				192													206
3	WARRENVILLE RD.	801 WARRENVILLE ROAD	W					189													
3	WARRENVILLE RD.	801 WARRENVILLE ROAD	E					195													226
3	WARRENVILLE RD.	550 WARRENVILLE ROAD	W					162													
3	WARRENVILLE RD.	HATCH LANE	W					220													109
3	WARRENVILLE RD.	HATCH LANE	E					167													81
3	WARRENVILLE RD.	IVANHOE LANE	W					220													
3	WARRENVILLE RD.	IVANHOE LANE	E					176													68
3	WARRENVILLE RD.	EXTENDED STAY HOTEL	W					147													
3	WARRENVILLE RD.	EXTENDED STAY HOTEL	E					100													171
3	WARRENVILLE RD.	I-355 BRIDGE DECK																			
3	WARRENVILLE RD.	AUTHORITY DR	W					152													117
3	WARRENVILLE RD.	AUTHORITY DR	E					100													117
3	WARRENVILLE RD.	COMMERCE DR	W					103													
3	WARRENVILLE RD.	COMMERCE DR	E					96													66
3	WARRENVILLE RD.	CROSS STREET	S	27				303													
3	WARRENVILLE RD.	CROSS STREET	W	35				500													
3	WARRENVILLE RD.	CROSS STREET	E	25				152													56
3	WARRENVILLE RD.	2500-2560 WARRENVILLE ROAD	W					122													
3	WARRENVILLE RD.	FINLEY ROAD	W	21	114																150
8	YORK RD (NORTH)	DEVON TO IL 19																			
8	YORK RD (SOUTH)	GOLF ENT TO S OF SPRING																			
8	YORK RD (SOUTH)	GOLF ENT	N																		126
8	YORK RD (SOUTH)	GOLF ENT	S					220													91
8	YORK RD (SOUTH)	BUTLER JR HIGH SCHOOL	N					140													
8	YORK RD (SOUTH)	WINDSOR DR.	N					100													39
8	YORK RD (SOUTH)	WINDSOR DR.	S																		132
8	YORK RD (SOUTH)	31ST	N	44	230		184	245													152
8	YORK RD (SOUTH)	31ST	S	42	156			250													84
8	YORK RD (SOUTH)	CHURCH ENT	S					40													
8	YORK RD (SOUTH)	CANTERBURY LN			144		109														
8	YORK RD (SOUTH)	PATH CROSSING			72		54														
8	YORK RD (SOUTH)	OLD MILL ROAD	N					115													
8	YORK RD (SOUTH)	YORK TAVERN	N																		78
8	YORK RD (SOUTH)	YORK TAVERN	S					60													
8	YORK RD (SOUTH)	SPRING RD.	N	24	78			123													44
8	YORK RD (SOUTH)	SPRING RD.	S	24	84			152													94
9	LEMONT ROAD	SOUTH OF GROVE SHOPPING CENTER																			
9	LEMONT ROAD	83rd St. to TIMBER TRAIL/ HERITAGE PKWY																			
9	LEMONT ROAD	83RD ST.	S	48	162			384													
9	LEMONT ROAD	83RD CT.	N					50													

BASE BID

			2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																			
NO.	HIGHWAY	INTERSECTION	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	
			24" S.W.	12" S.W.	8" S.W.	6" SW CROSSWALK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.		
9	LEMONT ROAD	83RD CT.	S					44				11	1	1								
9	LEMONT ROAD	CENTRAL AVE.	N					98				21	1	1								
9	LEMONT ROAD	CENTRAL AVE.	S																			
9	LEMONT ROAD	BELLER DR.	N																			
9	LEMONT ROAD	BELLER DR.	S					172					2	1								
9	LEMONT ROAD	85TH CT.	N																			
9	LEMONT ROAD	85TH CT.	S																			
9	LEMONT ROAD	86TH ST.	N					104				20	1	1								
9	LEMONT ROAD	86TH ST.	S					110				17	1	1								
9	LEMONT ROAD	87TH ST.	N	53				150				12	1	1								
9	LEMONT ROAD	87TH ST.	W	39	156																	
9	LEMONT ROAD	87TH ST.	E	25																		
9	LEMONT ROAD	87TH ST.	S	36				162				11	2	1								
9	LEMONT ROAD	WOODCREST DR.	N																			221
9	LEMONT ROAD	WOODCREST DR.	S					115				17	1	1								284
9	LEMONT ROAD	TIMBER TRAILS/ HERITAGE PKWY	N	36	144			121				17	1	1								
9	LEMONT ROAD	TIMBER TRAILS/ HERITAGE PKWY	S	36	144			270				25	2	2								
15	CASS AVENUE	PLAINFIELD TO 91ST ST																				
15	CASS AVENUE	PLAINFIELD RD	S	47	156			230				30	2	2								102
15	CASS AVENUE	REGENCY GROVE DR	N					98				20	2	1								42
15	CASS AVENUE	REGENCY GROVE DR	S					108				20	3	1								40
15	CASS AVENUE	ASHBROOK CT/ CONCORD PL	N	36	132			100				20	3	1								40
15	CASS AVENUE	ASHBROOK CT/ CONCORD PL	W	21	108																	
15	CASS AVENUE	ASHBROOK CT/ CONCORD PL	E	28	150																	
15	CASS AVENUE	ASHBROOK CT/ CONCORD PL	S	38	132			95				18	1	1								45
15	CASS AVENUE	SLEEP HOLLOW TO DARIEN PATH																				
15	CASS AVENUE	NORTH FRONTAGE RD	N	46	159	416		158		89		21	2	1								40
15	CASS AVENUE	NORTH FRONTAGE RD	W	30																		
15	CASS AVENUE	NORTH FRONTAGE RD	E	29				95					1	1	1							25
15	CASS AVENUE	NORTH FRONTAGE RD	S	44				182				21	2	1								
15	CASS AVENUE	I-55 RAMPS	N			1149				300												
15	CASS AVENUE	I-55 BRIDGE DECK																				
15	CASS AVENUE	I-55 RAMPS	S			1187				304												
15	CASS AVENUE	SOUTH FRONTAGE RD	N									17	2	1								
15	CASS AVENUE	SOUTH FRONTAGE RD	S					100				10	1	1								100
15	CASS AVENUE	NORTHGATE	N																			
15	CASS AVENUE	NORTHGATE	W	30		118				30			2									
15	CASS AVENUE	NORTHGATE	S					185				20	2	1								175
15	CASS AVENUE	SOUTHERN DUPAGE REGIONAL TRAIL			189		114															
15	CASS AVENUE	91ST	N					175				41	2	1								
20	GRAND AVENUE	LAKE ST.	N																			
21	FABYAN PARKWAY	IL 38 TO WEST COUNTY LINE																				
25	MEYERS ROAD	IL 38 (ROOSEVELT) TO IL 56 (BUTTERFIELD)																				1096
25	MEYERS ROAD	IL 38 - ROOSEVELT RD.	S	44				600				36	12	6								
25	MEYERS ROAD	14TH ST.	N	36	138			165				26	2	1								
25	MEYERS ROAD	14TH ST.	S	36	128			165				26	6	1								
25	MEYERS ROAD	16TH ST.	N	35	138			150				26	2	1								
25	MEYERS ROAD	16TH ST.	S	35				245				23	2	1								
25	MEYERS ROAD	COURTYARD DR.	N					150				21	2	1								
25	MEYERS ROAD	COURTYARD DR.	S																			
25	MEYERS ROAD	18TH ST.	N					100				18	1	1								
25	MEYERS ROAD	18TH ST.	S					91				17	1	1								
25	MEYERS ROAD	CORPORATE CENTER	N	33				146				24	2	1								
25	MEYERS ROAD	CORPORATE CENTER	S	25																		
25	MEYERS ROAD	22ND ST.	N	36				148				20	1	1								
25	MEYERS ROAD	22ND ST.	S	46				300				37	2	2								
25	MEYERS ROAD	N TOWER RD. / FOUNTAIN SQUARE DR.	N		66	132		210				28	3	2								
25	MEYERS ROAD	N TOWER RD. / FOUNTAIN SQUARE DR.	S		31	148						14	1	1								
25	MEYERS ROAD	IL 56 / BUTTERFIELD RD.	N	51				591				49	5	5								
28	WOODDALE ROAD	SUNSET DR. TO LAKE ST.																				
33	75TH ST	LYMAN AVE TO E OF OLYMPUS																				
33	75TH ST	LYMAN AVE	S	23	209		150															
33	75TH ST	LYMAN AVE	E	40																		40
33	75TH ST	LYMAN AVE	W	39	33	89		482					3	3								81
33	75TH ST	JIMMY JOHN'S	W					190				27	1	1								48
33	75TH ST	ELITE HOME FURNITURE	E					199				22	2	2								77
33	75TH ST	LEMONT RD	N	53				647				54	6	6								13
33	75TH ST	LEMONT RD	S	57	281			650				62	6	6								11

BASE BID

			2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																		
NO.	HIGHWAY	INTERSECTION	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	LF	LF	LF
			24" S.W.	12" S.W.	8" S.W.	6" SW CROSSWALK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.	
33	75TH ST	LEMONT RD	E	72				628		94	6	6									41
33	75TH ST	LEMONT RD	W	71				995		93	6	6									37
33	75TH ST	DUNHAM RD	N	27																	
33	75TH ST	DUNHAM RD	S	22	146		99														
33	75TH ST	DUNHAM RD	E	50	219	780				24	3	3							16	16	
33	75TH ST	DUNHAM RD	W	46	198	780				22	3	3							16	16	
33	75TH ST	ZIGFIELD TROY GOLF	E	204	730					24	3	3							18	16	
33	75TH ST	ZIGFIELD TROY GOLF	W	207	755					23	3	3							18	16	
33	75TH ST	DEVEREUX RD	E	239	828					24	3	3							18	74	14
33	75TH ST	DEVEREUX RD	W	218	764					25	3	3							21	14	
33	75TH ST	VILLAGE OF WOODRIDGE BLDG	E	49	548					25	3	3								23	
33	75TH ST	VILLAGE OF WOODRIDGE BLDG	W	43	238					20	1	1									
33	75TH ST	WOODWARD AVE	N	45																	
33	75TH ST	WOODWARD AVE	S	44				618		22	4	4								9	
33	75TH ST	WOODWARD AVE	E	77	99	587		498		72	6	6							13	33	
33	75TH ST	WOODWARD AVE	W	81				1298		63	7	7								90	
33	75TH ST	I-355 BRIDGE																			
33	75TH ST	I-355 RAMPS	E	34	139			512		75	4	4								71	
33	75TH ST	I-355 RAMPS	W	110	90			1138		24	3	7				4				59	
33	75TH ST	JAMES AVE	N	33	199	74															
33	75TH ST	JAMES AVE	S	54	210	72															
33	75TH ST	JAMES AVE	E	70	252			414		58	4	2								9	
33	75TH ST	JAMES AVE	W	54	258			189		18	1	1								25	
33	75TH ST	WOODRIDGE DR.	N	38	156																
33	75TH ST	WOODRIDGE DR.	S	38	154																
33	75TH ST	WOODRIDGE DR.	E	46				173		22	2	1								28	
33	75TH ST	WOODRIDGE DR.	W	40	188		147	160		23	2	1								9	
33	75TH ST	IL 53	E	50				633		61	5	5								10	
33	75TH ST	IL 53	W	39				248		23	2	2									
33	75TH ST	BRIDGE																			
33	75TH ST	GREENE RD	N	32																	
33	75TH ST	GREENE RD	S	28	237																
33	75TH ST	GREENE RD	E	43	351			253		23	2	2								9	
33	75TH ST	GREENE RD	W	36				165		25	2	2								9	
33	75TH ST	RIDGESTONE DR.	W					107		24	1	1									
33	75TH ST	GLADESTONE DR.	E					201		24	2	2								9	
33	75TH ST	GLADESTONE DR.	W					106		22	1	1								53	
33	75TH ST	PALOMINO DR.	W					158		26	2	1								49	
33	75TH ST	RANCHVIEW DR.	S	29																	
33	75TH ST	RANCHVIEW DR.	E	35				301		24	3	3								9	
33	75TH ST	RANCHVIEW DR.	W	24																29	
33	75TH ST	COLLEGE RD	E					145		24	1	1								9	
33	75TH ST	COLLEGE RD	W					146		26	1	1									
33	75TH ST	WEHRLI RD	E	39				223		25	2	2								18	
33	75TH ST	WEHRLI RD	W	40	134			341		39	3	3								57	22
33	75TH ST	NAPER BLVD	N	31																	
33	75TH ST	NAPER BLVD	S	42																	
33	75TH ST	NAPER BLVD	E	60	430	1419		270		23	6	6							106	13	
33	75TH ST	NAPER BLVD	W	54	212	1119				19	3	3								13	
33	75TH ST	WASHINGTON ST	N	69	251		304														
33	75TH ST	WASHINGTON ST	S	68	237		280														
33	75TH ST	WASHINGTON ST	E	74	173		239	235		84	1	4									
33	75TH ST	WASHINGTON ST	W	75	180		238	909		87	8	8				2				38	
43	COUNTY FARM RD.	N. OF KELLY DRIVE TO ARMY TRAIL ROAD																			
43	COUNTY FARM RD.	NORTH AVE. TO ROOSEVELT RD.																			
43	COUNTY FARM RD.	NORTH AVE.	S					152		21	1	1									62
43	COUNTY FARM RD.	ST. CHARLES RD.	N	51	94	157		251		20	2	2									
43	COUNTY FARM RD.	ST. CHARLES RD.	S	38				264		21	2	2									404
43	COUNTY FARM RD.	ST. CHARLES RD.	E	38				374		21	4	4									
43	COUNTY FARM RD.	ST. CHARLES RD.	W	33				211		24	2	2									
43	COUNTY FARM RD.	IPP			174		120														
43	COUNTY FARM RD.	HAWTHORNE LN./TIMBER CREEK DR.	N					119		22	1	1									
43	COUNTY FARM RD.	HAWTHORNE LN./TIMBER CREEK DR.	S					147		20	1	1									96
43	COUNTY FARM RD.	HICKORY LN	N					150		22	2	1									
43	COUNTY FARM RD.	HICKORY LN	S																	84	53
43	COUNTY FARM RD.	FOREST PRESERVE ENT.	S					146		19	2	1									69
43	COUNTY FARM RD.	COUNTY FARM RD	N	50	171			213		21	2	2									76
43	COUNTY FARM RD.	COUNTY FARM RD	S	42	251		143	236		20	2	2								50	23
43	COUNTY FARM RD.	COUNTY FARM RD	E	38	166			201			2	2									
43	COUNTY FARM RD.	COUNTY FARM RD	W	39	242		159	203			2	2									
43	COUNTY FARM RD.	BUSINESS ENT.	S					149		21	2	1									
43	COUNTY FARM RD.	WINFIELD SCOTT DR.	N					153		20	2	1									
43	COUNTY FARM RD.	WINFIELD SCOTT DR.	S					152		17	2	1									25



**BASE BID**

			2023 PAVEMENT MARKING REMOVE AND REPLACE - URETHANE ON CONCRETE															
NO.	HIGHWAY	INTERSECTION	LF	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	SF	
			24" S.W	12" S.W.	8" SW	6" SW XW	6" SW TURN.	12" S.Y.	4" S.Y.	4" SW	6" DASHES	ARROWS	ONLYS	THRU ARR	COMB. ARRO	"SCHOOL"	MEDIAN NOSES	
<b>BASE BID</b>																		
3	WARRENVILLE RD.	I-355 BRIDGE DECK							3628	2218								
8	YORK RD (NORTH)	DEVON TO IL 19						240	3801	2987								
8	YORK RD (SOUTH)	SPRING RD.	N					42	44	844	480	20	1	1				
15	CASS AVENUE	NORTH FRONTAGE RD	S														58	
15	CASS AVENUE	I-55 BRIDGE DECK							670	660								
15	CASS AVENUE	SOUTH FRONTAGE RD	N														70	
20	GRAND AVENUE	LAKE ST.	N	66				1108		532	120		7	7			181	
33	75TH ST	LYMAN AVE	E														77	
33	75TH ST	LYMAN AVE	W														104	
33	75TH ST	JIMMY JOHN'S	W														210	
33	75TH ST	ELITE HOME FURNITURE	E														110	
33	75TH ST	LEMONT RD	E														72	
33	75TH ST	LEMONT RD	W														44	
33	75TH ST	DUNHAM RD	E														102	
33	75TH ST	DUNHAM RD	W														78	
33	75TH ST	ZIGFIELD TROY GOLF	E														66	
33	75TH ST	ZIGFIELD TROY GOLF	W														74	
33	75TH ST	DEVEREUX RD	E														69	
33	75TH ST	DEVEREUX RD	W														72	
33	75TH ST	VILLAGE OF WOODRIDGE BLDG	E														100	
33	75TH ST	VILLAGE OF WOODRIDGE BLDG	W														45	
33	75TH ST	WOODWARD AVE	E														48	
33	75TH ST	WOODWARD AVE	W														75	
33	75TH ST	I-355 RAMPS	E														200	
33	75TH ST	I-355 RAMPS	W														105	
33	75TH ST	JAMES AVE	E														38	
33	75TH ST	JAMES AVE	W														44	
33	75TH ST	WOODRIDGE DR.	E														60	
33	75TH ST	WOODRIDGE DR.	W														115	
33	75TH ST	IL 53	E														65	
33	75TH ST	IL 53	W														130	
33	75TH ST	GREENE RD	E														40	
33	75TH ST	GREENE RD	W														34	
33	75TH ST	GLADESTONE DR.	E														33	
33	75TH ST	GLADESTONE DR.	W														62	
33	75TH ST	PALOMINO DR.	W														77	
33	75TH ST	RANCHVIEW DR.	E														36	
33	75TH ST	RANCHVIEW DR.	W														60	
33	75TH ST	COLLEGE RD	E														40	
33	75TH ST	COLLEGE RD	W														44	
33	75TH ST	WEHRLI RD	E														40	
33	75TH ST	WEHRLI RD	W														47	
33	75TH ST	NAPER BLVD	E														42	
33	75TH ST	NAPER BLVD	W														44	
33	75TH ST	WASHINGTON ST	E					654	438	220		6	3				58	
33	75TH ST	WASHINGTON ST	W														48	
		TOTAL		66	0	0	0	1804	284	9381	7097	140	7	11	7	0	0	3117
		LENGTH (FT)		66	-	-	-	1804	284	9381	7097	280	-	-	-	-	-	-
		AREA (SQ FT)		-	-	-	-	-	-	-	-	109.2	228.8	80.5	-	-	-	3117
		REMOVAL AREA (SQ FT)		132	-	-	-	902	284	3127	2365.667	140	109.2	228.8	80.5	-	-	3117

**BASE BID**

NO.	HIGHWAY	INTERSECTION	2023 REMOVAL ONLY						2023 NEW THERMOPLASTIC STRIPING ON ASPHALT										
			LF	LF	LF	EA.	EA.	EA.	LF	LF	LF	LF	EA	EA.	EA.	EA.	LF	EA	
			4" REM.	6" REM	12" REM	REM ARROW	REM ONLY	"SCHOOL"	NEW 12"	NEW 6" S.W.	NEW 24" S.W.	4"	RXR	"SCHOOL"	ARROW	ONLY	NEW 8" S.W.	6" DASH	
<b>BASE BID</b>																			
3	WARRENVILLE RD.	CROSS STREET	S	108						115									
3	WARRENVILLE RD.	FINLEY ROAD	W	113						120									
9	LEMONT ROAD	SOUTH OF GROVE SHOPPING CENTER								48	90		85						6
		<b>TOTAL</b>		0	221	0	0	0	0	283	90	0	85	0	0	0	0	0	6
		LENGTH (FT)		-	221	-	-	-	-	283	90	-	85	-	-	-	-	-	12
		AREA (SQ FT)		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
		REMOVAL AREA (SQ FT)		-	110.5	-	-	-	-	283	45	-	28.3333	-	-	-	-	-	6



# BASE BID

NO.	HIGHWAY	INTERSECTION	2023 SPRAY THERMOPLASTIC		
			LF	LF	EA
			4" SW	4 " S.Y.	4" SW SKIPS
<b>BASE BID</b>					
3	WARRENVILLE RD.	NAPERVILLE RD to FINLEY RD	22725	49305	834
8	YORK RD (NORTH)	DEVON TO IL 19	59484	27898	436
9	LEMONT ROAD	83rd St. to TIMBER TRAIL/ HERITAGE PKWY	2000	9700	225
15	CASS AVENUE	PLAINFIELD to 91ST ST	8400	22410	433
21	FABYAN PARKWAY	IL 38 TO WEST COUNTY LINE	11900	14026	
25	MEYERS ROAD	IL 38 (ROOSEVELT) to IL 56 (BUTTERFIELD)		14520	288
28	WOODDALE ROAD	SUNSET DR. TO LAKE ST.	17487	21234	
33	75TH ST	LYMAN AVE TO E OF OLYMPUS	28910	66700	2216
43	COUNTY FARM RD.	N. OF KELLY DRIVE TO ARMY TRAIL ROAD		1260	30
43	COUNTY FARM RD.	NORTH AVE. TO ROOSEVELT RD.		56220	847
		<b>TOTAL</b>	<b>150906</b>	<b>283273</b>	<b>5309</b>
		LENGTH (FT)	150906	283273	53090
		AREA (SQ FT)	-	-	-
		REMOVAL AREA (SQ FT)	50302	94424.3333	17696.67



**ALTERNATIVE A**

			2023 PAVEMENT MARKING REMOVE AND REPLACE - URETHANE ON CONCRETE														
NO.	HIGHWAY	INTERSECTION	LF	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	SF
			24" S.W	12" S.W.	8" SW	6" SW XW	6" SW TURN.	12" S.Y.	4" S.Y.	4" SW	6" DASHES	ARROWS	ONLYS	THRU ARR	COMB. ARRO	"SCHOOL"	MEDIAN NOSES
<b>ALT A</b>																	
2	FINLEY RD.	BRIDGE							1494	463							
9	HIGHLAND AVENUE	IL 56 TO SOUTH OF I-88	355	270	664		2074		1605	856		142	14	14			122
		<b>TOTAL</b>	<b>355</b>	<b>270</b>	<b>664</b>	<b>0</b>	<b>2074</b>	<b>0</b>	<b>3099</b>	<b>1319</b>	<b>0</b>	<b>142</b>	<b>14</b>	<b>14</b>	<b>0</b>	<b>0</b>	<b>122</b>
		<b>LENGTH (FT)</b>	355	270	664	-	2074	-	3099	1319	-	-	-	-	-	-	-
		<b>AREA (SQ FT)</b>	-	-	-	-	-	-	-	-	-	2215.2	291.2	161	-	-	122
		<b>REMOVAL AREA (SQ FT)</b>	710	270	442.6667	-	1037	-	1033	439.6667	-	2215.2	291.2	161	-	-	122

# ALTERNATIVE A

NO.	HIGHWAY	INTERSECTION	2023 SPRAY THERMOPLASTIC		
			LF	LF	EA
			4" SW	4" S.Y.	4" SW SKIPS
<b>ALT A</b>					
2	FINLEY RD.	BUTTERFIELD RD TO OGDEN RD.	4573	24544	501
8	MADISON ST.	55TH ST. to JOLIET RD.	11530	30354	
27	HIGH LAKE RD.	CREEKSIDE DR. TO PRINCE CROSSING RD.	6804	9932	
27	PRINCE CROSSING RD.	HIGH LAKE RD. to GENEVA RD.	5779	6620	
34	31ST STREET	HIGHLAND AVE. TO MEYERS RD.		12250	225
51	HERRICK ROAD	SO. OF BUTTERFIELD TO WARRENVILLE	12970	16500	
52	CROSS STREET	WARRENVILLE RD to US 34 OGDEN AVE		1700	
		<b>TOTAL</b>	<b>41656</b>	<b>101900</b>	<b>726</b>
		LENGTH (FT)	41656	101900	7260
		AREA (SQ FT)	-	-	-
		REMOVAL AREA (SQ FT)	13885.33333	33966.6667	2420

ALTERNATIVE B

NO.	HIGHWAY	INTERSECTION	2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																			
			LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.		
			24" S.W	12" S.W.	8" S.W.	6" SW CROSSWA LK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.		
<b>ALT B</b>																						
9	LEMONT ROAD	97TH to BLUFF RD.																				
18	MUNGER ROAD	BREWSTER CREEK	N				382													22		
18	MUNGER ROAD	BREWSTER CREEK	S				254			20	2	2								22		
18	MUNGER ROAD	1350 MUNGER ROAD	N																	52		
18	MUNGER ROAD	1350 MUNGER ROAD	S					230		17	2	2								22		
18	MUNGER ROAD	SCHIFERL	N					198		22	2	2								22		
18	MUNGER ROAD	SCHIFERL	S					204		21	2	2								27		
21	FABYAN PARKWAY	IL 38	S	35	87	250		625	572	50	4	4								12	516	
23	GARY AVE.	JEWELL RD. TO NORTH AVE.																				
38	63RD STREET	MARIANO'S ENT. TO MADISON STREET																				
38	63RD STREET	CASS AVENUE	N	38	155					8	2	2										
38	63RD STREET	CASS AVENUE	S	41	168			216		8	2	2									10	
38	63RD STREET	CASS AVENUE	W	37	168			206		29	2	2										
38	63RD STREET	CASS AVENUE	E	37	173			201		24	2	2										
54	SWIFT RD.	ST. CHARLES RD. TO COLLINS AVE.																				
59	FREEDOM DRIVE	WARRENVILLE RD TO I-88 SOUTH RAMP																				
		TOTAL		188	751	250	0	2516	0	572	199	20	20	0	0	0	0	0	0	179	526	
		LENGTH (FT)		188	751	250	-	2516	-	572	398	-	-	-	-	-	-	-	-	179	526	
		AREA (SQ FT)		-	-	-	-	-	-	-	312	416	-	-	-	-	-	-	-	-	-	
		REMOVAL AREA (SQ FT)		376	751	166.6667	-	1258	-	572	199	312	416	-	-	-	-	-	-	-	59.666667	526

**ALTERNATIVE B**

			2023 PAVEMENT MARKING REMOVE AND REPLACE - URETHANE ON CONCRETE															
NO.	HIGHWAY	INTERSECTION	LF	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	SF	
			24" S.W	12" S.W.	8" SW	6" SW XW	6" SW TURN.	12" S.Y.	4" S.Y.	4" SW	6" DASHES	ARROWS	ONLYS	THRU ARR	COMB. ARRO	"SCHOOL"	MEDIAN NOSES	
<b>ALT B</b>																		
18	MUNGER ROAD	BREWSTER CREEK	N				181			2051	2545	15	1	1			13	
18	MUNGER ROAD	BREWSTER CREEK	S														13	
18	MUNGER ROAD	1350 MUNGER ROAD	N														38	
18	MUNGER ROAD	1350 MUNGER ROAD	S														30	
18	MUNGER ROAD	SCHIFERL	N														42	
18	MUNGER ROAD	SCHIFERL	S														42	
		<b>TOTAL</b>		<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>181</b>	<b>0</b>	<b>0</b>	<b>2051</b>	<b>2545</b>	<b>15</b>	<b>1</b>	<b>1</b>	<b>0</b>	<b>0</b>	<b>178</b>
		LENGTH (FT)		-	-	-	-	181	-	-	2051	5090	-	-	-	-	-	-
		AREA (SQ FT)		-	-	-	-	-	-	-	-	234	20.8	11.5	-	-	-	178
		REMOVAL AREA (SQ FT)		-	-	-	-	90.5	-	-	683.6667	2545	234	20.8	11.5	-	-	178

**ALTERNATIVE B**

NO.	HIGHWAY	INTERSECTION	2023 REMOVAL ONLY						2023 NEW THERMOPLASTIC STRIPING ON ASPHALT										
			LF	LF	LF	EA.	EA.	EA.	LF	LF	LF	LF	EA	EA.	EA.	EA.	LF	EA	
			4" REM.	6" REM	12" REM	REM ARROW	REM ONLY	"SCHOOL"	NEW 12"	NEW 6" S.W.	NEW 24" S.W.	4"	RXR	"SCHOOL"	ARROW	ONLY	NEW 8" S.W.	6" DASH	
<b>ALT B</b>																			
18	MUNGER ROAD	BREWSTER CREEK	N													4	2		
		<b>TOTAL</b>		0	0	0	0	0	0	0	0	0	0	0	0	4	2	0	0
		LENGTH (FT)		-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
		AREA (SQ FT)		-	-	-	-	-	-	-	-	-	-	-	-	62.4	41.6	-	-
		REMOVAL AREA (SQ FT)		-	-	-	-	-	-	-	-	-	-	-	-	62.4	41.6	-	-

# ALTERNATIVE B

NO.	HIGHWAY	INTERSECTION	2023 SPRAY THERMOPLASTIC		
			LF	LF	EA
			4" SW	4 " S.Y.	4" SW SKIPS
<b>ALT B</b>					
9	LEMONT ROAD	97TH to BLUFF RD.	9400	26000	431
23	GARY AVE.	JEWELL RD. TO NORTH AVE.	3078	21528	285
38	63RD STREET	MARIANO'S ENT. TO MADISON STREET	7820	20488	413
54	SWIFT RD.	ST. CHARLES RD. TO COLLINS AVE.	8073	22314	
59	FREEDOM DRIVE	WARRENVILLE RD TO I-88 SOUTH RAMP	356	2220	86
		<b>TOTAL</b>	<b>28727</b>	<b>92550</b>	<b>1215</b>
		LENGTH (FT)	28727	92550	12150
		AREA (SQ FT)	-	-	-
		REMOVAL AREA (SQ FT)	9575.666667	30850	4050



ALTERNATIVE C

NO.	HIGHWAY	INTERSECTION	2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																		
			LF	LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	LF	LF
			24" S.W	12" S.W.	8" S.W.	6" SW CROSSWALK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.	
<b>ALT C</b>																					
7	ST. CHARLES RD.	NORTH AVE TO GRAY AVE (N)																		34	128
7	ST. CHARLES RD.	RIFORD RD. TO IL 53																			
8	MADISON ST.	NORRIS DR.	N																	70	81
8	MADISON ST.	63RD ST.	N																	50	42
8	MADISON ST.	CREEKSIDE CT.	S																	64	94
8	MADISON ST.	68TH ST.	N																	62	86
21	FABYAN PARKWAY	TECHNOLOGY BLVD	N	55																	
21	FABYAN PARKWAY	TECHNOLOGY BLVD	S	60																	
21	FABYAN PARKWAY	TECHNOLOGY BLVD	W	40	228		136	472		255	54	4	4								90
21	FABYAN PARKWAY	TECHNOLOGY BLVD	E	44				482			54	4	4								
		TOTAL		199	228	0	136	954	0	255	108	8	8	0	0	0	0	0	0	280	521
		LENGTH (FT)		199	228	-	136	954	-	255	216	-	-	-	-	-	-	-	-	280	521
		AREA (SQ FT)		-	-	-	-	-	-	-	124.8	166.4	-	-	-	-	-	-	-	-	-
		REMOVAL AREA (SQ FT)		398	228	-	68	477	-	255	108	124.8	166.4	-	-	-	-	-	-	93.333333	521

ALTERNATIVE C

NO.	HIGHWAY	INTERSECTION	2023 REMOVAL ONLY						2023 NEW THERMOPLASTIC STRIPING ON ASPHALT										
			LF	LF	LF	EA.	EA.	EA.	LF	LF	LF	LF	EA	EA.	EA.	EA.	EA.	LF	EA
			4" REM.	6" REM	12" REM	REM ARROW	REM ONLY	"SCHOOL"	NEW 12"	NEW 6" S.W.	NEW 24" S.W.	4"	RXR	"SCHOOL"	ARROW	ONLY	NEW 8" S.W.	6" DASH	
<b>ALT C</b>																			
21	FABYAN PARKWAY	TECHNOLOGY BLVD	E								94								
		<b>TOTAL</b>		<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>		<b>94</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
		LENGTH (FT)		-	-	-	-	-	-		94	-	-	-	-	-	-	-	-
		AREA (SQ FT)		-	-	-	-	-	-		-	-	-	-	-	-	-	-	-
		REMOVAL AREA (SQ FT)		-	-	-	-	-	-		94	-	-	-	-	-	-	-	-

# ALTERNATIVE C

NO.	HIGHWAY	INTERSECTION	2023 SPRAY THERMOPLASTIC		
			LF	LF	EA
			4" SW	4 " S.Y.	4" SW SKIPS
<b>ALT C</b>					
7	ST. CHARLES RD.	NORTH AVE TO GRAY AVE (N)	21934	23816	
7	ST. CHARLES RD.	RIFORD RD. TO IL 53	7748	13106	273
		<b>TOTAL</b>	<b>29682</b>	<b>36922</b>	<b>273</b>
		<b>LENGTH (FT)</b>	29682	36922	2730
		<b>AREA (SQ FT)</b>	-	-	-
		<b>REMOVAL AREA (SQ FT)</b>	9894	12307.3333	910

ALTERNATIVE D

NO.	HIGHWAY	INTERSECTION	2023 PAVEMENT MARKING REMOVE AND REPLACE - THERMOPLASTIC ON ASPHALT																			
			LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	
			24" S.W.	12" S.W.	8" S.W.	6" SW CROSSWA LK	6" SW TURN.	6" S.W. MISC.	12" S.W. MISC. HATCH	6" DASHES	ARROWS	ONLY'S	COMB. ARRO	THRU ARR	"SCHOOL"	R X R	BIKE	4" S.W.	4" S.Y.	12" S.Y.		
<b>ALTD</b>																						
8	YORK RD (NORTH)	DEVON AVE	S	38					398				12	2	2						56	
8	YORK RD (NORTH)	S OF DEVON TO PAN AM BLVD												5	5							
8	YORK RD (NORTH)	PAN AM BLVD	S					152						1	1					103	28	
8	YORK RD (NORTH)	SUPREME DR.	S																			
8	YORK RD (NORTH)	I-390 DEVELOPMENT	S					159					16	2	1					82	627	
8	YORK RD (NORTH)	THORNEDALE	N	33																160	1139	
8	YORK RD (NORTH)	THORNEDALE	S	46				598					48	4	4					92	227	
8	YORK RD (NORTH)	FOSTER AVE.	N	187				102					18	1	1				4	86	50	
8	YORK RD (NORTH)	FOSTER AVE.	S	38				208						2	2							
8	YORK RD (NORTH)	FOSTER AVE.	W	23																		
8	YORK RD (NORTH)	BEELINE DR.	N											3	3							
8	YORK RD (NORTH)	BEELINE DR.	S					152					14	5	4							
8	YORK RD (NORTH)	GATEWAY RD.	S											11								
8	YORK RD (NORTH)	LOGISTICS PLUS ENT	S																			
8	YORK RD (NORTH)	IL 19	N																			
9	LEMONT ROAD	97TH / WESTGATE	N	36				309					16	2	2							
9	LEMONT ROAD	97TH / WESTGATE	S	36				127					24	2	1							
9	LEMONT ROAD	101ST ST	N	39	260		147	242					20	2	1							
9	LEMONT ROAD	101ST ST	S	33				145					17	2	1				2			
9	LEMONT ROAD	SPEEDWAY	N		91	104		83					20	1	1						144	
9	LEMONT ROAD	SPEEDWAY	S																			
9	LEMONT ROAD	103RD ST	S					150					13	2	1						62	
9	LEMONT ROAD	INTERNATIONALE PKWY	N	45				377					36	3	3						60	
9	LEMONT ROAD	INTERNATIONALE PKWY	W	35																		
9	LEMONT ROAD	INTERNATIONALE PKWY	E	35																		
9	LEMONT ROAD	INTERNATIONALE PKWY	S	30				275					14	2	2							
9	LEMONT ROAD	NAPLES LN	N					110					14	1	1							
9	LEMONT ROAD	NAPLES LN	S					100					16	1	1						90	
9	LEMONT ROAD	DAVEY RD	N	55				402					48	3	3							
9	LEMONT ROAD	DAVEY RD	W	28																		
9	LEMONT ROAD	DAVEY RD	S	35				252					26	2	2						86	
9	LEMONT ROAD	109TH ST	N																		67	
9	LEMONT ROAD	109TH ST	S					82					11	1	1							
9	LEMONT ROAD	TEMPLE	N					233					29	2	2							
9	LEMONT ROAD	TEMPLE	S																			
9	LEMONT ROAD	BLUFF RD	N					120					15	1	1							
28	WOODDALE ROAD	MONTROSE AVE	N		102			152					44	2	1							
28	WOODDALE ROAD	MURRAY DR	N														1				42	20
28	WOODDALE ROAD	MURRAY DR	S		68																	
28	WOODDALE ROAD	ELIZABETH DR	N	22				159					10	2	1				1			
28	WOODDALE ROAD	ELIZABETH DR	S	22																		
28	WOODDALE ROAD	ELIZABETH DR	E	12																		
28	WOODDALE ROAD	ELIZABETH DR	W	12																		
28	WOODDALE ROAD	OAK MEADOWS DR	N	22				168					15	2	1							
28	WOODDALE ROAD	OAK MEADOWS DR	S	23				179					14	2	1							
28	WOODDALE ROAD	OAK MEADOWS DR	E	21																	47	
38	63RD STREET	RIDGE ROAD	N	18	89																	
38	63RD STREET	RIDGE ROAD	S	15	98																	
38	63RD STREET	RIDGE ROAD	W	36	149			190					22	2	2							
38	63RD STREET	RIDGE ROAD	E	35				202					22	2	2							
38	63RD STREET	CLARENDON HILLS	N	37																		
38	63RD STREET	CLARENDON HILLS	S	28																		
38	63RD STREET	CLARENDON HILLS	W	36				178					21	2	1							
38	63RD STREET	CLARENDON HILLS	E	39				190					21	2	1					84	102	
38	63RD STREET	CANTERBERRY	W											4								
38	63RD STREET	CANTERBERRY	E					99					21	1	1							
38	63RD STREET	AMERICANA DR	N	23																		
38	63RD STREET	AMERICANA DR	S	25	99																	
38	63RD STREET	AMERICANA DR	W	52	215			93	118				29	2	2					68	50	
38	63RD STREET	AMERICANA DR	E	58																15		
38	63RD STREET	BRENTON LAKES DR.	E																			
38	63RD STREET	MADISON STREET	W	26				229					23	4	4							
		TOTAL		1334	1171	104	147	6615	118	0	669	90	63	0	0	2	8	0	0	732	2855	
		LENGTH (FT)		1334	1171	104	147	6615	118	-	1338	-	-	-	-	-	-	-	-	-	732	2855
		AREA (SQ FT)		-	-	-	-	-	-	-	-	1404	1310.4	-	-	64.6	489.6	-	-	-	-	-
		REMOVAL AREA (SQ FT)		2668	1171	69.33333	73.5	3307.5	59	-	669	1404	1310.4	-	-	64.6	489.6	-	-	-	244	2855

**ALTERNATIVE D**

			2023 PAVEMENT MARKING REMOVE AND REPLACE - URETHANE ON CONCRETE															
NO.	HIGHWAY	INTERSECTION		LF	LF	LF	LF	LF	LF	LF	EA.	EA.	EA.	EA.	EA.	EA.	SF	
				24" S.W	12" S.W.	8" SW	6" SW XW	6" SW TURN.	12" S.Y.	4" S.Y.	4" SW	6" DASHES	ARROWS	ONLYS	THRU ARR	COMB. ARRO	"SCHOOL"	MEDIAN NOSES
<b>ALT D</b>																		
8	YORK RD (NORTH)	PAN AM BLVD	S					183			17	1	1					
8	YORK RD (NORTH)	SUPREME DR.	S					211			15	1	1					
8	YORK RD (NORTH)	BEEELINE DR.	S														148	
8	YORK RD (NORTH)	GATEWAY RD.	S		56	370							2	2				
8	YORK RD (NORTH)	LOGISTICS PLUS ENT	S		50	426					13	1	1					
8	YORK RD (NORTH)	IL 19	N	64	96	601		1834		2121	540	178	10	8			15	
38	63RD STREET	AMERICANA DR	W														50	
38	63RD STREET	AMERICANA DR	E	51	48	225	225	225			26	2	2					
38	63RD STREET	BRENTON LAKES DR.	E					91	34		34	1	1					
		<b>TOTAL</b>		115	250	1622	225	2544	0	34	2121	572	253	18	14	0	0	213
		<b>LENGTH (FT)</b>		115	250	1622	225	2544	-	34	2121	1144	-	-	-	-	-	
		<b>AREA (SQ FT)</b>		-	-	-	-	-	-	-	-	3946.8	374.4	161	-	-	213	
		<b>REMOVAL AREA (SQ FT)</b>		230	250	1081.333	112.5	1272	-	11.33333	707	572	3946.8	374.4	161	-	-	213

**ALTERNATIVE D**

NO.	HIGHWAY	INTERSECTION	2023 REMOVAL ONLY							2023 NEW THERMOPLASTIC STRIPING ON ASPHALT									
			LF	LF	LF	EA.	EA.	EA.	LF	LF	LF	LF	EA	EA.	EA.	EA.	LF	EA	
			4" REM.	6" REM	12" REM	REM ARROW	REM ONLY	"SCHOOL"	NEW 12"	NEW 6" S.W.	NEW 24" S.W.	4"	RXR	"SCHOOL"	ARROW	ONLY	NEW 8" S.W.	6" DASH	
<b>ALT D</b>																			
9	LEMONT ROAD	INTERNATIONALE PKWY	W	153															
38	63RD STREET	CLARENDON HILLS	N		138						189								
38	63RD STREET	CLARENDON HILLS	S		104						150								
38	63RD STREET	BRENTON LAKES DR.	E																33
38	63RD STREET	MADISON STREET	W		46														
		<b>TOTAL</b>		<b>153</b>	<b>288</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>		<b>339</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>33</b>
		<b>LENGTH (FT)</b>		<b>153</b>	<b>288</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>		<b>339</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>66</b>
		<b>AREA (SQ FT)</b>		<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>		<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>
		<b>REMOVAL AREA (SQ FT)</b>		<b>51</b>	<b>144</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>		<b>339</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>33</b>



**STATE OF ILLINOIS**

**SPECIAL PROVISIONS**

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction", adopted January 1, 2022, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways", the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids and the "Supplemental Specifications and Recurring Special Provisions" indicated on the Check Sheet included herein which apply to and govern the proposed improvement designated as Section **23-PVMKG-11-GM**, and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

**DESCRIPTION OF WORK**

This contract includes two separate categories of pavement marking installation for markings on County Highways and other locations as directed by the Engineer.

PRESCRIBED LOCATIONS ("PL") pavement markings include identified project locations that the DuPage County Division of Transportation (DCDOT) intends to install under this project. These quantities are described as PL throughout the bidding documents. PL pavement markings are subject to a completion date as specified and the Contractor will be required to install complete markings throughout the indicated segments concluding at logical termini along the county highways. The project quantities are estimates and reflect the conditions observed by the Engineer at the time the bid documents were prepared. Any adjustments to quantities to add or include work areas that are located at or adjacent to the work sites listed in the PL quantity tables will be paid at pay item unit prices.

LOCATIONS ON REQUEST ("LOR") pavement markings include nominal quantities for unanticipated or unprescribed locations throughout the County Highway system that will be requested by the Engineer for on-demand installation. These quantities are described as LOR or throughout the bidding documents. LOR pavement markings are generally used to restore pavement markings damaged by highway maintenance or isolated areas where markings have worn prematurely. This work is subject to a unique completion date as specified and the Contractor will be required to mobilize and install the markings upon request of the Engineer according to the terms included in the Special Provision and General Notes herein. The quantities included are nominal and will be adjusted by the Engineer as required to meet the needs of the DCDOT. Any adjustments to quantities performed under LOR terms will be paid at pay item unit prices.

**BIDDING DETAILS**

This contract is subject to *shared services* clause. If the contractor agrees to provide *shared services* by agreeing to the attached *special provision*, the shared services pricing offered to all participating municipalities will be pay item unit price pricing provided that the contract is approved by the municipality prior to June 1, 2023.

This contract includes Added Alternate Bidding subject to the Special Provision included herein.



**BIDDING REQUIREMENTS AND CONDITIONS FOR CONTRACT PROPOSALS**

(Illinois Department of Transportation Bureau of Local Roads and Streets Special Provision for BIDDING REQUIREMENTS AND CONDITIONS FOR CONTRACT PROPOSALS LRS Check Sheet #6)

Add the following to the section **Prequalification of Bidders**: “Prequalification is required. The Certificate of Eligibility shall be accompanied by a Request for Authorization to Bid form completed by the prospective bidder. The Certificate of Eligibility and Request for Authorization to Bid shall be submitted at least one business day prior to the public opening of proposals. Authorization to bid will be issued by the DuPage County Division of Transportation to prospective bidders who are qualified to perform the work, as evidenced by the Certificate of Eligibility.”

Revise the first sentence of the section **Preparation of the Proposal** to read: "Bidders shall submit their proposals on the form furnished by the Awarding Authority or on a form approved by the Awarding Authority prior to submittal of the Proposal."

Add the following to the section **Preparation of the Proposal**: "Unit prices shall only be accepted rounded to the nearest one-hundredth (0.01) of a dollar."

Add the following to the section **Preparation of the Proposal**: “The low bidder shall complete and submit the IRS W-9 form included in this proposal within 48 hours of being notified as the low bidder. The form shall be emailed to Department at [DOTBidInfo@dupageco.org](mailto:DOTBidInfo@dupageco.org). All bidders may either submit the W-9 form with their bid proposal or wait to be notified that they are the low bidder.

Add the following to the section **Public Opening of Proposals**: “Proposals will only be accepted by bidders who have been issued an authorization to bid by the DuPage County Division of Transportation. Proposals submitted without authorization to bid will be returned unopened.”

Add the following to after the first sentence of the section **Consideration of Proposals**: “If the Proposal includes quantities and unit prices for multiple agencies, then the summation to be compared shall include all items and not just the items for a single agency.”

**ADDED ALTERNATIVE BIDDING**

Added Alternative Bidding: The DCDOT desires to maximize the available budget for this maintenance project. To accomplish this, project locations and quantities have been divided into a Base Bid (minimum project) and Added Alternatives A, B, and C. The Added Alternatives are prioritized from A to C with A being the highest priority.

A Contract Award Limit of \$500,000 has been designated for the 2023 Pavement Marking Maintenance project. As the Base Bid is the minimum project to be awarded, DCDOT will not award any contracts with a base bid greater than the Contract Award Limit.

For this maintenance project, the Contractor shall submit the same unit price for identical pay items, i.e. pay items with the same pay code. For example if the Contractor submits a unit price of \$1.25 per gallon for PROTECTIVE COAT for the Base Bid, he/she shall use the same unit price of \$1.25 per gallon for PROTECTIVE COAT in each of the Added Alternatives. Bid proposals submitted with different unit prices will be rejected.

The Contractor shall submit unit prices / bids for all pay items included in the Base Bid and all Added Alternatives. Incomplete bids will be considered not responsive and will not be read.

The final bid tabulation will evaluate all bids based on the base bid and the alternatives to be included in the project. Alternatives not included in the project will not be included in the bid tabulation.

**ADD ALTERNATIVE BIDDING – LOW BIDDER DETERMINATION EXAMPLES**

Effective: April 1, 2011

For this project the low bidder will be determined using the process shown in the following examples:

**Example 1:** In this example the Contracting Authority desires to maximize the \$2,000,000 that it has available for the project. The project location and/or quantities have been divided into a Base Bid, and Added Alternatives A, B, and C. A Contract Award Limit of **\$2,000,000** has been designated.

The following bids were received:

Bidder	Base Bid	Bid on Added Alternative A	Bid on Added Alternative B	Bid on Added Alternative C
Contractor 1	\$1,500,000	\$325,000	\$150,000	\$300,000
Contractor 2	\$1,600,000	\$250,000	\$50,000	\$300,000
Contractor 3	\$1,600,000	\$100,000	\$200,000	\$200,000
Contractor 4	\$1,800,000	\$150,000	\$150,000	\$50,000

The first basis for award is the bidder submitting a bid with the most Added Alternatives (in order of priority) not exceeding the Contract Award Limit (\$2,000,000). In the example above, Contractors 1, 2 & 3 submitted bids that included the Base Bid and Added Alternatives A and B which do not exceed \$2,000,000. Contractor 4 will not be considered further because he/she submitted a bid in which the Base Bid and only Added Alternative A is less than \$2,000,000 (i.e. Contractor 4 submitted a bid with fewer options not exceeding the Contract Award Limit).

The next basis for award is the lowest bid submitted (not exceeding the Contract Award Limit) with the Base Bid and the same Added Alternative(s). In this example the Contractor’s combined bids for the Base Bid and Added Alternatives A and B are:

Bidder	Combined Bid	<b>Contractor 2’s bid of \$1,900,000 is the low bid</b>
Contractor 1	\$1,975,000	
Contractor 2	\$1,900,000	
Contractor 3	\$2,000,000	

In this example above it makes no difference that:

- Contractor 1 is the low bidder on the Base Bid only – because Added Alternatives A & B can be added to 1 or more of the Contractor’s bids and the resulting combined bid does not exceed the Contract Award Limit they must be included.

SPECIAL PROVISIONS  
2023 PAVEMENT MARKING MAINTENANCE  
SEC. 23-PVMKG-11-GM

- Contractor 3 is the low bidder on the Base Bid and Added Alternative A – because Added Alternative B can also be added to 1 or more of the Contractor’s bids and the resulting combined bid does not exceed the Contract Award Limit it must be included.
- Contractor 4 is the low bidder on the Base Bid plus all Added Alternatives – because Contractor 4’s total bid for the Base Bid and all the Added Alternatives exceeds the Contract Award Limit it cannot be considered.

**Example 2:** In this example the Contracting Authority desires to maximize the \$200,000 that it has available for a maintenance project. The project location(s) and/or quantities have been divided into a Base Bid, and Added Alternatives A, B, and C. A Contract Award Limit of **\$200,000** has been designated.

The following bids were received:

<b>Bidder</b>	<b>Base Bid</b>	<b>Bid on Added Alternative A</b>	<b>Bid on Added Alternative B</b>	<b>Bid on Added Alternative C</b>
<b>Contractor 1</b>	<b>\$165,000</b>	<b>\$50,000</b>	<b>\$15,000</b>	<b>\$15,000</b>
<b>Contractor 2</b>	<b>\$160,000</b>	<b>\$55,000</b>	<b>\$25,000</b>	<b>\$15,000</b>
<b>Contractor 3</b>	<b>\$170,000</b>	<b>\$35,000</b>	<b>\$20,000</b>	<b>\$15,000</b>
<b>Contractor 4</b>	<b>\$180,000</b>	<b>\$30,000</b>	<b>\$15,000</b>	<b>\$15,000</b>

Like the previous example the first basis for award is the bidder submitting a bid with the most Added Alternatives (in order of priority) not exceeding the Contract Award Limit (\$200,000). In this example, all of the combined submittals for the Base Bid plus Added Alternative A are more than \$200,000. Therefore, Added Alternative A is ignored and will not be included in the contract. The bid comparison shifts to the sum of the Base Bid and Added Alternative B for which all of the Contractors submitted a bid that is less than the \$200,000 limit. The comparison continues by adding in Added Alternative C. Contractors 1 & 2 submitted bids for the Base Bid and Added Alternatives B and C which do not exceed \$200,000.

The next basis for award is the lowest bid submitted (not exceeding the Contract Award Limit) with the Base Bid and the same Added Alternative(s). In this example the Contractor’s combined bids for the Base Bid and Added Alternatives B and C are:

<b>Bidder</b>	<b>Combined Bid</b>	<b>Contractor 1’s bid of \$195,000 is the low bid</b>
<b>Contractor 1</b>	<b>\$195,000</b>	
<b>Contractor 2</b>	<b>\$200,000</b>	

**SECTION 107 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC**

Article 107.20 Protection and Restoration of Property. Add the following after the first paragraph of this Article:

“The Contractor shall maintain conveyance of all flows during construction of this project. When existing drainage facilities are disturbed, the Contractor shall provide and maintain temporary inlets, outlets, and connections for all private and public drains, sewers, culverts, and other drainage facilities. The Contractor shall provide facilities to take in all storm water which will be received by these drains and sewers, and discharge the same. The Contractor shall provide and maintain a pumping plant, if necessary, and a temporary outlet and be prepared at all time to dispose of water received from these temporary connections until such time that the permanent drainage facilities are in service.”

Revise the last paragraph of this Article to read:

“The cost of all materials and equipment required and all labor necessary to comply with the above Provisions will not be paid for separately, but shall be considered as included in the unit bid prices of the contract, and no additional compensation will be allowed.”

Article 107.26 Indemnification. In addition to the requirements of this Article, for any activity occurring on an easement or any other property not owned by the Department, the indemnification shall also be extended to the property owners and any tenants thereon.

Article 107.27 Insurance. In addition to the requirements of this Article, the policies of insurance for Commercial (Comprehensive) General Liability and Commercial (Comprehensive) Automobile Liability shall include an additional insured endorsement naming the County of DuPage, its officers and employees as additional insureds. The endorsements shall be on forms acceptable to the County of DuPage. This additional insured is to be on a primary and non-contributory basis and include a Waiver of Subrogation endorsement.

Employer’s Liability insurance shall be in an amount not less than one million (\$1,000,000.00) dollars each accident/injury and one million (\$1,000,000.00) dollars each employee/disease.

Limits of Umbrella Excess Liability (over primary) shall not be less than an amount that in combination with Commercial General Liability totals \$6,000,000 of liability insurance per occurrence. The Umbrella Excess Liability Policy shall include in the “Who is Insured” pages of the policy wording such as “Any other person or organization you have agreed in a written contract to provide additional insurance” or wording to that affect. The contractor shall provide a copy of said section of the excess/umbrella liability policy upon request by the County of DuPage.

The Contractor shall require all subcontractors to maintain the same insurance coverage required of the contractor. The County of DuPage retains the right to obtain evidence of subcontractor insurance coverage at any time.

Replace the second sentence of the second paragraph (third to last paragraph) of this article with the following: “It is the duty of the Contractor to immediately notify the County of DuPage if any insurance required under this contract has been cancelled, materially changed, or renewal has been refused, and the Contractor shall immediately suspend all work in progress and take the necessary steps to purchase, maintain and provide the required insurance coverage. If a suspension of work should occur due to insurance requirements, upon verification by the County of DuPage of the required insurance coverage, the County of DuPage shall notify the Contractor that the Contractor can proceed with the work that is a part of this contract. Failure to provide and maintain the required insurance coverage could result in the immediate cancellation of this contract, and the Contractor shall accept and bear all costs that may result from the cancellation of this contract due to Contractor's failure to provide and maintain the required insurance.”

Article 107.36 Dust Control. Add the following to the second paragraph of this article:

“The Contractor will be required to have available a water truck or similar equipment to control dust. If necessary, the Contractor shall be required to control dust during non-working hours.”

## **SECTION 108 PROSECUTION AND PROGRESS**

Article 108.03 Prosecution of the Work. Revise the first sentence of this Article to read, "The Contractor shall not begin the work to be performed under the contract without written authorization from the DuPage County Division of Transportation to proceed with the work, and shall commence work not later than 10 days after receiving the authorization to proceed.”

This contract shall be subject to liquidated damages as described in Section 108 according to the completion date defined in the “COMPLETION DATE REQUIREMENT” Special Provision.

#### **SECTION 109 MEASUREMENT AND PAYMENT**

Article 109.08 Acceptance and Final Payment. Add the following to this Article: “Prior to final payment, an affidavit from the Contractor will be required.”

#### **SECTION 671 MOBILIZATION**

Article 671.02 Basis of Payment. Revise this article to read: “Basis of Payment. This work will not be paid for separately, but shall be included in the various items of work.”

#### **SECTION 1105 PAVEMENT MARKING EQUIPMENT**

Delete the last sentence of Article 1105.01(b).

#### **CALENDAR DAY REQUIREMENTS**

This specification will address the completion day requirements of the project:

**PL** –The Contractor is required to complete all the work described herein as prescribed locations by **Friday, August 11, 2023 at 5pm CST**. Failure to complete the work by the date stated above will result in liquidated damages per Article 108.09 of the Standard Specifications.

**LOR** –The Contractor is required to complete all assigned LOR by **Thursday, November 30, 2023 at 5pm CST**. Failure to complete the work by the date stated above will result in liquidated damages per Article 108.09 of the Standard Specifications.

#### **TRAFFIC CONTROL AND PROTECTION**

Description. The traffic control and protection for this project shall be performed in accordance with the project Traffic Control Plan and Section 701 of the Standard Specifications as amended by the Special Provision for Work Zone Traffic Control (Illinois Department of Transportation Check Sheet #LRS 3).

The furnishing, placing, and removal of material, or any temporary concrete barrier and impact attenuators, not shown on the plans but required in order to meet the drop off requirements, shall be included in the unit price of the associated pay items for MARKING, MARKING REMOVAL, and MARKER, of the type specified and for the applicable PL or LOR work category.

The cost of supplying, erecting, and maintaining barricades, warning lights, and signs will be included in the unit price of the associated pay items for MARKING, MARKING REMOVAL, and MARKER, of the type specified and for the applicable PL or LOR work category.

Method of Measurement. Traffic control will not be measured by location or per Standard.

Basis of Payment. The cost of Traffic Control and Protection provided under the Traffic Control Plan and Section 701 WORK ZONE TRAFFIC CONTROL will not be paid for separately but will be included in the unit price of the associated pay items for MARKING, MARKING REMOVAL, and MARKER, of the type specified and for the applicable PL or LOR work category. No additional payment shall be made for traffic control and protection under this contract.

**TRAFFIC CONTROL PLAN**

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall notify the Engineer at least 72 hours in advance of beginning work.

- 701101-05 Off-Road Operations, Multilane, 15' (4.5 m) to 24' (600 mm) From Pavement Edge
- 701106-02 Off-Road Operations, Multilane, More Than 15' (4.5 m) Away
- 701421-08 Lane Closure, Multilane, Day Operations Only, for Speeds > 45 MPH to 55 MPH
- 701422-10 Lane Closure, Multilane, for Speeds > 45 MPH to 55 MPH
- 701501-06 Urban Lane Closure, 2L, 2W, Undivided
- 701601-09 Urban Lane Closure, Multilane, 1W or 2W with Nontraversable Median
- 701606-10 Urban Single Lane Closure, Multilane, 2W with Mountable Median
- 701701-10 Urban Lane Closure, Multilane Intersection
- 701801-06 Sidewalk, Corner or Crosswalk Closure
- 701901-08 Traffic Control Devices

**DETAILS:**

- TC-10 Traffic Control And Protection For Side Roads, Intersections, And Driveways
- TC-14 Traffic Control And Protection At Turn Bays (To Remain Open To Traffic)
- TC-16 Pavement Marking Letters And Symbols For Traffic Staging

**SPECIAL PROVISIONS:**

- PUBLIC CONVENIENCE AND SAFETY
- TRAFFIC CONTROL AND PROTECTION (SPECIAL)
- MAINTENANCE OF ROADWAYS

**RECESSED REFLECTIVE PAVEMENT MARKERS**

Description. This work shall consist of setting reflective pavement markers in a recessed groove in the pavement. The recessed pavement markers shall be used to supplement other pavement markings, similar to the use of Raised Reflective Pavement Markers.

Materials. The reflective pavement marker shall be listed on the Illinois Department of Transportation approved list of snowplowable raised pavement markers, or Engineer approved equivalent, and be compatible with the reflector holder. The reflector holder shall be a MarkerOne Series R100 reflector holder or Engineer approved equivalent. The epoxy used shall be as recommended by the pavement marker manufacturer.

Installation. Spacing and orientation of the pavement markers shall be as detailed in the plans or as directed by the Engineer.

A recessed groove shall be cut in the pavement 5.25" wide, 0.9" deep on a 15.5" diameter. An additional 3.5' long groove shall taper from 0" (normal pavement) to 0.3" depth (full-recessed).

The recessed area shall be cleaned free of all loose material, and dry before the placement of the pavement marker. All excess material resulting from the construction of the recessed area shall be completely removed from the surface of the roadway by means of vacuum sweeper truck. The pavement marker shall be cemented with epoxy in the center of the 0.9" deep recessed groove.

Inspection. A straight edge shall be placed across the recess to check that the top of the marker is below the pavement. Inspection and acceptance shall be according to Article 781.04 of the Standard Specifications.

Basis of Payment. This work will be paid for at the contract unit price each for RECESSED REFLECTIVE PAVEMENT MARKER.

**45 MIL HOT SPRAY THERMOPLASTIC PAVEMENT MARKING**

This work shall consist of furnishing and applying spray thermoplastic pavement marking lines, sizes and colors as shown on the plans. The material shall be a mixture of resins and other materials providing an essentially nonvolatile thermoplastic compound especially developed for traffic markings. Spray thermoplastic pavement markings shall be applied only by contractors "approved" or "conditionally approved" for HAND OPERATED APPLICATION ONLY or for TRUCK OR HAND APPLICATION, on the list of Approved Thermoplastic Contractors maintained by the IDOT Engineer of Operations and in effect on the date of advertisement for bids.

**Ingredient Materials:**

- (a) Binder. The binder shall consist of a mixture of synthetic resins, at least one of which is solid at room temperature. The total binder content of the thermoplastic compound shall be well distributed throughout the compound. The binder shall be free from all foreign objects or ingredients that would cause bleeding, staining or discoloration. The binder shall be 25 percent minimum by weight of the thermoplastic compound. The binder shall be characterized by an "IR Spectra". Future shipments of binder will be checked by an "IR Spectra" to verify that the binder has not been changed.

- (b) Pigment. The pigment used for the white thermoplastic compound shall be a highgrade pure (minimum 93 percent) titanium dioxide (TiO<sub>2</sub>). The white pigment content shall not be less than 10 percent by weight and shall be uniformly distributed throughout the thermoplastic compound.

The pigments used for the yellow thermoplastic compound shall be heat resistant, and color-fast yellows, golds and oranges, which shall produce a compound meeting the requirements of the current Federal Highway Color Tolerance Chart, PR Color No. 1. The medium chrome yellow pigment content shall be not less than 4 percent by weight and shall be uniformly distributed throughout the thermoplastic compound.

- (c) Filler: The filler to be incorporated with the resins as a binder shall be a white calcium carbonate, silica, or an approved substitute. Any filler, which is insoluble in 6N hydrochloric acid, shall be of such particle size as to pass a No. 100 (150 µm) sieve.

- (d) Glass Beads.

(1) Scope:

This specification covers glass beads to be used for reflectorizing pavement marking lines.

Type A – uncoated

Type B - moisture resistant, silicone coated

Type A shall be used as intermix beads with thermoplastic pavement marking materials. They shall be uniformly mixed throughout the material at the rate of not less than 25 percent by weight (retained on the No. 100 (150 µm) sieve) of thermoplastic compound. Type B shall be used as drop-on beads with thermoplastic pavement marking materials and shall be applied uniformly at a minimum rate of 6 pounds per 100 square feet (2.9 kilograms per 10 square meters).

(2) Properties:

The glass beads furnished under this specification shall consist essentially of transparent, water-white glass particles of a spherical shape. They shall be manufactured from a glass of a composition designed to be highly resistant to traffic wear and to the effects of weathering. The glass beads shall conform to the following requirements:

- (a) Sieve Analysis. The glass beads shall meet the following sieve requirements:

Total Percent (By Weight)	
<u>Sieve Size</u>	<u>Passing</u>
No. 20 (850 µm)	100
No. 30 (600 µm)	75 - 100
No. 50 (300 µm)	15 - 40
No. 100 (150 µm)	0 - 5
No. 200 (75 µm)	0 - 1

- (b) Imperfections. The surface of the glass beads shall be free of pits and scratches. The glass beads shall be spherical in shape and shall contain no more than 20 percent by weight of irregular shapes when tested by the standard method using a vibratile inclined glass plate as adopted by the Department.



- (c) Index of Refraction. The index of refraction of the glass beads shall be not less than 1.50 when tested by the immersion method at 77 °F (25 °C).
- (d) Silica Content. The glass beads shall contain not less than 65 percent silica (SiO<sub>2</sub>).
- (e) Chemical Stability. Glass beads which show a tendency toward decomposition, including surface etching, when exposed to paint or thermoplastic constituents will be rejected. The glass beads shall be tested by Federal Specification TT-B-1325B, Section 4.3.9 (water resistance) and evaluated for compliance with Section 3.2.9, with the following exceptions:

The size of the sample to be tested shall be 25 grams and the reflux time shall be 5 hours.

- (f) Flowing Properties. The glass beads shall flow uniformly through dispensing equipment in atmospheric humidity up to 94%.

Intermix beads shall pass the following test: One hundred grams of glass beads, spread evenly and thinly in a suitable container, shall be conditioned at 77 °F (25 °C) for 4 hours over a solution of sulfuric acid (Sp. Gr. 1.10) in a closed desiccator. After 4 hours, the glass beads shall flow readily through a clean glass analytical funnel, 60°, 75 mm diameter and 105 mm stem. Inside diameter of the stem shall be a nominal 1/4 inch (6.35 mm).

The drop-on beads shall have a silicone, moisture resistant coating and pass the following test: One hundred grams of beads are placed in a 600 ml beaker and an equivalent volume of distilled water shall be added to the beaker. The beaker will then stand for 5 minutes, at the end of which time the water shall be carefully poured off and the beads transferred to a clean dry beaker and allowed to stand for 5 minutes. The beads will then be poured slowly into a standard glass funnel (Corning 6120), 127 mm diameter, 102 mm stem length and 11 mm stem inside diameter.

The beads shall flow through the funnel stem without stoppage. Slight initial agitation to start the flow through the funnel at the beginning of the test is permissible.

- (g) Packaging. The Type B glass beads shall be delivered in approved moisture proof bags consisting of a least five-ply paper construction unless otherwise specified. Each bag shall contain 50 pounds (22.7 kg) net, and shall be legibly marked with the manufacturer, specifications and type, lot number, and the month and year the glass beads were packaged.

Thermoplastic Compound:

- (a) Characteristic Requirements:

- (1) In the plastic state, the material shall not give off fumes that are toxic or otherwise injurious to persons or property. The manufacturer shall provide material safety data sheets for the product.

SPECIAL PROVISIONS  
2023 PAVEMENT MARKING MAINTENANCE  
SEC. 23-PVMKG-11-GM

- (2) The temperature versus viscosity characteristic of the plastic material shall remain constant and the material shall not deteriorate in any manner during reheating processes.
- (3) There shall be no obvious change in color of the material as a result of repeated heating or from batch to batch. The maximum elapsed time after application after which normal traffic will leave no impression or imprint on the new stripe shall be 30 seconds when the air and road surface temperature is approximately  $70 \pm 3$  °F ( $21 \pm 2$  °C). After application and proper drying, the material shall show no appreciable deformation or discoloration, shall remain free from tack, and shall not lift from the pavement under normal traffic conditions within a road temperature range of -20 to 150 °F (-28.9 to 65.6 °C). The stripe shall maintain its original dimensions and placement.

Cold ductility of the material shall be such as to permit normal dimensional distortion as a result of traffic impact within the temperature range specified.

- (4) The material shall provide a stripe that has a uniform thickness throughout its cross section and has the density and character to provide a sharp edge of the line.
- (5) The thermoplastic compound after heating for 4 hours  $\pm$  5 min. at  $375 \pm 3$  °F ( $190.6 \pm 2$  °C) and cooled at 77 °F (25 °C) shall meet the following requirements for daylight reflectance and color, when tested, using a color spectrophotometer with 45° circumferential / 0° geometry, illuminant C, and 2° observer angle. The color instrument shall measure the visible spectrum from 380 to 720 nm with a wavelength measurement interval and spectral bandpass of 10 nm.

White: Daylight Reflectance, 75 percent minimum

\*Yellow: Daylight Reflectance, 45 percent minimum

\*Shall match Federal Highway Color Tolerance Chart, PR Color No. 1.

- (6) Specific Gravity - the specific gravity of the thermoplastic material shall not exceed 2.15.
- (7) Softening Point - After heating the thermoplastic material for 4 hours  $\pm$  5 min. at  $375 \pm 3$  °F ( $190.6 \pm 2$  °C) and testing in accordance with ASTM E28, the material shall have a minimum softening point of 180 °F (82.2 °C) as measured by the ring and ball method.
- (8) Tensile Bond Strength - After heating the thermoplastic material for 4 hours  $\pm$  5 min. at 375 °F (190.6 °C), the tensile bond strength to unprimed, sandblasted portland cement concrete block, 0.0625 inch (1.587 mm) thick film drawn-down 375 °F (190.6 °C), tested at  $75 \pm 2$  °F ( $23.9 \pm 1$  °C) shall exceed 180 psi (1.24 Mpa) when tested in accordance with ASTM D4796-88.
- (9) Impact Resistance - After heating the thermoplastic material for 4 hours  $\pm$  5 min at  $375 \pm 3$  °F ( $190.6 \pm 2$  °C) the impact resistance shall be a minimum of 50 inch pounds (0.576 kilogram meters) with no cracks or bond loss when 0.0625 inch (1.587 mm) thick film drawdown is made at 375 °F (190.6 °C) on an unprimed sandblasted Portland cement concrete block, male indenter 5/8 inch (15.875 mm), no female Die, tested at  $75 \pm 2$  °F ( $23.9 \pm 1$  °C) when tested in accordance with ASTM D2794 minimum.
- (10) Yellowness Index - The white thermoplastic material shall not exceed a yellowness index of 12 when tested in accordance with ASTM D1925.

(b) Identification

Each package of material shall be stenciled with the manufacturer's name, the type of material and IDOT specification number, the month and year the material was packaged and lot number. Lot numbers must begin with the last two digits of the year manufactured and be sequential with Lot 1. The letters and numbers used in the stencils shall be a minimum of 1/2 inch (12.7 mm) in height.

(c) Packaging

The thermoplastic material shall be packaged in suitable containers that will not adhere to the product during shipment and storage. The container of thermoplastic material shall weigh approximately 50 lbs. (22.7 kg). Each container shall designate the color, binder (alkyd or hydrocarbon), spray and user information. The label shall warn the user that the material shall be heated in the range of 350 – 400 °F (177 – 204 °C).

(d) Storage Life

The material shall meet the requirements of this specification for a period of one year. The thermoplastic must also melt uniformly with no evidence of skins or unmelted particles for this one-year period. The manufacturer shall replace any material that does not meet the above requirements.

Sampling and Testing:

- (a) Unless otherwise provided, all materials shall be sampled and tested in accordance with the latest published standard methods of the American Society for Testing and Materials, and revisions thereof, in effect on the date of invitation for bids, where such standard methods exist. In case there are no ASTM Standards which apply, applicable standard methods of the American Association of State Highway Transportation Officials, or the Federal Government, or of other recognized standardizing agencies shall be used.
- (b) The right is reserved to inspect the material either at the place of manufacture or at the destination or at both places. If inspected at the place of manufacture, the manufacturer shall furnish such facilities as may be required for collecting and forwarding samples, and shall also furnish facilities for testing the material during the process of manufacture, if required. Tests will be made by and at the expense of the Department. All material samples for acceptance tests shall be taken or witnessed by a representative of the Bureau of Materials and Physical Research. All material samples shall be submitted to the Engineer of Materials and Physical Research, 126 East Ash Street, Springfield, Illinois 62704-4766 at least 30 days in advance of the pavement marking operations. Random check samples may be taken at the job site at the discretion of the Engineer.
- (c) The Engineer will test and approve the basic ingredients.
- (d) The sample(s) shall be labeled with the lot number, date, quantity and any other pertinent information. Samples shall be submitted in the following manner:
  - (1) Ingredient Materials:
    - (a) Glass beads: At least three randomly selected bags or containers shall be obtained from each lot or shipment of glass beads. The content of each bag or container shall be passed through a large Riffle Sampler, thus splitting the material down until a representative 1-quart (1-liter) sample is obtained. The sample from each container shall be submitted for testing.

- (b) Binder: One pint (0.5 liter).
  - (c) Pigments: One pint (0.5 liter).
  - (d) Filler: One pint (0.5 liter).
- (2) Thermoplastic:

At least three randomly selected containers shall be obtained from each lot. A 10 pound (4.5 kg) composite sample of the three containers shall be submitted for testing and acceptance. The lot size shall be approximately 44,000 pounds (20,000 kg) unless the total order is less than this amount.

Manufacturer's Responsibility:

- (a) The manufacturer shall perform tests on a minimum of one sample per 10,000 pounds (4,500 kg) of thermoplastic produced. Minimum tests required shall be a softening point determination and color. Manufacturer's test results shall be submitted along with the thermoplastic sample to the Bureau of Materials and Physical Research.
- (b) The manufacturer shall retain the test sample for a minimum period of 18 months.
- (c) The manufacturer shall furnish the Bureau of Materials and Physical Research with copies of bills of lading for all material inspected. Bills of lading shall indicate the consignee and destination, date of shipment, lot numbers, quantity, type of material, name and location of source.

Material Acceptance:

Final acceptance of a particular lot of thermoplastic will be based on the following:

- (a) Compliance of ingredient materials with the specifications.
- (b) Compliance of thermoplastic material with the specifications.
- (c) Manufacturer's test results for each lot of thermoplastic have been received.
- (d) Identification requirements are satisfactory.

Notification: The Contractor shall notify the Engineer 72 hours prior to the placement of the thermoplastic markings in order that an inspector can be present during the operation. At the time of this notification, the Contractor shall indicate the manufacturer and lot numbers of thermoplastic and glass beads that he intends to use. The Engineer will ensure that the approved lot numbers appear on the material package. Failure to comply with this provision may be cause for rejection.

Installation Requirements:

- (a) Before applying thermoplastic, the crack sealant shall be fully cured and hardened and the Contractor shall remove any dirt, glaze, grease, or any other material that would reduce the adhesion of the thermoplastic to the pavement.

- (b) This thermoplastic material shall be readily renewable by placing an overlay of new material directly over old markings of the same material. Such new material shall bond itself to the old markings in such a manner that no splitting or separation takes place. The contractor shall remove all existing material that might cause premature failure of the new material.
- (c) The thermoplastic material shall be installed in a molten state by the spray method at a minimum temperature of 350 °F (177 °C) and a maximum temperature of 400 °F (204 °C). Scorching or discoloration of material shall be cause for rejection by the Engineer. The machinery shall be constructed so that all mixing and conveying parts, up to and including the spray gun maintain the material in the molten state.
- (d) Thermoplastic pavement marking materials shall not be applied by the spray method when air and pavement surface temperatures are below 50 °F (10 °C) or when the surface of the pavement contains any evidence of moisture.
- (e) Unless directed by the Engineer, lines shall not be laid directly over a longitudinal crack or joint. The edge of the center line or lane line shall be offset a minimum distance of 2 inches (50 mm) from a longitudinal crack or joint. Edge lines shall be approximately 2 inches (50 mm) from the edge of pavement. The finished center and lane lines shall be straight, with the lateral deviation of any 10 foot (3 meter) line not to exceed 1 inch (25 mm).
- (f) A primer sealer of the type recommended by the manufacturer of the thermoplastic material shall be applied on all Portland concrete pavement surfaces, and if recommended by the manufacturer, on other types of pavement surface, prior to the installation of the thermoplastic material. The primer shall be free of solvent and water prior to the thermoplastic application.
- (g) The thermoplastic material shall be applied at a thickness of not less than 0.045 inch (1.143 mm), but in no case shall it exceed a thickness of 0.050 inch (1.27 mm). Finished lines shall be within a 1/4 inch (6.35 mm) of the width specified in the plans.
- (h) The Contractor shall place the thermoplastic markings with adequate drop on glass in accordance with the above requirements, uniformly applied to assure nighttime reflectivity. It shall be the Contractor's responsibility to use compatible combination of thermoplastic material and beads to preclude the surface beads from sinking deeply into the thermoplastic.
- (i) The thickness of the markings will be measured above the pavement surface at such random points as the Engineer selects to determine conformance to these specifications. If the measurements show less than 0.045 inch (1.143 mm), the Engineer will "chip" the edges of the markings at random points and measure the thickness of the chips to determine if the overall thickness of the markings is at least 0.045 inch (1.143 mm). If the overall thickness or the thickness above the pavement surface is substantially in conformance with the thickness requirements, payment will be made at 100 percent of the contract unit prices involved. When the thickness at a given location is less than 0.045 inch (1.143 mm), additional measurements will be taken on each side of such location at such intervals as the Engineer may select to determine the extent of the deficient portion of the marking. The Contractor shall then apply additional thermoplastic material and beads to bring the thickness of the markings to at least 0.045 inch (1.143 mm).

Equipment Requirements:

- (a) The application equipment used for placing lane and edge line on County Highways shall be Truck-Mounted and meeting Article 1105.01 of the Standard Specifications and the requirements listed

below. When the Truck-Mounted method is used, the application equipment shall be permanently mounted on a truck of sufficient size and stability to insure smooth, straight application. The truck shall be equipped to carry a minimum of 4,000 pounds (1800 kilograms) of molten thermoplastic.

The equipment shall have the capability of automatically placing intermittent and continuous lines. The equipment shall be so constructed as to provide the various widths of pavement marking lines specified. The mounting shall be such as to allow the spray equipment to accurately follow road irregularities and produce lines of uniform dimensions.

- (b) The equipment used to install hot applied thermoplastic material shall provide continuous uniform heating to temperatures exceeding 400 °F (204 °C), mixing and agitation of the material. Conveying parts of the equipment between the main material reservoir and the dispensing device shall prevent accumulation and clogging. All parts of the equipment, which comes in contact with the material, shall be constructed for easy accessibility and exposure for cleaning and maintenance. The equipment shall operate so that all mixing and conveying parts including the line dispensing device, maintains the material at the plastic temperature. The use of pans, aprons, or similar devices to prevent die overruns will not be permitted.
- (c) Glass beads applied to the surface of the completed marking shall be applied by an automatic bead dispenser attached to the marking machine so that the beads are dispensed closely behind the installed marking. The glass bead dispenser shall be equipped with an automatic cut-off control synchronized with the cut-off of the thermoplastic material.
- (d) A special kettle shall be provided for uniformly melting and heating the thermoplastic material. The kettle must be equipped with an automatic thermostat control device and material thermometer for positive temperature control and to prevent overheating or under-heating of the material. The heating kettle and application equipment shall meet the requirements of the National Fire Underwriters and the National Fire Protection Association.
- (e) The Contractor shall provide an accurate temperature measuring device which shall be capable of measuring the pavement temperature prior to installation of the thermoplastic and the temperature of the molten thermoplastic material immediately after it is applied.

Inspection: The 45 mil hot spray thermoplastic pavement markings will be inspected following installation, but no later than November 1, and inspected following a winter performance period that extends 180 days from November 1 in accordance with the provisions of Article 780.12 of the Standard Specification.

Method of Measurement: Lines will be measured for payment in feet. Double yellow lines will be measured as two separate lines.

Basis of Payment: This work will be paid for at the contract unit prices per foot of applied line width for HOT SPRAY THERMOPLASTIC PAVEMENT MARKING – LINE.

**MODIFIED URETHANE PAVEMENT MARKING – RAISED MEDIAN**

Description. This work shall consist of removing existing median pavement marking and applying modified urethane pavement markings in accordance with Sections 780 and 783 of the Standard Specifications, except as modified herein, to the median ramped noses as shown in the plans or as directed by the Engineer.

Construction Requirements. The shotblast method of cleaning shall not be permitted.

Method of Measurement. This work will be measured for payment in place and the area computed in square feet based on the area of installed material. The area measured will include applications to concrete curb and gutter monolithic to the median ramped noses.

Basis of Payment. This work will be paid for at the contract unit price per square foot for MODIFIED URETHANE PAVEMENT MARKING – RAISED MEDIAN, which price shall include all necessary equipment, labor and materials required to remove the existing median pavement markings, prepare the surface and install the pavement markings

**TEMPORARY PAVEMENT MARKING REMOVAL**

Description: This work shall consist of removing all temporary or work zone pavement marking, painted pavement markings, or pavement marking tape type III in accordance with the applicable portions of Section 783 and 703 of the Standard Specifications and described herein. Pavement marking tape type III may be peeled off. Removal using high-pressure water spray, or “hydro-blast,” will not be allowed.

Equipment Requirements: All equipment shall be of sufficient capacity to efficiently and economically clean the roadway surface to the specified cleanliness. Equipment shall be power driven and in good operating condition. Equipment shall utilize moisture and oil traps, in working order, of sufficient capacity to remove contaminants from the water and prevent deposition of oil and other contaminants on the roadway surface.

Removal Requirements: Removal requirements shall be as follows:

a) The existing paint pavement markings or epoxy paint pavement markings shall be removed without pavement surface damage to the satisfaction of the Engineer.

b) Over cleaning to the extent of possible damage to the roadway surface shall be held to a minimum. Very small particles of tightly adhering existing markings may remain in place, if in the opinion of the Engineer, complete removal of the small particles will result in pavement surface damage.

Method of Measurement: The removal of temporary or work zone pavement marking, painted pavement markings, epoxy paint pavement markings, thermoplastic pavement marking, or pavement marking tape type III will be measured in square feet.

Basis of Payment: This work will be paid for at the contract unit price per square foot for TEMPORARY PAVEMENT MARKING REMOVAL.

**CHECK SHEET FOR RECURRING SPECIAL PROVISIONS  
DUPAGE COUNTY PREVAILING  
LOCAL ROADS AND STREETS SPECIAL PROVISIONS  
BDE SPECIAL PROVISIONS**





Local Public Agency	County	Section Number
County of DuPage	DuPage	23-PVMKG-11-GM

**Check this box for lettings prior to 01/01/2022.**

The Following Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Recurring Special Provisions

<u>Check Sheet #</u>		<u>Reference Page No.</u>
1	<input type="checkbox"/> Additional State Requirements for Federal-Aid Construction Contracts	1
2	<input type="checkbox"/> Subletting of Contracts (Federal-Aid Contracts)	4
3	<input type="checkbox"/> EEO	5
4	<input type="checkbox"/> Specific EEO Responsibilities Non Federal-Aid Contracts	15
5	<input type="checkbox"/> Required Provisions - State Contracts	20
6	<input type="checkbox"/> Asbestos Bearing Pad Removal	26
7	<input type="checkbox"/> Asbestos Waterproofing Membrane and Asbestos HMA Surface Removal	27
8	<input type="checkbox"/> Temporary Stream Crossings and In-Stream Work Pads	28
9	<input type="checkbox"/> Construction Layout Stakes	29
10	<input type="checkbox"/> Use of Geotextile Fabric for Railroad Crossing	32
11	<input type="checkbox"/> Subsealing of Concrete Pavements	34
12	<input type="checkbox"/> Hot-Mix Asphalt Surface Correction	38
13	<input type="checkbox"/> Pavement and Shoulder Resurfacing	40
14	<input type="checkbox"/> Patching with Hot-Mix Asphalt Overlay Removal	41
15	<input type="checkbox"/> Polymer Concrete	43
16	<input type="checkbox"/> PVC Pipeliner	45
17	<input type="checkbox"/> Bicycle Racks	46
18	<input type="checkbox"/> Temporary Portable Bridge Traffic Signals	48
19	<input type="checkbox"/> Nighttime Inspection of Roadway Lighting	50
20	<input type="checkbox"/> English Substitution of Metric Bolts	51
21	<input type="checkbox"/> Calcium Chloride Accelerator for Portland Cement Concrete	52
22	<input type="checkbox"/> Quality Control of Concrete Mixtures at the Plant	53
23	<input type="checkbox"/> Quality Control/Quality Assurance of Concrete Mixtures	61
24	<input type="checkbox"/> Digital Terrain Modeling for Earthwork Calculations	77
25	<input type="checkbox"/> Preventive Maintenance - Bituminous Surface Treatment (A-1)	79
26	<input type="checkbox"/> Temporary Raised Pavement Markers	85
27	<input type="checkbox"/> Restoring Bridge Approach Pavements Using High-Density Foam	86
28	<input type="checkbox"/> Portland Cement Concrete Inlay or Overlay	89
29	<input type="checkbox"/> Portland Cement Concrete Partial Depth Hot-Mix Asphalt Patching	93
30	<input type="checkbox"/> Longitudinal Joint and Crack Patching	96
31	<input type="checkbox"/> Concrete Mix Design - Department Provided	98
32	<input type="checkbox"/> Station Numbers in Pavements or Overlays	99

County of DuPage

DuPage

23-PVMKG-11-GM

The Following Local Roads And Streets Recurring Special Provisions Indicated By An "X" Are Applicable To This Contract And Are Included By Reference:

Local Roads And Streets Recurring Special Provisions

<u>Check Sheet #</u>		<u>Page No.</u>
LRS 1	<b>Reserved</b>	101
LRS 2	<input type="checkbox"/> Furnished Excavation	102
LRS 3	<input checked="" type="checkbox"/> Work Zone Traffic Control Surveillance	103
LRS 4	<input checked="" type="checkbox"/> Flaggers in Work Zones	104
LRS 5	<input checked="" type="checkbox"/> Contract Claims	105
LRS 6	<input checked="" type="checkbox"/> Bidding Requirements and Conditions for Contract Proposals	106
LRS 7	<input type="checkbox"/> Bidding Requirements and Conditions for Material Proposals	112
LRS 8	<b>Reserved</b>	118
LRS 9	<input type="checkbox"/> Bituminous Surface Treatments	119
LRS 10	<b>Reserved</b>	123
LRS 11	<input checked="" type="checkbox"/> Employment Practices	124
LRS 12	<input checked="" type="checkbox"/> Wages of Employees on Public Works	126
LRS 13	<input checked="" type="checkbox"/> Selection of Labor	128
LRS 14	<input type="checkbox"/> Paving Brick and Concrete Paver Pavements and Sidewalks	129
LRS 15	<input checked="" type="checkbox"/> Partial Payments	132
LRS 16	<input checked="" type="checkbox"/> Protests on Local Lettings	133
LRS 17	<input checked="" type="checkbox"/> Substance Abuse Prevention Program	134
LRS 18	<input type="checkbox"/> Multigrade Cold Mix Asphalt	135
LRS 19	<input type="checkbox"/> Reflective Crack Control Treatment	136

## DuPage County Prevailing Wage Rates posted on 1/18/2023

Trade Title	Rg	Type	C	Base	Foreman	Overtime				H/W	Pension	Vac	Trng	Other Ins
						M-F	Sa	Su	Hol					
ASBESTOS ABT-GEN	All	ALL		47.40	48.40	1.5	1.5	2.0	2.0	17.05	15.21	0.00	0.90	
ASBESTOS ABT-MEC	All	BLD		39.60	42.77	1.5	1.5	2.0	2.0	14.77	13.59	0.00	0.86	
BOILERMAKER	All	BLD		53.66	58.48	2.0	2.0	2.0	2.0	6.97	23.69	0.00	2.67	
BRICK MASON	All	BLD		49.81	54.79	1.5	1.5	2.0	2.0	12.10	21.56	0.00	1.10	
CARPENTER	All	ALL		52.01	54.01	1.5	1.5	2.0	2.0	11.79	24.76	1.50	0.80	
CEMENT MASON	All	ALL		49.75	51.75	2.0	1.5	2.0	2.0	17.08	20.74	0.00	1.00	
CERAMIC TILE FINISHER	All	BLD		44.18	44.18	1.5	1.5	2.0	2.0	12.25	14.77	0.00	1.00	
CERAMIC TILE LAYER	All	BLD		51.44	55.44	1.5	1.5	2.0	2.0	12.25	18.48	0.00	1.08	
COMMUNICATION TECHNICIAN	All	BLD		35.92	38.72	1.5	1.5	2.0	2.0	13.60	24.04	3.20	0.83	
ELECTRIC PWR EQMT OP	All	ALL		47.56	64.89	1.5	1.5	2.0	2.0	7.00	13.32	0.00	1.19	1.43
ELECTRIC PWR GRNDMAN	All	ALL		36.53	64.89	1.5	1.5	2.0	2.0	7.00	10.23	0.00	0.92	1.10
ELECTRIC PWR LINEMAN	All	ALL		57.17	64.89	1.5	1.5	2.0	2.0	7.00	16.01	0.00	1.43	1.72
ELECTRIC PWR TRK DRV	All	ALL		37.86	64.89	1.5	1.5	2.0	2.0	7.00	10.61	0.00	0.95	1.14
ELECTRICIAN	All	BLD		43.08	47.33	1.5	1.5	2.0	2.0	13.60	27.57	7.13	1.20	
ELEVATOR CONSTRUCTOR	All	BLD		62.47	70.28	2.0	2.0	2.0	2.0	16.03	20.21	5.00	0.65	
FENCE ERECTOR	NE	ALL		46.89	48.89	1.5	1.5	2.0	2.0	13.68	17.42	0.00	0.75	
FENCE ERECTOR	W	ALL		48.83	52.74	2.0	2.0	2.0	2.0	13.31	25.25	0.00	1.28	
GLAZIER	All	BLD		48.75	50.25	1.5	2.0	2.0	2.0	15.19	24.43	0.00	1.70	
HEAT/FROST INSULATOR	All	BLD		52.80	55.97	1.5	1.5	2.0	2.0	14.77	16.76	0.00	0.86	
IRON WORKER	E	ALL		55.81	57.81	2.0	2.0	2.0	2.0	16.05	25.31	0.00	0.49	
IRON WORKER	W	ALL		48.83	52.74	2.0	2.0	2.0	2.0	13.31	25.25	0.00	1.28	
LABORER	All	ALL		47.40	48.15	1.5	1.5	2.0	2.0	17.05	15.21	0.00	0.90	
LATHER	All	ALL		52.01	54.01	1.5	1.5	2.0	2.0	11.79	24.76	1.50	0.80	
MACHINIST	All	BLD		53.18	57.18	1.5	1.5	2.0	2.0	9.93	8.95	1.85	1.47	
MARBLE FINISHER	All	ALL		38.00	51.41	1.5	1.5	2.0	2.0	12.10	19.60	0.00	0.60	
MARBLE SETTER	All	BLD		48.96	53.86	1.5	1.5	2.0	2.0	12.10	21.03	0.00	0.78	
MATERIAL TESTER I	All	ALL		37.40		1.5	1.5	2.0	2.0	17.05	15.21	0.00	0.90	
MATERIALS TESTER II	All	ALL		42.40		1.5	1.5	2.0	2.0	17.05	15.21	0.00	0.90	
MILLWRIGHT	All	ALL		52.01	54.01	1.5	1.5	2.0	2.0	11.79	24.76	1.50	0.80	
OPERATING ENGINEER	All	BLD	1	55.10	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	BLD	2	53.80	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	

OPERATING ENGINEER	All	BLD	3	51.25	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	BLD	4	49.50	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	BLD	5	58.85	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	BLD	6	56.10	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	BLD	7	58.10	59.10	2.0	2.0	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	FLT		41.00	41.00	1.5	1.5	2.0	2.0	20.90	17.85	2.00	2.15	
OPERATING ENGINEER	All	HWY	1	53.30	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	2	52.75	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	3	50.70	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	4	49.30	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	5	48.10	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	6	56.30	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
OPERATING ENGINEER	All	HWY	7	54.30	57.30	1.5	1.5	2.0	2.0	22.15	19.30	2.00	2.55	
ORNAMENTAL IRON WORKER	E	ALL		53.32	55.82	2.0	2.0	2.0	2.0	14.23	25.00	0.00	1.75	
ORNAMENTAL IRON WORKER	W	ALL		48.83	52.74	2.0	2.0	2.0	2.0	13.31	25.25	0.00	1.28	
PAINTER	All	ALL		50.30	52.30	1.5	1.5	1.5	2.0	19.73	4.15	0.00	1.55	
PAINTER - SIGNS	All	BLD		41.55	46.67	1.5	1.5	2.0	2.0	3.04	3.90	0.00	0.00	
PILEDRIIVER	All	ALL		52.01	54.01	1.5	1.5	2.0	2.0	11.79	24.76	1.50	0.80	
PIPEFITTER	All	BLD		53.00	56.00	1.5	1.5	2.0	2.0	11.85	22.85	0.00	2.92	
PLASTERER	All	BLD		49.85	52.84	1.5	1.5	2.0	2.0	12.10	21.48	0.00	1.09	
PLUMBER	All	BLD		54.80	58.10	1.5	1.5	2.0	2.0	16.70	17.04	0.00	1.58	
ROOFER	All	BLD		48.00	53.00	1.5	1.5	2.0	2.0	11.83	15.26	0.00	0.99	
SHEETMETAL WORKER	All	BLD		53.33	56.00	1.5	1.5	2.0	2.0	11.85	19.43	0.00	1.59	2.54
SPRINKLER FITTER	All	BLD		54.55	57.30	1.5	1.5	2.0	2.0	14.20	18.70	0.00	0.75	
STEEL ERECTOR	E	ALL		55.81	57.81	2.0	2.0	2.0	2.0	16.05	25.31	0.00	0.49	
STEEL ERECTOR	W	ALL		48.83	52.74	2.0	2.0	2.0	2.0	13.31	25.25	0.00	1.28	
STONE MASON	All	BLD		49.81	54.79	1.5	1.5	2.0	2.0	12.10	21.56	0.00	1.10	
TERRAZZO FINISHER	All	BLD		45.57	45.57	1.5	1.5	2.0	2.0	12.25	17.14	0.00	1.03	
TERRAZZO MECHANIC	All	BLD		49.41	52.91	1.5	1.5	2.0	2.0	12.25	18.60	0.00	1.07	
TRAFFIC SAFETY WORKER I	All	HWY		39.30	40.90	1.5	1.5	2.0	2.0	9.65	9.10	0.00	0.10	
TRAFFIC SAFETY WORKER II	ALL	HWY		40.30	41.90	1.5	1.5	2.0	2.0	9.65	9.10	0.00	0.10	
TRUCK DRIVER	All	ALL	1	41.06	41.61	1.5	1.5	2.0	2.0	10.83	14.15	0.00	0.15	
TRUCK DRIVER	All	ALL	2	41.21	41.61	1.5	1.5	2.0	2.0	10.83	14.15	0.00	0.15	
TRUCK DRIVER	All	ALL	3	41.41	41.61	1.5	1.5	2.0	2.0	10.83	14.15	0.00	0.15	
TRUCK DRIVER	All	ALL	4	41.61	41.61	1.5	1.5	2.0	2.0	10.83	14.15	0.00	0.15	
TUCKPOINTER	All	BLD		49.53	50.53	1.5	1.5	2.0	2.0	9.04	21.06	0.00	1.07	

## **Legend**

**Rg** Region

**Type** Trade Type - All,Highway,Building,Floating,Oil & Chip,Rivers

**C** Class

**Base** Base Wage Rate

**OT M-F** Unless otherwise noted, OT pay is required for any hour greater than 8 worked each day, Mon through Fri. The number listed is the multiple of the base wage.

**OT Sa** Overtime pay required for every hour worked on Saturdays

**OT Su** Overtime pay required for every hour worked on Sundays

**OT Hol** Overtime pay required for every hour worked on Holidays

**H/W** Health/Welfare benefit

**Vac** Vacation

**Trng** Training

**Other Ins** Employer hourly cost for any other type(s) of insurance provided for benefit of worker.

Explanations DUPAGE COUNTY

IRON WORKERS AND FENCE ERECTOR (WEST) - West of Route 53.

The following list is considered as those days for which holiday rates of wages for work performed apply: New Years Day, Memorial Day, Fourth of July, Labor Day, Thanksgiving Day, Christmas Day and Veterans Day in some classifications/counties. Generally, any of these holidays which fall on a Sunday is celebrated on the following Monday. This then makes work performed on that Monday payable at the appropriate overtime rate for holiday pay. Common practice in a given local may alter certain days of celebration. If in doubt, please check with IDOL.

## EXPLANATION OF CLASSES

ASBESTOS - GENERAL - removal of asbestos material/mold and hazardous materials from any place in a building, including mechanical systems where those mechanical systems are to be removed. This includes the removal of asbestos materials/mold and hazardous materials from ductwork or pipes in a building when the building is to be demolished at the time or at some close future date.

ASBESTOS - MECHANICAL - removal of asbestos material from mechanical systems, such as pipes, ducts, and boilers, where the mechanical systems are to remain.

## TRAFFIC SAFETY Worker I

Traffic Safety Worker I - work associated with the delivery, installation, pick-up and servicing of safety devices during periods of roadway construction, including such work as set-up and maintenance of barricades, barrier wall reflectors, drums, cones, delineators, signs, crash attenuators, glare screen and other such items, and the layout and application or removal of conflicting and/or temporary roadway markings utilized to control traffic in construction zones, as well as flagging for these operations.

## TRAFFIC SAFETY WORKER II

Work associated with the installation and removal of permanent pavement markings and/or pavement markers including both installations performed by hand and installations performed by truck.

## CERAMIC TILE FINISHER

The grouting, cleaning, and polishing of all classes of tile, whether for interior or exterior purposes, all burned, glazed or unglazed products; all composition materials, granite tiles, warning detectable tiles, cement tiles, epoxy composite materials, pavers, glass, mosaics, fiberglass, and all substitute materials, for tile made in tile-like units; all mixtures in tile like form of cement, metals, and other materials that are for and intended for use as a finished floor surface, stair treads, promenade roofs, walks, walls, ceilings, swimming pools, and all other places where tile is to form a finished interior or exterior. The mixing of all setting mortars including but not limited to thin-set mortars, epoxies, wall mud, and any other sand and cement mixtures or adhesives when used in the preparation, installation, repair, or maintenance of tile and/or similar materials. The handling and unloading of all sand, cement, lime, tile, fixtures, equipment, adhesives, or any other materials to be used in the preparation, installation, repair, or maintenance of tile and/or similar materials. Ceramic Tile Finishers shall fill all joints and voids regardless of method on all tile work, particularly and especially after installation of said tile work. Application of any and all protective coverings to all types of tile installations including, but not be limited to, all soap compounds, paper products, tapes, and all polyethylene coverings, plywood, masonite, cardboard, and any new type of products that may be used to protect tile installations, Blastrac equipment, and all floor scarifying equipment used in preparing floors to receive tile. The clean up and removal of all waste and materials. All demolition of existing tile floors and walls to be re-tiled.

#### COMMUNICATIONS TECHNICIAN

Low voltage installation, maintenance and removal of telecommunication facilities (voice, sound, data and video) including telephone and data inside wire, interconnect, terminal equipment, central offices, PABX, fiber optic cable and equipment, micro waves, V-SAT, bypass, CATV, WAN (wide area networks), LAN (local area networks), and ISDN (integrated system digital network), pulling of wire in raceways, but not the installation of raceways.

#### MARBLE FINISHER

Loading and unloading trucks, distribution of all materials (all stone, sand, etc.), stocking of floors with material, performing all rigging for heavy work, the handling of all material that may be needed for the installation of such materials, building of scaffolding, polishing if needed, patching, waxing of material if damaged, pointing up, caulking, grouting and cleaning of marble, holding water on diamond or Carborundum blade or saw for setters cutting, use of tub saw or any other saw needed for preparation of material, drilling of holes for wires that anchor material set by setters, mixing up of molding plaster for installation of material, mixing up thin set for the installation of material, mixing up of sand to cement for the installation of material and such other work as may be required in helping a Marble Setter in the handling of all material in the erection or installation of interior marble, slate, travertine, art marble, serpentine, alberene stone, blue stone, granite and other stones (meaning as to stone any foreign or domestic materials as are specified and used in building interiors and exteriors and customarily known as stone in the trade), carrara, sanionyx, vitrolite and similar opaque glass and the laying of all marble tile, terrazzo tile, slate tile and precast tile, steps, risers treads, base, or any other materials that may be used as substitutes for any of the aforementioned materials and which are used on interior and exterior which are installed in a similar manner.

MATERIAL TESTER I: Hand coring and drilling for testing of materials; field inspection of uncured concrete and asphalt.

MATERIAL TESTER II: Field inspection of welds, structural steel, fireproofing, masonry, soil, facade, reinforcing steel, formwork, cured concrete, and concrete and asphalt batch plants; adjusting proportions of bituminous mixtures.

#### OPERATING ENGINEER - BUILDING

Class 1. Asphalt Plant; Asphalt Spreader; Autograde; Backhoes with Caisson Attachment; Batch Plant; Benoto (requires Two Engineers); Boiler and Throttle Valve; Caisson Rigs; Central Redi-Mix Plant; Combination Back Hoe Front End-loader Machine; Compressor and Throttle Valve; Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Conveyor (Truck Mounted); Concrete Paver Over 27E cu. ft; Concrete Paver 27E cu. ft. and Under; Concrete Placer; Concrete Placing Boom; Concrete Pump (Truck Mounted); Concrete Tower; Cranes, All; Cranes, Hammerhead; Cranes, (GCI and similar Type); Creter Crane; Spider Crane; Crusher, Stone, etc.; Derricks, All; Derricks, Traveling; Formless Curb and Gutter Machine; Grader, Elevating; Grouting Machines;

Heavy Duty Self-Propelled Transporter or Prime Mover; Highlift Shovels or Front Endloader 2-1/4 yd. and over; Hoists, Elevators, outside type rack and pinion and similar machines; Hoists, One, Two and Three Drum; Hoists, Two Tugger One Floor; Hydraulic Backhoes; Hydraulic Boom Trucks; Hydro Vac (and similar equipment); Locomotives, All; Motor Patrol; Lubrication Technician; Manipulators; Pile Drivers and Skid Rig; Post Hole Digger; Pre-Stress Machine; Pump Cretes Dual Ram; Pump Cretes: Squeeze Cretes-Screw Type Pumps; Gypsum Bulker and Pump; Raised and Blind Hole Drill; Roto Mill Grinder; Scoops - Tractor Drawn; Slip-Form Paver; Straddle Buggies; Operation of Tie Back Machine; Tournapull; Tractor with Boom and Side Boom; Trenching Machines.

Class 2. Boilers; Broom, All Power Propelled; Bulldozers; Concrete Mixer (Two Bag and Over); Conveyor, Portable; Forklift Trucks; Highlift Shovels or Front Endloaders under 2-1/4 yd.; Hoists, Automatic; Hoists, Inside Elevators; Hoists, Sewer Dragging Machine; Hoists, Tugger Single Drum; Laser Screed; Rock Drill (Self-Propelled); Rock Drill (Truck Mounted); Rollers, All; Steam Generators; Tractors, All; Tractor Drawn Vibratory Roller; Winch Trucks with "A" Frame.

Class 3. Air Compressor; Combination Small Equipment Operator; Generators; Heaters, Mechanical; Hoists, Inside Elevators (remodeling or renovation work); Hydraulic Power Units (Pile Driving, Extracting, and Drilling); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Low Boys; Pumps, Well Points; Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 4. Bobcats and/or other Skid Steer Loaders; Oilers; and Brick Forklift.

Class 5. Assistant Craft Foreman.

Class 6. Gradall.

Class 7. Mechanics; Welders.

#### OPERATING ENGINEERS - HIGHWAY CONSTRUCTION

Class 1. Asphalt Plant; Asphalt Heater and Planer Combination; Asphalt Heater Scarfire; Asphalt Spreader; Autograder/GOMACO or other similar type machines: ABG Paver; Backhoes with Caisson Attachment; Ballast Regulator; Belt Loader; Caisson Rigs; Car Dumper; Central Redi-Mix Plant; Combination Backhoe Front Endloader Machine, (1 cu. yd. Backhoe Bucket or over or with attachments); Concrete Breaker (Truck Mounted); Concrete Conveyor; Concrete Paver over 27E cu. ft.; Concrete Placer; Concrete Tube Float; Cranes, all attachments; Cranes, Tower Cranes of all types: Creter Crane: Spider Crane; Crusher, Stone, etc.; Derricks, All; Derrick Boats; Derricks, Traveling; Dredges; Elevators, Outside type Rack & Pinion and Similar Machines; Formless Curb and Gutter Machine; Grader, Elevating; Grader, Motor Grader, Motor Patrol, Auto Patrol, Form Grader, Pull Grader, Subgrader; Guard Rail Post Driver Truck Mounted; Hoists, One, Two and Three Drum; Heavy Duty Self-Propelled Transporter or Prime Mover; Hydraulic Backhoes; Backhoes with shear attachments up to 40' of boom reach; Lubrication Technician; Manipulators; Mucking Machine; Pile Drivers and Skid Rig; Pre-Stress Machine; Pump Cretes Dual Ram; Rock Drill - Crawler or Skid Rig; Rock Drill - Truck Mounted; Rock/Track Tamper; Roto Mill Grinder; Slip-Form Paver; Snow Melters; Soil Test Drill Rig (Truck Mounted); Straddle Buggies; Hydraulic Telescoping Form (Tunnel); Operation of Tieback Machine; Tractor Drawn Belt Loader; Tractor Drawn Belt Loader (with attached pusher - two engineers); Tractor with Boom; Tractaire with Attachments; Traffic Barrier Transfer Machine; Trenching; Truck Mounted Concrete Pump with Boom; Raised or Blind Hole Drills (Tunnel Shaft); Underground Boring and/or Mining Machines 5 ft. in diameter and over tunnel, etc; Underground Boring and/or Mining Machines under 5 ft. in diameter; Wheel Excavator; Widener (APSCO).

Class 2. Batch Plant; Bituminous Mixer; Boiler and Throttle Valve; Bulldozers; Car Loader Trailing Conveyors; Combination Backhoe Front Endloader Machine (Less than 1 cu. yd. Backhoe Bucket or over or with attachments); Compressor and Throttle Valve; Compressor, Common Receiver (3); Concrete Breaker or Hydro Hammer; Concrete Grinding Machine; Concrete Mixer or Paver 7S Series to and including 27 cu. ft.; Concrete Spreader; Concrete Curing Machine, Burlap Machine, Belting Machine and Sealing Machine; Concrete Wheel Saw; Conveyor Muck Cars (Haglund or Similar Type); Drills, All; Finishing Machine - Concrete; Highlift Shovels or Front Endloader; Hoist - Sewer Dragging Machine; Hydraulic Boom Trucks (All Attachments); Hydro-Blaster; Hydro

Excavating (excluding hose work); Laser Screed; All Locomotives, Dinky; Off-Road Hauling Units (including articulating) Non Self-Loading Ejection Dump; Pump Cretes: Squeeze Cretes - Screw Type Pumps, Gypsum Bulker and Pump; Roller, Asphalt; Rotary Snow Plows; Rototiller, Seaman, etc., self-propelled; Self-Propelled Compactor; Spreader - Chip - Stone, etc.; Scraper - Single/Twin Engine/Push and Pull; Scraper - Prime Mover in Tandem (Regardless of Size); Tractors pulling attachments, Sheeps Foot, Disc, Compactor, etc.; Tug Boats.

Class 3. Boilers; Brooms, All Power Propelled; Cement Supply Tender; Compressor, Common Receiver (2); Concrete Mixer (Two Bag and Over); Conveyor, Portable; Farm-Type Tractors Used for Mowing, Seeding, etc.; Forklift Trucks; Grouting Machine; Hoists, Automatic; Hoists, All Elevators; Hoists, Tugger Single Drum; Jeep Diggers; Low Boys; Pipe Jacking Machines; Post-Hole Digger; Power Saw, Concrete Power Driven; Pug Mills; Rollers, other than Asphalt; Seed and Straw Blower; Steam Generators; Stump Machine; Winch Trucks with "A" Frame; Work Boats; Tamper-Form-Motor Driven.

Class 4. Air Compressor; Combination - Small Equipment Operator; Directional Boring Machine; Generators; Heaters, Mechanical; Hydraulic Power Unit (Pile Driving, Extracting, or Drilling); Light Plants, All (1 through 5); Pumps, over 3" (1 to 3 not to exceed a total of 300 ft.); Pumps, Well Points; Vacuum Trucks (excluding hose work); Welding Machines (2 through 5); Winches, 4 Small Electric Drill Winches.

Class 5. SkidSteer Loader (all); Brick Forklifts; Oilers.

Class 6. Field Mechanics and Field Welders

Class 7. Dowell Machine with Air Compressor; Gradall and machines of like nature.

#### OPERATING ENGINEER - FLOATING

Diver. Diver Wet Tender, Diver Tender, ROV Pilot, ROV Tender

#### TRUCK DRIVER - BUILDING, HEAVY AND HIGHWAY CONSTRUCTION

Class 1. Two or three Axle Trucks. A-frame Truck when used for transportation purposes; Air Compressors and Welding Machines, including those pulled by cars, pick-up trucks and tractors; Ambulances; Batch Gate Lockers; Batch Hopperman; Car and Truck Washers; Carry-alls; Fork Lifts and Hoisters; Helpers; Mechanics Helpers and Greasers; Oil Distributors 2-man operation; Pavement Breakers; Pole Trailer, up to 40 feet; Power Mower Tractors; Self-propelled Chip Spreader; Skipman; Slurry Trucks, 2-man operation; Slurry Truck Conveyor Operation, 2 or 3 man; Teamsters; Unskilled Dumpman; and Truck Drivers hauling warning lights, barricades, and portable toilets on the job site.

Class 2. Four axle trucks; Dump Crets and Adgetors under 7 yards; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turnapulls or Turntrailers when pulling other than self-loading equipment or similar equipment under 16 cubic yards; Mixer Trucks under 7 yards; Ready-mix Plant Hopper Operator, and Winch Trucks, 2 Axles.

Class 3. Five axle trucks; Dump Crets and Adgetors 7 yards and over; Dumpsters, Track Trucks, Euclids, Hug Bottom Dump Turntrailers or turnapulls when pulling other than self-loading equipment or similar equipment over 16 cubic yards; Explosives and/or Fission Material Trucks; Mixer Trucks 7 yards or over; Mobile Cranes while in transit; Oil Distributors, 1-man operation; Pole Trailer, over 40 feet; Pole and Expandable Trailers hauling material over 50 feet long; Slurry trucks, 1-man operation; Winch trucks, 3 axles or more; Mechanic--Truck Welder and Truck Painter.

Class 4. Six axle trucks; Dual-purpose vehicles, such as mounted crane trucks with hoist and accessories; Foreman; Master Mechanic; Self-loading equipment like P.B. and trucks with scoops on the front.

#### TERRAZZO FINISHER

The handling of sand, cement, marble chips, and all other materials that may be used by the Mosaic Terrazzo Mechanic, and the



mixing, grinding, grouting, cleaning and sealing of all Marble, Mosaic, and Terrazzo work, floors, base, stairs, and wainscoting by hand or machine, and in addition, assisting and aiding Marble, Masonic, and Terrazzo Mechanics.

#### Other Classifications of Work:

For definitions of classifications not otherwise set out, the Department generally has on file such definitions which are available. If a task to be performed is not subject to one of the classifications of pay set out, the Department will upon being contacted state which neighboring county has such a classification and provide such rate, such rate being deemed to exist by reference in this document. If no neighboring county rate applies to the task, the Department shall undertake a special determination, such special determination being then deemed to have existed under this determination. If a project requires these, or any classification not listed, please contact IDOL at 217-782-1710 for wage rates or clarifications.

#### LANDSCAPING

Landscaping work falls under the existing classifications for laborer, operating engineer and truck driver. The work performed by landscape plantsman and landscape laborer is covered by the existing classification of laborer. The work performed by landscape operators (regardless of equipment used or its size) is covered by the classifications of operating engineer. The work performed by landscape truck drivers (regardless of size of truck driven) is covered by the classifications of truck driver.

#### MATERIAL TESTER & MATERIAL TESTER/INSPECTOR I AND II

Notwithstanding the difference in the classification title, the classification entitled "Material Tester I" involves the same job duties as the classification entitled "Material Tester/Inspector I". Likewise, the classification entitled "Material Tester II" involves the same job duties as the classification entitled "Material Tester/Inspector II".

State of Illinois  
Department of Transportation  
Bureau of Local Roads and Streets  
SPECIAL PROVISION  
FOR  
CONSTRUCTION AND MAINTENANCE SIGNS

Effective: January 1, 2004  
Revised: June 1, 2007

All references to Sections or Articles in this specification shall be construed to mean a specific Section or Article of the Standard Specifications for Road and Bridge Construction, adopted by the Department of Transportation.

701.14. Signs. Add the following paragraph to Article 701.14:

All warning signs shall have minimum dimensions of 1200 mm x 1200 mm (48" x 48") and have a black legend on a fluorescent orange reflectorized background, meeting, as a minimum, Type AP reflectivity requirements of Table 1091-2 in Article 1091.02.

## **COMPENSABLE DELAY COSTS (BDE)**

Effective: June 2, 2017

Revised: April 1, 2019

Revise Article 107.40(b) of the Standard Specifications to read:

“(b) Compensation. Compensation will not be allowed for delays, inconveniences, or damages sustained by the Contractor from conflicts with facilities not meeting the above definition; or if a conflict with a utility in an unanticipated location does not cause a shutdown of the work or a documentable reduction in the rate of progress exceeding the limits set herein. The provisions of Article 104.03 notwithstanding, compensation for delays caused by a utility in an unanticipated location will be paid according to the provisions of this Article governing minor and major delays or reduced rate of production which are defined as follows.

- (1) Minor Delay. A minor delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two hours, but not to exceed two weeks.
- (2) Major Delay. A major delay occurs when the work in conflict with the utility in an unanticipated location is completely stopped for more than two weeks.
- (3) Reduced Rate of Production Delay. A reduced rate of production delay occurs when the rate of production on the work in conflict with the utility in an unanticipated location decreases by more than 25 percent and lasts longer than seven calendar days.”

Revise Article 107.40(c) of the Standard Specifications to read:

“(c) Payment. Payment for Minor, Major, and Reduced Rate of Production Delays will be made as follows.

- (1) Minor Delay. Labor idled which cannot be used on other work will be paid for according to Article 109.04(b)(1) and (2) for the time between start of the delay and the minimum remaining hours in the work shift required by the prevailing practice in the area.

Equipment idled which cannot be used on other work, and which is authorized to standby on the project site by the Engineer, will be paid for according to Article 109.04(b)(4).

- (2) Major Delay. Labor will be the same as for a minor delay.

Equipment will be the same as for a minor delay, except Contractor-owned equipment will be limited to two weeks plus the cost of move-out to either the

Contractor's yard or another job and the cost to re-mobilize, whichever is less. Rental equipment may be paid for longer than two weeks provided the Contractor presents adequate support to the Department (including lease agreement) to show retaining equipment on the job is the most economical course to follow and in the public interest.

- (3) Reduced Rate of Production Delay. The Contractor will be compensated for the reduced productivity for labor and equipment time in excess of the 25 percent threshold for that portion of the delay in excess of seven calendar days. Determination of compensation will be in accordance with Article 104.02, except labor and material additives will not be permitted.

Payment for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be determined according to Article 109.13.”

Revise Article 108.04(b) of the Standard Specifications to read:

“(b) No working day will be charged under the following conditions.

- (1) When adverse weather prevents work on the controlling item.
- (2) When job conditions due to recent weather prevent work on the controlling item.
- (3) When conduct or lack of conduct by the Department or its consultants, representatives, officers, agents, or employees; delay by the Department in making the site available; or delay in furnishing any items required to be furnished to the Contractor by the Department prevents work on the controlling item.
- (4) When delays caused by utility or railroad adjustments prevent work on the controlling item.
- (5) When strikes, lock-outs, extraordinary delays in transportation, or inability to procure critical materials prevent work on the controlling item, as long as these delays are not due to any fault of the Contractor.
- (6) When any condition over which the Contractor has no control prevents work on the controlling item.”

Revise Article 109.09(f) of the Standard Specifications to read:

“(f) Basis of Payment. After resolution of a claim in favor of the Contractor, any adjustment in time required for the work will be made according to Section 108. Any adjustment in the costs to be paid will be made for direct labor, direct materials, direct equipment, direct jobsite overhead, direct offsite overhead, and other direct costs allowed by the resolution. Adjustments in costs will not be made for interest charges, loss of anticipated profit, undocumented loss of efficiency, home office overhead and unabsorbed overhead

other than as allowed by Article 109.13, lost opportunity, preparation of claim expenses and other consequential indirect costs regardless of method of calculation.

The above Basis of Payment is an essential element of the contract and the claim cost recovery of the Contractor shall be so limited.”

Add the following to Section 109 of the Standard Specifications.

**“109.13 Payment for Contract Delay.** Compensation for escalated material costs, escalated labor costs, extended project overhead, and extended traffic control will be allowed when such costs result from a delay meeting the criteria in the following table.

Contract Type	Cause of Delay	Length of Delay
Working Days	Article 108.04(b)(3) or Article 108.04(b)(4)	No working days have been charged for two consecutive weeks.
Completion Date	Article 108.08(b)(1) or Article 108.08(b)(7)	The Contractor has been granted a minimum two week extension of contract time, according to Article 108.08.

Payment for each of the various costs will be according to the following.

- (a) Escalated Material and/or Labor Costs. When the delay causes work, which would have otherwise been completed, to be done after material and/or labor costs have increased, such increases will be paid. Payment for escalated material costs will be limited to the increased costs substantiated by documentation furnished by the Contractor. Payment for escalated labor costs will be limited to those items in Article 109.04(b)(1) and (2), except the 35 percent and 10 percent additives will not be permitted.
- (b) Extended Project Overhead. For the duration of the delay, payment for extended project overhead will be paid as follows.
  - (1) Direct Jobsite and Offsite Overhead. Payment for documented direct jobsite overhead and documented direct offsite overhead, including onsite supervisory and administrative personnel, will be allowed according to the following table.

Original Contract Amount	Supervisory and Administrative Personnel
Up to \$5,000,000	One Project Superintendent
Over \$ 5,000,000 - up to \$25,000,000	One Project Manager, One Project Superintendent or Engineer, and One Clerk
Over \$25,000,000 - up to \$50,000,000	One Project Manager, One Project Superintendent, One Engineer, and

	One Clerk
Over \$50,000,000	One Project Manager, Two Project Superintendents, One Engineer, and One Clerk

(2) Home Office and Unabsorbed Overhead. Payment for home office and unabsorbed overhead will be calculated as 8 percent of the total delay cost.

(c) Extended Traffic Control. Traffic control required for an extended period of time due to the delay will be paid for according to Article 109.04.

When an extended traffic control adjustment is paid under this provision, an adjusted unit price as provided for in Article 701.20(a) for increase or decrease in the value of work by more than ten percent will not be paid.

Upon payment for a contract delay under this provision, the Contractor shall assign subrogation rights to the Department for the Department's efforts of recovery from any other party for monies paid by the Department as a result of any claim under this provision. The Contractor shall fully cooperate with the Department in its efforts to recover from another party any money paid to the Contractor for delay damages under this provision."

## CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)

Effective: June 1, 2010

Revised: November 1, 2014

The reduction of emissions of particulate matter (PM) for off-road equipment shall be accomplished by installing retrofit emission control devices. The term “equipment” refers to diesel fuel powered devices rated at 50 hp and above, to be used on the jobsite in excess of seven calendar days over the course of the construction period on the jobsite (including rental equipment).

Contractor and subcontractor diesel powered off-road equipment assigned to the contract shall be retrofitted using the phased in approach shown below. Equipment that is of a model year older than the year given for that equipment’s respective horsepower range shall be retrofitted:

Effective Dates	Horsepower Range	Model Year
June 1, 2010 <sup>1/</sup>	600-749	2002
	750 and up	2006
June 1, 2011 <sup>2/</sup>	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006
June 1, 2012 <sup>2/</sup>	50-99	2004
	100-299	2003
	300-599	2001
	600-749	2002
	750 and up	2006

1/ Effective dates apply to Contractor diesel powered off-road equipment assigned to the contract.

2/ Effective dates apply to Contractor and subcontractor diesel powered off-road equipment assigned to the contract.

The retrofit emission control devices shall achieve a minimum PM emission reduction of 50 percent and shall be:

- a) Included on the U.S. Environmental Protection Agency (USEPA) *Verified Retrofit Technology List* (<http://www.epa.gov/cleandiesel/verification/verif-list.htm>), or verified by the California Air Resources Board (CARB) (<http://www.arb.ca.gov/diesel/verdev/vt/cvt.htm>); or
- b) Retrofitted with a non-verified diesel retrofit emission control device if verified retrofit emission control devices are not available for equipment proposed to be used on the project, and if the Contractor has obtained a performance certification from the retrofit

device manufacturer that the emission control device provides a minimum PM emission reduction of 50 percent.

Note: Large cranes (Crawler mounted cranes) which are responsible for critical lift operations are exempt from installing retrofit emission control devices if such devices adversely affect equipment operation.

Diesel powered off-road equipment with engine ratings of 50 hp and above, which are unable to be retrofitted with verified emission control devices or if performance certifications are not available which will achieve a minimum 50 percent PM reduction, may be granted a waiver by the Department if documentation is provided showing good faith efforts were made by the Contractor to retrofit the equipment.

Construction shall not proceed until the Contractor submits a certified list of the diesel powered off-road equipment that will be used, and as necessary, retrofitted with emission control devices. The list(s) shall include (1) the equipment number, type, make, Contractor/rental company name; and (2) the emission control devices make, model, USEPA or CARB verification number, or performance certification from the retrofit device manufacturer. Equipment reported as fitted with emissions control devices shall be made available to the Engineer for visual inspection of the device installation, prior to being used on the jobsite.

The Contractor shall submit an updated list of retrofitted off-road construction equipment as retrofitted equipment changes or comes on to the jobsite. The addition or deletion of any diesel powered equipment shall be included on the updated list.

If any diesel powered off-road equipment is found to be in non-compliance with any portion of this special provision, the Engineer will issue the Contractor a diesel retrofit deficiency deduction.

Any costs associated with retrofitting any diesel powered off-road equipment with emission control devices shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall not be grounds for a claim.

### **Diesel Retrofit Deficiency Deduction**

When the Engineer determines that a diesel retrofit deficiency exists, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

The deficiency will be based on lack of diesel retrofit emissions control.

If a Contractor accumulates three diesel retrofit deficiency deductions for the same piece of equipment in a contract period, the Contractor will be shutdown until the deficiency is corrected.



Such a shutdown will not be grounds for any extension of the contract time, waiver of penalties, or be grounds for any claim.

80261

## **SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)**

Effective: April 2, 2018

Add the following to Section 109 of the Standard Specifications.

**“109.14 Subcontractor and Disadvantaged Business Enterprise Payment Reporting.**  
The Contractor shall report all payments made to the following parties:

- (a) first tier subcontractors;
- (b) lower tier subcontractors affecting disadvantaged business enterprise (DBE) goal credit;
- (c) material suppliers or trucking firms that are part of the Contractor’s submitted DBE utilization plan.

The report shall be made through the Department’s on-line subcontractor payment reporting system within 21 days of making the payment.”

80397

## **SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)**

Effective: November 2, 2017

Revised: April 1, 2019

Replace the second paragraph of Article 109.12 of the Standard Specifications with the following:

“This mobilization payment shall be made at least seven days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form BC 260A submitted for the approval of the subcontractor’s work.

Value of Subcontract Reported on Form BC 260A	Mobilization Percentage
Less than \$10,000	25%
\$10,000 to less than \$20,000	20%
\$20,000 to less than \$40,000	18%
\$40,000 to less than \$60,000	16%
\$60,000 to less than \$80,000	14%
\$80,000 to less than \$100,000	12%
\$100,000 to less than \$250,000	10%
\$250,000 to less than \$500,000	9%
\$500,000 to \$750,000	8%
Over \$750,000	7%”

80391

## WORK ZONE TRAFFIC CONTROL DEVICES (BDE)

Effective: March 2, 2020

Add the following to Article 701.03 of the Standard Specifications:

“(q) Temporary Sign Supports ..... 1106.02”

Revise the third paragraph of Article 701.14 of the Standard Specifications to read:

“For temporary sign supports, the Contractor shall provide a FHWA eligibility letter for each device used on the contract. The letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device. The signs shall be supported within 20 degrees of vertical. Weights used to stabilize signs shall be attached to the sign support per the manufacturer’s specifications.”

Revise the first paragraph of Article 701.15 of the Standard Specifications to read:

“**701.15 Traffic Control Devices.** For devices that must meet crashworthiness standards, the Contractor shall provide a manufacturer’s self-certification or a FHWA eligibility letter for each Category 1 device and a FHWA eligibility letter for each Category 2 and Category 3 device used on the contract. The self-certification or letter shall provide information for the set-up and use of the device as well as a detailed drawing of the device.”

Revise the first six paragraphs of Article 1106.02 of the Standard Specifications to read:

“**1106.02 Devices.** Work zone traffic control devices and combinations of devices shall meet crashworthiness standards for their respective categories. The categories are as follows.

Category 1 includes small, lightweight, channelizing and delineating devices that have been in common use for many years and are known to be crashworthy by crash testing of similar devices or years of demonstrable safe performance. These include cones, tubular markers, plastic drums, and delineators, with no attachments (e.g. lights). Category 1 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 1 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2024.

Category 2 includes devices that are not expected to produce significant vehicular velocity change but may otherwise be hazardous. These include vertical panels with lights, barricades, temporary sign supports, and Category 1 devices with attachments (e.g. drums with lights). Category 2 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 2 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2024.

Category 3 includes devices that are expected to cause significant velocity changes or other potentially harmful reactions to impacting vehicles. These include crash cushions (impact

attenuators), truck mounted attenuators, and other devices not meeting the definitions of Category 1 or 2. Category 3 devices manufactured after December 31, 2019 shall be MASH-16 compliant. Category 3 devices manufactured on or before December 31, 2019, and compliant with NCHRP 350 or MASH 2009, may be used on contracts let before December 31, 2029. Category 3 devices shall be crash tested for Test Level 3 or the test level specified.

Category 4 includes portable or trailer-mounted devices such as arrow boards, changeable message signs, temporary traffic signals, and area lighting supports. It is preferable for Category 4 devices manufactured after December 31, 2019 to be MASH-16 compliant; however, there are currently no crash tested devices in this category, so it remains exempt from the NCHRP 350 or MASH compliance requirement.

For each type of device, when no more than one MASH-16 compliant is available, an NCHRP 350 or MASH-2009 compliant device may be used, even if manufactured after December 31, 2019.”

Revise Articles 1106.02(g), 1106.02(k), and 1106.02(l) to read:

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.




Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”



ABV	ABOVE	CU YD	CUBIC YARD	HATCH	HATCHING	PM	PAVEMENT MARKING	STD	STANDARD
A/C	ACCESS CONTROL	CULV	CULVERT	HD	HEAD	PED	PEDESTAL	SBI	STATE BOND ISSUE
AC	ACRE	C&G	CURB & GUTTER	HDW	HEADWALL	PNT	POINT	SR	STATE ROUTE
ADJ	ADJUST	D	DEGREE OF CURVE	HDUTY	HEAVY DUTY	PC	POINT OF CURVATURE	STA	STATION
AS	AERIAL SURVEYS	DC	DEPRESSED CURVE	ha	HECTARE	PI	POINT OF INTERSECTION OF HORIZONTAL CURVE	SPBGR	STEEL PLATE BEAM GUARDRAIL
AGG	AGGREGATE	DET	DETECTOR	HMA	HOT MIX ASPHALT	PRC	POINT OF REVERSE CURVE	SS	STORM SEWER
AH	AHEAD	DIA	DIAMETER	HWY	HIGHWAY	PT	POINT OF TANGENCY	STY	STORY
APT	APARTMENT	DIST	DISTRICT	HORIZ	HORIZONTAL	POT	POINT ON TANGENT	ST	STREET
ASPH	ASPHALT	DOM	DOMESTIC	HSE	HOUSE	POLYETH	POLYETHYLENE	STR	STRUCTURE
AUX	AUXILIARY	DBL	DOUBLE	IL	ILLINOIS	PCC	PORTLAND CEMENT CONCRETE	e	SUPERELEVATION RATE
AGS	AUXILIARY GAS VALVE (SERVICE)	DSEL	DOWNSTREAM ELEVATION	IMP	IMPROVEMENT	PP	POWER POLE OR PRINCIPAL POINT	S.E. RUN.	SUPERELEVATION RUNOFF LENGTH
AVE	AVENUE	DSFL	DOWNSTREAM FLOWLINE	IN DIA	INCH DIAMETER	PRM	PRIME	SURF	SURFACE
AX	AXIS OF ROTATION	DR	DRAINAGE OR DRIVE	INL	INLET	PE	PRIVATE ENTRANCE	SMK	SURVEY MARKER
BK	BACK	DI	DRAINAGE INLET OR DROP INLET	INST	INSTALLATION	PE	PRIVATE ENTRANCE	T	TANGENT DISTANCE
B-B	BACK TO BACK	DRV	DRIVEWAY	IDS	INTERSECTION DESIGN STUDY	PROF	PROFILE	T.R.	TANGENT RUNOUT DISTANCE
BKPL	BACKPLATE	DCT	DUCT	INV	INVERT	PGL	PROFILE GRADELINE	TEL	TELEPHONE
B	BARN	EA	EACH	IP	IRON PIPE	PROJ	PROJECT	TB	TELEPHONE BOX
BARR	BARRICADE	EB	EASTBOUND	IR	IRON ROD	P.C.	PROPERTY CORNER	TP	TELEPHONE POLE
BL	BASELINE	EOP	EDGE OF PAVEMENT	JT	JOINT	PL	PROPERTY LINE	TEMP	TEMPORARY
BGN	BEGIN	E-CL	EDGE TO CENTERLINE	kg	KILOGRAM	PR	PROPOSED	TBM	TEMPORARY BENCH MARK
BM	BENCHMARK	E-E	EDGE TO EDGE	km	KILOMETER	R	RADIUS or RESIDENTIAL	TD	TILE DRAIN
BIND	BINDER	ELEC	ELECTRICAL	LS	LANDSCAPING	RR	RAILROAD	TBE	TO BE EXTENDED
BIT	BITUMINOUS	EL	ELEVATION	LN	LANE	RRS	RAILROAD SPIKE	TBR	TO BE REMOVED
BTM	BOTTOM	ENTR	ENTRANCE	LT	LEFT	RPS	REFERENCE POINT STAKE	TBS	TO BE SAVED
BLVD	BOULEVARD	EXC	EXCAVATION	LIDAR	LIGHT DETECTION AND RANGING	REF	REFLECTIVE	TWP	TOWNSHIP
BRK	BRICK	EX	EXISTING	LP	LIGHT POLE	RCCP	REINFORCED CONCRETE CULVERT PIPE	TR	TOWNSHIP ROAD
BBOX	BUFFALO BOX	EXPWAY	EXPRESSWAY	LGT	LIGHTING	REINF	REINFORCEMENT	TS	TRAFFIC SIGNAL
BLDG	BUILDING	E	EXTERNAL DISTANCE OF HORIZONTAL CURVE	LF	LINEAL FEET OR LINEAR FEET	REM	REMOVAL	TSCB	TRAFFIC SIGNAL CONTROL BOX
CATV	CABLE	E	OFFSET DISTANCE TO VERTICAL CURVE	L	LITER OR CURVE LENGTH	RC	REMOVE CROWN	TSC	TRAFFIC SYSTEMS CENTER
CIP	CAST IRON PIPE	F-F	FACE TO FACE	LC	LONG CHORD	REP	REPLACEMENT	TRVS	TRANSVERSE
CB	CATCH BASIN	FA	FEDERAL AID	LNG	LONGITUDINAL	REST	RESTAURANT	TRVL	TRAVEL
C-C	CENTER TO CENTER	FAI	FEDERAL AID INTERSTATE	L SUM	LUMP SUM	RESURF	RESURFACING	TRN	TURN
CL	CENTERLINE OR CLEARANCE	FAP	FEDERAL AID PRIMARY	MACH	MACHINE	RET	RETAINING	TY	TYPE
CL-E	CENTERLINE TO EDGE	FAS	FEDERAL AID SECONDARY	MB	MAIL BOX	RT	RIGHT	T-A	TYPE A
CL-F	CENTERLINE TO FACE	FAUS	FEDERAL AID URBAN SECONDARY	MH	MANHOLE	ROW	RIGHT-OF-WAY	TYP	TYPICAL
CTS	CENTERS	FP	FENCE POST	MATL	MATERIAL	RD	ROAD	UNDGND	UNDERGROUND
CERT	CERTIFIED	OPT	FIBER OPTIC	MED	MEDIAN	RDWY	ROADWAY	USGS	U.S. GEOLOGICAL SURVEY
CHSLD	CHISELED	FE	FIELD ENTRANCE	m	METER	RTE	ROUTE	USEL	UPSTREAM ELEVATION
CS	CITY STREET	FH	FIRE HYDRANT	METH	METHOD	SAN	SANITARY	USFL	UPSTREAM FLOWLINE
CP	CLAY PIPE	FL	FLOW LINE	M	MID-ORDINATE	SANS	SANITARY SEWER	UTIL	UTILITY
CLSD	CLOSED	FB	FOOT BRIDGE	mm	MILLIMETER	SEC	SECTION	VBOX	VALVE BOX
CLID	CLOSED LID	FDN	FOUNDATION	mm DIA	MILLIMETER DIAMETER	SEED	SEEDING	VV	VALVE VAULT
CT	COAT OR COURT	FR	FRAME	MIX	MIXTURE	SHAP	SHAPING	VL	VAULT
COMB	COMBINATION	F&G	FRAME & GRATE	MBH	MOBILE HOME	S	SHED	VEH	VEHICLE
C	COMMERCIAL BUILDING	FRWAY	FREEWAY	MOD	MODIFIED	SH	SHEET	VP	VENT PIPE
CE	COMMERCIAL ENTRANCE	GAL	GALLON	MFT	MOTOR FUEL TAX	SHLD	SHOULDER	VERT	VERTICAL
CONC	CONCRETE	GALV	GALVANIZED	N & BC	NAIL & BOTTLE CAP	SW	SIDEWALK OR SOUTHWEST	VC	VERTICAL CURVE
CONST	CONSTRUCT	G	GARAGE	N & C	NAIL & CAP	SIG	SIGNAL	VPC	VERTICAL POINT OF CURVATURE
CONTD	CONTINUED	GM	GAS METER	N & W	NAIL & WASHER	SOD	SODDING	VPI	VERTICAL POINT OF INTERSECTION
CONT	CONTINUOUS	GV	GAS VALVE	NC	NORMAL CROWN	SM	SOLID MEDIUM	VPT	VERTICAL POINT OF TANGENCY
COR	CORNER	GIS	GEOGRAPHICAL INFORMATION SYSTEM	NB	NORTHBOUND	SB	SOUTHBOUND	WM	WATER METER
CORR	CORRUGATED	GRAN	GRANULAR	NE	NORTHEAST	SE	SOUTHEAST	VV	WATER VALVE
CMP	CORRUGATED METAL PIPE	GR	GRATE	NW	NORTHWEST	SPL	SPECIAL	WMAIN	WATER MAIN
CNTY	COUNTY	GRVL	GRAVEL	O/S	OFFSET	SD	SPECIAL DITCH	WB	WESTBOUND
CH	COUNTY HIGHWAY	GND	GROUND	O&C	OIL AND CHIP	SQ FT	SQUARE FEET	WILDFL	WILDFLOWERS
CSE	COURSE	GUT	GUTTER	OLID	OPEN LID	m <sup>2</sup>	SQUARE METER	W	WITH
XSECT	CROSS SECTION	GP	GUY POLE	PAT	PATTERN	mm <sup>2</sup>	SQUARE MILLIMETER	WO	WITHOUT
m <sup>3</sup>	CUBIC METER	GW	GUY WIRE	PVD	PAVED	SQ YD	SQUARE YARD		
mm <sup>3</sup>	CUBIC MILLIMETER	HH	HANDHOLE	PVMT	PAVEMENT	STB	STABILIZED		

 Illinois Department of Transportation	
PASSED <u>January 1, 2021</u>  ENGINEER OF POLICY AND PROCEDURES	ISSUED 1-1-97
APPROVED <u>January 1, 2021</u>  ENGINEER OF DESIGN AND ENVIRONMENT	

DATE	REVISIONS
1-1-21	Updated fonts, abbreviations and symbols.
1-1-19	Added new symbols.

## STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS

(Sheet 1 of 9)


**STANDARD 000001-08**

<u>ADJUSTMENT ITEMS</u>		<u>EX</u>	<u>PR</u>	<u>ALIGNMENT ITEMS</u>		<u>EX</u>	<u>PR</u>	<u>DRAINAGE ITEMS</u>		<u>EX</u>	<u>PR</u>
Structure To Be Adjusted			ADJ	Baseline	_____	_____		Channel or Stream Line	-----	-----	
Structure To Be Cleaned			C	Centerline	-----	-----		Culvert Line	-----	-----	
Main Structure To Be Filled			FM	Centerline Break Circle	○	⊙		Grading & Shaping Ditches	-----	-----	
Structure To Be Filled			F	Baseline Symbol	⊥	⊥		Drainage Boundary Line	////	////	
Structure To Be Filled Special			FSP	Centerline Symbol		⊥		Paved Ditch	-----	-----	
Structure To Be Removed			R	PI Indicator	△	△		Aggregate Ditch	-----	-----	
Structure To Be Reconstructed			REC	Point Indicator	○	○		Pipe Underdrain	-----	-----	
Structure To Be Reconstructed Special			RSP	Horizontal Curve Data (Half Size)	EX. CURVE P.I. STA= Δ= D= R= T= L= E= e= T.R.= S.E. RUN= P.C. STA= P.T. STA=	CURVE P.I. STA= Δ= D= R= T= L= E= e= T.R.= S.E. RUN= P.C. STA= P.T. STA=		Storm Sewer	-----	-----	
Frame and Grate To Be Adjusted			A	<u>BOUNDARIES ITEMS</u>		<u>EX</u>	<u>PR</u>	Flowline	⊥	⊥	
Frame and Lid To Be Adjusted			A	Dashed Property Line	-----	-----		Ditch Check	◆	◆	
Domestic Service Box To Be Adjusted			A	Solid Property/Lot Line	_____	_____		Headwall	-	∩	
Valve Vault To Be Adjusted			A	Section/Grant Line	-----	-----		Inlet	□	■	
Special Adjustment			SP	Quarter Section Line	-----	-----		Manhole	⊙	⊙	
Item To Be Abandoned			AB	Quarter/Quarter Section Line	-----	-----		Summit	↔	↔	
Item To Be Moved			M	County/Township Line	-----	-----		Roadway Ditch Flow	~→	~→	
Item To Be Relocated			REL	State Line	-----	-----		Swale	→	→	
Pavement Removal and Replacement				Chiseled Square Found	□	□		Catch Basin	○	●	
				Iron Pipe Found	○	●		Culvert End Section	◁	◁	
				Iron Pipe Set	●	●		Water Surface Indicator	▽	▽	
				Survey Marker	⊙	⊙		Riprap	▒	▒	
				Property Line Symbol	⊥	⊥		<u>HYDRAULICS ITEMS</u>		<u>EX</u>	<u>PR</u>
				Same Ownership Symbol (Half Size)	↗	↗		Overflow	↪	↪	
				Northwest Quarter Corner (Half Size)	⊙	⊙		Sheet Flow	→	→	
				Section Corner (Half Size)	⊙	⊙		Hydrant Outlet	→	→	
				Southeast Quarter Corner (Half Size)	⊙	⊙					

**STANDARD SYMBOLS,  
ABBREVIATIONS  
AND PATTERNS**  
(Sheet 2 of 9)  
**STANDARD 000001-08**

Illinois Department of Transportation

PASSED January 1, 2021  
  
 ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97




**EROSION & SEDIMENT CONTROL ITEMS**

**EX**

**PR**

- Cleaning & Grading Limits
- Dike
- Erosion Control Fence
- Perimeter Erosion Barrier
- Temporary Fence
- Ditch Check Temporary
- Ditch Check Permanent
- Inlet & Pipe Protection
- Sediment Basin
- Erosion Control Blanket
- Fabric Formed Concrete Revetment Mat
- Turf Reinforcement Mat
- Mulch Temporary
- Mulch Method 1
- Mulch Method 2 Stabilized
- Mulch Method 3 Hydraulic




**CONTOUR ITEMS**

**EX**

**PR**

- Approx. Index Line
- Approx. Intermediate Line
- Index Contour
- Intermediate Contour




**NON-HIGHWAY IMPROVEMENT ITEMS**

**EX**

**PR**

- Noise Attn./Levee
- Field Line
- Fence
- Base of Levee
- Mailbox
- Multiple Mailboxes
- Pay Telephone
- Advertising Sign
- ITS\* Camera
- Wind Turbine
- Cellular Tower




\*Intelligent Transportation Systems

**LANDSCAPING ITEMS**

**EX**

**PR**

- Contour Mounding Line
- Fence
- Fence Post
- Shrubs
- Mowline
- Perennial Plants
- Seeding Class 2
- Seeding Class 2A
- Seeding Class 4
- Seeding Class 4 & 5 Combined




**EXISTING LANDSCAPING ITEMS (contd.)**

**EX**

**PR**

- Seeding Class 5
- Seeding Class 7
- Seedlings Type 1
- Seedlings Type 2
- Sodding
- Mowstake w/Sign
- Tree Trunk Protection
- Evergreen Tree
- Shade Tree




**LIGHTING**

**EX**

**PR**

- Duct
- Conduit
- Electrical Aerial Cable
- Electrical Buried Cable
- Controller
- Underpass Luminaire
- Power Pole



Illinois Department of Transportation

PASSED January 1, 2021  
*Michael Bond*  
 ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
*Joe E. Cole*  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS**  
 (Sheet 3 of 9)

**STANDARD 000001-08**

**LIGHTING  
(contd.)**

**EX**

**PR**

Pull Point



Handhole



Heavy Duty Handhole



Junction Box



Light Unit Comb.



Electrical Ground



Traffic Flow Arrow



High Mast Pole  
(Half Size)



Light Unit-1




**PAVEMENT (MISC.)**


**EX**

**PR**


Keyed Long. Joint



Keyed Long. Joint w/Tie Bars



Sawed Long. Joint w/Tie Bars




Bituminous Shoulder



Bituminous Taper



Stabilized Driveway



Widening



**PAVEMENT MARKINGS**


**EX**

**PR**

Handicap Symbol



RR Crossing



Raised Marker Amber 1 Way




Raised Marker Amber 2 Way





Raised Marker Crystal 1 Way



Two Way Turn Left




Shoulder Diag. Pattern



Skip-Dash White




Skip-Dash Yellow




Stop Line




Solid Line



Double Centerline



Dotted Lines



Illinois Department of Transportation

PASSED January 1, 2021  
  
 ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS,  
ABBREVIATIONS  
AND PATTERNS**

(Sheet 4 of 9)

**STANDARD 000001-08**

**PAVEMENT MARKINGS**  
**(contd.)**

CL 2Ln 2Way  
RRPM 12.2 m (40') o.c.

CL 2Ln 2Way  
RRPM 80' (24.4 m) o.c.

CL Multilane Div.  
RRPM 40' (12.2 m) o.c.

CL Multilane Div.  
RRPM 80' (24.4 m) o.c.

CL Multilane Div. Dbl.  
RRPM 80' (24.4 m) o.c.

CL Multilane Undiv.

Two Way Turn Left Line

Urban Combination Left

Urban Combination Right

Urban Left Turn Arrow

Urban Right Turn Arrow


Urban Left Turn Only

Urban Right Turn Only

Urban Thru Only

**EX**

**PR**



ONLY  
ONLY  
ONLY



**RAILROAD ITEMS**

**EX**

**PR**

Abandoned Railroad



Railroad



Railroad Point



Control Box



Crossing Gate



Flashing Signal



Railroad Cant. Mast Arm



Crossbuck




**REMOVAL ITEMS**


**EX**

**PR**


Removal Tic



Bituminous Removal



Hatch Pattern



Tree Removal Single



**RIGHT OF WAY ITEMS**

**EX**

**PR**


Future ROW Corner Monument



ROW Marker




ROW Line



Easement



Temporary Easement



**STANDARD SYMBOLS,  
ABBREVIATIONS  
AND PATTERNS**

(Sheet 5 of 9)

**STANDARD 000001-08**

Illinois Department of Transportation

PASSED January 1, 2021  
*Michael Bond*  
ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
*Scott Clark*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

Urban LT & RT Turn Arrow

Urban Thru Arrow

**PAVEMENT MARKINGS**  
**(contd.)**

**EX**

**PR**

Urban U-Turn



Urban Combined U-Turn



Rural Combination Left



Rural Combination Right




Rural Left Turn Arrow



Rural Right Turn Arrow




Rural Left Turn Only





**ONLY ONLY ONLY**



Rural Right Turn Only



Rural Thru Only




Rural Thru Arrow



Rural Lt & Rt Turn Arrow



Bike Lane Symbol



Bike Lane Text



Bike Path Shared



Bike Shared Roadway



Lane Drop Symbol



Wrong Way Arrow



Illinois Department of Transportation  
 PASSED January 1, 2021  
  
 ENGINEER OF POLICY AND PROCEDURES  
 APPROVED January 1, 2021  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS,  
 ABBREVIATIONS  
 AND PATTERNS**  
(Sheet 6 of 9)  
**STANDARD 000001-08**

**RIGHT OF WAY ITEMS**  
**(contd.)**

	<b>EX</b>	<b>PR</b>
Access Control Line	—	— AC —
Access Control Line & ROW	— AC —	— AC —
Access Control Line & ROW with Fence	— x — AC —	— x — AC — x —
Excess ROW Line		— XS —

**ROADWAY PLAN**  
**ITEMS**

	<b>EX</b>	<b>PR</b>
Cable Barrier		
Concrete Barrier		
Edge of Pavement	---	---
Bit Shoulders, Medians and C&G Line	---	---
Aggregate Shoulder	---	---
Sidewalks, Driveways	---	---
Guardrail		
Guardrail Post	□	□
Traffic Sign		
Corrugated Median		
Impact Attenuator		
North Arrow with District Office (Half Size)		
Match Line		STA. 45+00
Slope Limit Line	---	
Typical Cross-Section Line	---	---

**ROADWAY PROFILES**

	<b>EX</b>	<b>PR</b>
P.I. Indicator	△	△
Point Indicator	○	○
Earthworks Balance Point		
Begin Point		
Vert. Curve Data	VPI = ELEV = L = E =	VPI = ELEV = L = E =
Ditch Profile Left Side	---	---
Ditch Profile Right Side	---	---
Roadway Profile Line	---	---
Storm Sewer Profile Left Side	---	---
Storm Sewer Profile Right Side	---	---

**SIGNING ITEMS**

	<b>EX</b>	<b>PR</b>
Cone, Drum or Barricade		○
Barricade Type II		
Barricade Type III		TT
Barricade With Edge Line		
Flashing Light Sign		○
Panels I		
Panels II		
Direction of Traffic		
Sign Flag (Half Size)		

**SIGNING ITEMS**  
**(contd.)**

	<b>EX</b>	<b>PR</b>
Reverse Left W1-4L (Half Size)		
Reverse Right W1-4R (Half Size)		
Two Way Traffic Sign W6-3 (Half Size)		
Detour Ahead W20-2(O) (Half Size)		
Left Lane Closed Ahead W20-5L(O) (Half Size)		
Right Lane Closed Ahead W20-5R(O) (Half Size)		
Road Closed Ahead W20-3(O) (Half Size)		
Road Construction Ahead W20-1(O) (Half Size)		
Single Lane Ahead (Half Size)		
Transition Left W4-2L (Half Size)		
Transition Right W4-2R (Half Size)		

Illinois Department of Transportation

PASSED January 1, 2021  
*Michael Bond*  
ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
*Joe E. Cole*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS,  
ABBREVIATIONS  
AND PATTERNS**  
(Sheet 7 of 9)


**STANDARD 000001-08**

**SIGNING ITEMS**  
**(contd.)**


**EX**

**PR**

One Way Arrow Lrg. W1-6-(O)  
(Half Size)



Two Way Arrow Large W1-7-(O)  
(Half Size)



Detour M4-10L-(O)  
(Half Size)



Detour M4-10R-(O)  
(Half Size)



One Way Left R6-1L  
(Half Size)



One Way Right R6-1R  
(Half Size)



Left Turn Lane R3-I100L  
(Half Size)



Keep Left R4-7AL  
(Half Size)



Keep Left R4-7BL  
(Half Size)



Keep Right R4-7AR  
(Half Size)



Keep Right R4-7BR  
(Half Size)



Stop Here On Red R10-6-AL  
(Half Size)



Stop Here On Red R10-6-AR  
(Half Size)




No Left Turn R3-2  
(Half Size)




No Right Turn R3-1  
(Half Size)



Road Closed R11-2  
(Half Size)



Road Closed Thru Traffic R11-2  
(Half Size)




**STRUCTURES ITEMS**

**EX**

**PR**


Box Culvert Barrel



Box Culvert Headwall




Bridge Pier



Bridge



Retaining Wall



Temporary Sheet Piling



**TRAFFIC SHEET**  
**ITEMS**

**EX**

**PR**

Cable Number





Left Turn Green



Left Turn Yellow



Signal Backplate



Signal Section 8" (200 mm)



Signal Section 12" (300 mm)



Walk/Don't Walk Letters



Walk/Don't Walk Symbols



**TRAFFIC SIGNAL**  
**ITEMS**


**EX**

**PR**

Galv. Steel Conduit



Underground Cable



Detector Loop Line



Detector Loop Large



Detector Loop Small



Detector Loop Quadrapole



Illinois Department of Transportation

PASSED January 1, 2021  
*Michael Bond*  
ENGINEER OF POLICY AND PROCEDURES

APPROVED January 1, 2021  
*Joe E. Cline*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS,  
ABBREVIATIONS  
AND PATTERNS**  
(Sheet 8 of 9)

**STANDARD 000001-08**

**TRAFFIC SIGNAL ITEMS (contd.)**

	<b>EX</b>	<b>PR</b>
Detector Raceway		
Aluminum Mast Arm		
Steel Mast Arm		
Veh. Detector Magnetic		
Conduit Splice		
Controller		
Gulfbox Junction		
Wood Pole		
Temp. Signal Head		
Handhole		
Double Handhole		
Heavy Duty Handhole		
Junction Box		
Ped. Pushbutton Detector		
Ped. Signal Head		
Power Pole Service		
Priority Veh. Detector		
Signal Head		
Signal Head w/Backplate		
Signal Post		
Closed Circuit TV		
Video Detector System		

**UNDERGROUND UTILITY ITEMS**

	<b>EX</b>	<b>PR</b>	<b>ABANDONED</b>
Cable TV			
Electric Cable			
Fiber Optic			
Gas Pipe			
Oil Pipe			
Sanitary Sewer			
Telephone Cable			
Water Pipe			

**UTILITIES ITEMS**

	<b>EX</b>	<b>PR</b>
Controller		
Double Handhole		
Fire Hydrant		
GuyWire or Deadman Anchor		
Handhole		
Heavy Duty Handhole		
Junction Box		
Light Pole		
Manhole		
Monitoring Well (Gasoline)		
Pipeline Warning Sign		
Power Pole		
Power Pole with Light		
Sanitary Sewer Cleanout		
Splice Box Above Ground		
Telephone Splice Box Above Ground		
Telephone Pole		

**UTILITY ITEMS (contd.)**

	<b>EX</b>	<b>PR</b>
Traffic Signal		
Traffic Signal Control Box		
Water Meter		
Water Meter Valve Box		
Profile Line		
Aerial Power Line		

**VEGETATION ITEMS**

	<b>EX</b>	<b>PR</b>
Deciduous Tree		
Bush or Shrub		
Evergreen Tree		
Stump		
Orchard/Nursery Line		
Vegetation Line		
Woods & Bush Line		

**WATER FEATURE ITEMS**

	<b>EX</b>	<b>PR</b>
Stream or Drainage Ditch		
Waters Edge		
Water Surface Indicator		
Water Point		
Disappearing Ditch		
Marsh		
Marsh/Swamp Boundary		

Illinois Department of Transportation

PASSED January 1, 2021  
  
 ENGINEER OF POLICY AND PROCEDURES


APPROVED January 1, 2021  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS**  
 (Sheet 9 of 9)

**STANDARD 000001-08**

- ① Devices at 20' (6 m) centers in the taper.
- ② Cones at 25' (8 m) centers for the first 150' (45 m). Additional cones may be placed at 50' (15 m) centers. When drums or barricades are used, these intervals between devices may be doubled.



**TYPICAL APPLICATIONS**

- Isolated patching
- Utility operations
- Storm sewer
- Culverts
- Cable placement

**SYMBOLS**

- Work area
- Sign
- Barricade or drum
- Cone, drum or barricade
- Flagger with traffic control sign

**GENERAL NOTES**

This Standard is used where at any time, any vehicles, equipment, workers or their activities will encroach in the area between the center line and a line 24 (600) outside the edge of pavement for daylight operation.

When the distance between successive work areas exceeds 2000' (600 m), additional warning signs, flaggers, and taper shall be placed as shown.

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

APPROVED January 1, 2019  
  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2019  
  
 ENGINEER OF DESIGN AND ENVIRONMENT




ISSUED 1-1-97

DATE	REVISIONS
1-1-19	Revised device spacing in taper.
1-1-11	Revised flagger sign.

**LANE CLOSURE, 2L, 2W,  
DAY ONLY,  
FOR SPEEDS ≥ 45 MPH**

**STANDARD 701201-05**





SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

**TYPICAL APPLICATIONS**

- Marking patches
- Field survey
- String line
- Utility operations
- Cleaning up debris on pavement

**SYMBOLS**

- Work area
- Sign on portable or permanent support
- Flagger with traffic control sign

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-11	Revised flagger sign.
1-1-09	Switched units to English (metric).

**LANE CLOSURE, 2L, 2W,  
SHORT TIME OPERATIONS**



**STANDARD 701301-04**

Illinois Department of Transportation

PASSED January 1, 2011  
  
 ENGINEER OF SAFETY ENGINEERING

ISSUED 1-1-97

APPROVED January 1, 2011  
  
 ENGINEER OF DESIGN AND ENVIRONMENT



For contract construction projects:  
 W20-1103(0)-48 (Road Construction Ahead)  
 W20-4(0)-48 (One Lane Road Ahead)  
 W20-7(0)-48 (Flagger Ahead)

For maintenance and utility projects:  
 W20-1(0)-48 (Road Work Ahead)

**TYPICAL APPLICATIONS**

- Bituminous resurfacing
- Milling operations
- Utility operations
- Shoulder operations

**SYMBOLS**

- Work area
- Sign on portable or permanent support
- Flagger with traffic control sign

① Minimum distance is 200' (60 m). Maximum distance to be determined by the Engineer but should not exceed ½ the length required for one normal working day's operation or 2 miles (3200 m), whichever is less.

**GENERAL NOTES**

This Standard is used where at any time, any vehicle, equipment, workers or their activities require an intermittent or continuous moving operation on the pavement where the average speed of movement is greater than ½ mph (1 km/h) and less than 4 mph (6 km/h).

When the operation does not exceed 60 minutes, traffic control may be according to Standard 701301.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-18	Revised lower speed limit for operation to ½ mph.
1-1-11	Revised flagger sign.

**LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH**


**STANDARD 701306-04**

Illinois Department of Transportation

PASSED January 1, 2018  
  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2018  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97







\* Distance varies depending on terrain and susceptibility of pavement marking or crack sealant to wheel tracking.

**TYPICAL APPLICATIONS**

- Landscaping work
- Utility work
- Pavement marking
- Weed spraying
- Roadometer measurements
- Debris cleanup
- Crack pouring

**SYMBOLS**

-  Arrow board (Hazard Mode only)
-  Truck with headlights, emergency flashers and flashing amber light. (visible from all directions)
-  18x18 (450x450) min. orange flag (use when guide wheel is used)
-  Truck mounted attenuator

**GENERAL NOTES**

This Standard is used where any vehicle, equipment, workers or their activities will require a continuous moving operation where the average speed is greater than 3 mph (5 km/h).

For shoulder operations not encroaching on the pavement, use DETAIL A, Standard 701426.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-09	Switched units to English (metric). Omitted Pass With Care sign.
1-1-00	Elim. speed restrictions in Standard title.

**LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY**

**STANDARD 701311-03**

Illinois Department of Transportation


PASSED January 1, 2009

ENGINEER OF OPERATIONS

APPROVED January 1, 2009

ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97



**GENERAL NOTES**

This Standard is used where at any time, any vehicle, equipment, workers or their activities will encroach in the area between the center line and a line 24 (600) outside the edge of the pavement.

Two flaggers shall be required for each separate lane closure. The flagger shall be a minimum of 200' (60 m) and a maximum of 1/2 day's operation beyond the flagger sign. When the distance between successive patches exceeds 2000' (600 m), additional flaggers, warning signs, and tapers shall be placed as shown.

Barricades/drums shall be placed at intervals not greater than 100' (30 m) or cones shall be placed at intervals not greater than 50' (15 m) centers throughout the work zone. When the spacing between open holes is greater than 50' (15 m), two barricades/drums shall be placed in front of each open hole and one on the backside close to the centerline. When the open hole is greater than 10' (3 m) parallel to the centerline, one barricade/drum shall be placed in each hole. For large holes, barricades/drums shall be placed at 50' (16 m) centers.

All dimensions are in inches (millimeters) unless otherwise shown.

**SYMBOLS**

- ▨ Patches
- ⊥ Sign
- Flagger with traffic control sign
- I Barricade or drum
- Cone, barricade or drum

① 1/2 mile (800 m) maximum

**TYPICAL APPLICATIONS**

Patching

For contract construction projects  
ROAD CONSTRUCTION AHEAD  
W20-1103(0)-48  
Or

For maintenance and utility projects  
ROAD WORK AHEAD  
W20-1(0)-48

Illinois Department of Transportation

APPROVED January 1, 2019  
*Cynthia Watt*  
ENGINEER OF SAFETY PROG. AND ENGINEERING




APPROVED January 1, 2019  
*Joe E. ...*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

DATE	REVISIONS
1-1-19	Revised device spacing in taper.
1-1-11	Revised flagger sign.

**LANE CLOSURE, 2L, 2W,  
WORK AREAS IN SERIES,  
FOR SPEEDS ≥ 45 MPH**

**STANDARD 701336-07**



L = lane width X taper ratio	
Normal Posted Speed	Taper Ratio
mph	
55	55/1
45	45/1

**SYMBOLS**

- Arrow board
- Work area
- Sign
- Direction indicator barricade
- Cone, drum or barricade
- Flagger with traffic control sign
- Worker
- Type II barricade, drum, or vertical barricade with monodirectional flashing light

**TYPICAL APPLICATIONS**

- Pavement patch
- Utility operations
- Bituminous resurfacing

- ① Undivided roadway only with left lane closure in opposite direction.
- ② Omitted when median is less than 10' (3 m).
- ③ FLAGGER signs shall be moved as necessary to maintain the required spacing between the sign and each separate work activity.
- ④ Three Type II barricades, drums, or vertical barricades at 25' (8 m) centers.

**GENERAL NOTES**

This Standard is used where at any time, any vehicle, equipment, workers or their activities will encroach on the lane adjacent to the shoulder, or on the shoulder within 24 (600) of the edge of pavement.

This Standard also applies when work is being performed in the left lane. Under these conditions, LEFT LANE CLOSED signs shall be substituted for RIGHT LANE CLOSED signs. On undivided highways, signs shall be added in the opposite direction as shown.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-17	Rev. END WORK ZONE SPEED LIMIT sign. Changed device spacing at first arr. brd.
1-1-15	Revised END WORK ZONE SPEED LIMIT sign dimensions.

**LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS ≥ 45 MPH TO 55 MPH**

**STANDARD 701421-08**

Illinois Department of Transportation


PASSED January 1, 2017

ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2017

ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 4-1-04



For contract construction projects

ROAD CONSTRUCTION 1 MILE  
W20-1103(0)-48

RIGHT LANE CLOSED 1/2 MILE  
W20-5(0)-48

W4-2R(0)-48

For maintenance and utility projects

ROAD WORK 1 MILE  
W20-1(0)-48

L = lane width X taper ratio	
Normal Posted Speed	Taper Ratio
mph	
55	55/1
45	45/1

WORK ZONE  
W21-III5(0)-3618

SPEED LIMIT  
R2-1-3648

45

PHOTO ENFORCED  
R10-1108p-3618

SXXX FINE MINIMUM  
R2-1106p-3618

**SYMBOLS**

- Arrow board
- Work area
- Sign
- Direction indicator barricade with steady burn monodirectional light
- Type II barricade, drum, or vertical barricade
- Flagger with traffic control sign
- Worker
- Type II barricade, drum, or vertical barricade with monodirectional flashing light

- ① Undivided roadway only with left lane closure in opposite direction.
- ② Omitted when median is less than 10' (3 m).
- ③ ReflectORIZED temporary pavement marking tape shall be placed throughout the taper and for 300' (90 m) along-side the work area where the closure time is greater than fourteen days. The edge line shall be white for right lane closures and yellow for left lane closures.
- ④ FLAGGER signs shall be moved as necessary to maintain the required spacing between the sign and each separate work activity.
- ⑤ Three Type II barricades, drums, or vertical barricades at 25' (8 m) centers.

**GENERAL NOTES**

This standard is used where at any time any vehicle, equipment, workers or their activities will encroach on the lane adjacent to the shoulder, or on the shoulder within 24 (600) of the edge of pavement for daylight operation exceeding one day.

This standard also applies when work is being performed in the left lane. Under these conditions LEFT LANE CLOSED signs shall be substituted for RIGHT LANE CLOSED signs. On undivided highways, signs shall be added in the opposite direction as shown.

A check barricade shall be placed in the middle of the closed lane and at the shoulder at 1000' (300 m) centers.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-18	Omitted lights in tangent.
1-1-17	Rev. END WORK ZONE SPEED LIMIT sign. Changed device spacing at first arr. brd.

**LANE CLOSURE, MULTILANE, FOR SPEEDS ≥ 45 MPH TO 55 MPH**

**STANDARD 701422-10**

Illinois Department of Transportation


PASSED January 1, 2018

ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2018


ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 4-1-04



NOTE  
When a shoulder does not exist or is narrow, use Detail B.


**DETAIL A**



**DETAIL C**  
\* Required when workers are on the pavement.

**TYPICAL APPLICATIONS**

- Landscaping work
- Utility work
- Pavement marking
- Weed spraying
- Roadometer measurements
- Debris cleanup
- Crack pouring



**DETAIL B**

- ① Flaggers are required when workers are on the pavement.
- ② For striping operations only. See sign arrow detail on this standard.
- ③ For stationary operations which are on the roadway or shoulder, greater than 15 minutes and up to 1 hour.
- ④ The distance between the work and the lead truck may vary according to terrain or paint/crack sealing drying time.



G20-1101-2430  
(appropriate arrow)  
② (when striping only)

**GENERAL NOTES**

This Standard is used where any vehicle, equipment, workers or their activities will require:  
1) stationary operations up to 1 hour, or 2) a continuous or intermittent moving operation where the average speed of movement is greater than 1 mph (2 km/h).

This Standard is also applicable when work is being performed in the left lane(s) or on the median shoulder. Under these conditions, KEEP RIGHT signs shall be substituted for KEEP LEFT signs and arrow board indications shall be directed to the right.

All dimensions are in inches (millimeter) unless otherwise shown.

**SYMBOLS**

- ↑ Arrow board
- ▨ Work area
- 🚚 Truck with flashing amber light
- 🚛 Truck/Trailer mounted attenuator
- Flagger with traffic control sign
- 🚧 Sign

DATE	REVISIONS
1-1-17	Revised 'NOTE' on DETAIL A to use DETAIL B in lieu of DETAIL C.
4-1-16	Added trailer option for attenuator symbol. Added note ④. Revised gen. notes.

**LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≥ 45 MPH**


**STANDARD 701426-09**

Illinois Department of Transportation

PASSED January 1, 2017  
*Paul L. ...*  
ENGINEER OF SAFETY PROG. AND ENGINEERING


APPROVED January 1, 2017  
*Matthew M. ...*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97



NOTE  
When a shoulder does not exist or is narrow, use Detail B.


**DETAIL A**



**DETAIL C**  
\* Required when workers are on the pavement.

**TYPICAL APPLICATIONS**

- Landscaping work
- Utility work
- Pavement marking
- Weed spraying
- Roadometer measurements
- Debris cleanup
- Crack pouring



**DETAIL B**

- ① Flagger is required when workers are on the pavement.
- ② For striping operations only. See sign arrow detail on this standard.
- ③ For stationary operations which are on the roadway or shoulder, greater than 15 minutes and up to 1 hour.
- ④ Omit truck, attenuator and arrow board when no shoulder exists due to curb and gutter.
- ⑤ The distance between the work and the lead truck may vary according to terrain or paint/crack sealing time.



G20-1101-2430  
(appropriate arrow)  
② (when striping only)

**GENERAL NOTES**

This Standard is used where any vehicle, equipment, workers or their activities will require:  
1) stationary operations up to 1 hour, or 2) a continuous or intermittent moving operation where the average speed of movement is greater than 1 mph (2 km/h).

This Standard is also applicable when work is being performed in the left lane(s) or on the median shoulder. Under these conditions, KEEP RIGHT signs shall be substituted for KEEP LEFT signs and arrow board indications shall be directed to the right.

All dimensions are in inches (millimeter) unless otherwise shown.

**SYMBOLS**

- Arrow board
- Work area
- Truck with flashing amber light
- Truck/Trailer mounted attenuator
- Flagger with traffic control sign
- Sign

DATE	REVISIONS
1-1-17	Revised 'NOTE' on DETAIL A to use DETAIL B in lieu of DETAIL C.
4-1-16	Rev. gen. notes. Added note ⑤. Rev. dist. between work and lead truck.

**LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≤ 40 MPH**

**STANDARD 701427-05**



Illinois Department of Transportation

PASSED January 1, 2017  
*Paul L. ...*  
ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2017  
*Maureen M. ...*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-17





Illinois Department of Transportation

PASSED January 1, 2018  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2018  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

DATE	REVISIONS
1-1-18	Omitted lights on drums in tangent for westbound traffic and at work area.
1-1-17	Replaced W18-1100 plaque with W7-3a plaque. Changed flexible delineator to tubular marker.

**GENERAL NOTES**


This Standard is used where at any time, any vehicle, equipment, workers or their activities require the closure of two adjacent lanes and a temporary crossover is provided by making use of one lane of pavement normally used by opposing flow of traffic and flexible delineators are used to separate the opposing traffic.

Cones may be substituted for flexible delineators during daytime operations at half the spacing.

All dimensions are in inches (millimeters) unless otherwise shown.

**LANE CLOSURE, MULTILANE, UNDIV. WITH CROSSOVER, FOR SPEEDS ≥ 45 MPH TO 55 MPH**

**STANDARD 701431-13**



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

**SYMBOLS**

- Work area
- Cone, drum or barricade (not required for moving operations)
- Sign on portable or permanent support
- Flagger with traffic control sign
- Barricade or drum with flashing light
- Type III barricade with flashing lights

- ① Refer to SIGN SPACING TABLE for distances.
- ② For approved sideroad closures.
- ③ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ④ Cones, drums or barricades at 20' (6 m) centers.

**GENERAL NOTES**

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of one traffic lane in an urban area.

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

PASSED January 1, 2011  
  
 ENGINEER OF SAFETY ENGINEERING


APPROVED January 1, 2011  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

DATE	REVISIONS
1-1-11	Revised flagger sign.
1-1-09	Switched units to English (metric).
	Corrected sign No.'s.

**URBAN LANE CLOSURE,  
2L, 2W, UNDIVIDED**

**STANDARD 701501-06**



**CASE I**

(Signs required for both directions)

SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

**SYMBOLS**

- Work area
- Barricade or drum with flashing light
- Flagger with traffic control sign
- Cone, drum or barricade
- Sign on portable or permanent support
- Type III barricade with flashing lights

- ① Refer to SIGN SPACING TABLE for distances.
- ② Required for speeds > 40 mph (70 km/h).
- ③ Required if work exceeds 500' (164 m) or 1 block.
- ④ Cones at 25' (8 m) centers for 250' (75 m) on approach. Additional cones may be placed at 50' (15 m) centers. When drums or type I or II barricades are used, the interval between devices may be doubled.
- ⑤ For approved sideroad closures.
- ⑥ Cones, drums or barricades at 20' (6 m) centers in taper.
- ⑦ Use flagger sign only when flagger is present.

**GENERAL NOTES**

This Standard is used to close one lane of an urban, two lane, two way roadway with a bidirectional turn lane.

Case I applies when no workers are present. When workers are present, two lanes shall be closed and traffic control shall be according to Standard 701501.

Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L = (W)(S)$	$L = 0.65(W)(S)$

W = Width of offset in feet (meters).  
S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

APPROVED January 1, 2019  
*Lyndee Watt*  
ENGINEER OF SAFETY PROG. AND ENGINEERING


APPROVED January 1, 2019  
*J. E. ...*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-01

DATE	REVISIONS
1-1-19	Revised to allow cones at night.
1-1-18	Corrected sign number for TWO WAY TRAFFIC sign for CASE II.

**URBAN LANE CLOSURE,  
2L, 2W, WITH BIDIRECTIONAL  
LEFT TURN LANE**  
(Sheet 1 of 2)

**STANDARD 701502-09**



**CASE II**

Illinois Department of Transportation

APPROVED January 1, 2019  
*Cynthia Watt*  
 ENGINEER OF SAFETY PROG. AND ENGINEERING


APPROVED January 1, 2019  
*J. E. ...*  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-01

**URBAN LANE CLOSURE,  
 2L, 2W, WITH BIDIRECTIONAL  
 LEFT TURN LANE**








(Sheet 2 of 2)

**STANDARD 701502-09**



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

### SYMBOLS

-  Arrow board
-  Cone, drum or barricade
-  Sign on portable or permanent support
-  Work area
-  Barricade or drum with flashing light
-  Type III barricade with flashing lights
-  Flagger with traffic control sign.

- ① Refer to SIGN SPACING TABLE for distances.
- ② Required for speeds > 40 MPH
- ③ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ④ Use flagger sign only when flagger is present.
- ⑤ For approved sideroad closures.
- ⑥ Cones, drums or barricades at 20' (6 m) in taper.

### GENERAL NOTES

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement during shoulder operations or where construction requires lane closures in urban areas.


Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L = (W)(S)$	$L = 0.65(W)(S)$


W = Width of offset in feet (meters).  
S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

PASSED January 1, 2014  
  
 ENGINEER OF SAFETY ENGINEERING

ISSUED 1-1-97


APPROVED January 1, 2014  
  
 ENGINEER OF DESIGN AND ENVIRONMENT




DATE	REVISIONS
1-1-14	Revised workers sign number to agree with current MUTCD.
1-1-13	Omitted text 'WORKERS' sign.

## URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN

(Sheet 1 of 2)

STANDARD 701601-09




 Illinois Department of Transportation  
 PASSED January 1, 2014  
  
 ENGINEER OF SAFETY ENGINEERING  
 APPROVED January 1, 2014  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

**URBAN LANE CLOSURE,  
 MULTILANE, 1W OR 2W WITH  
 NONTRAVERSABLE MEDIAN**

(Sheet 2 of 2)

**STANDARD 701601-09**



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

- SYMBOLS**
- Arrow board
  - Work area
  - Barricade or drum with steady burning monidirectional light
  - Flagger with traffic control sign
  - Cone, drum or barricade
  - Sign on portable or permanent support
  - Type III barricade with flashing lights

**CASE I**

- ① Refer to SIGN SPACING TABLE for distances.
- ② Required for speeds > 40 mph (70 km/h).
- ③ Required if work exceeds 500' (164 m) or 1 block, repeat every 1 mile (1.6 km).
- ④ Cones at 25' (8 m) centers for 250' (75 m) on approach. Additional cones may be placed at 50' (15 m) centers. When drums or type I or II barricades are used, the interval between devices may be doubled.
- ⑤ For approved sideroad closures.
- ⑥ Cones, drums or barricades at 20' (6 m) centers in taper.
- ⑦ Use flagger sign only when flagger is present.

**GENERAL NOTES**

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of one traffic lane in an Urban area.

If the work operation is performed between 9:00 a.m. and 3:00 p.m. and does not exceed 15 min. Traffic protection shall be as shown for Standard 701426.

Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L=(W)(S)$	$L=0.65(W)(S)$

W = Width of offset in feet (meters).  
 S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-19	Revised to allow cones at night.
1-1-18	Moved arrow boards into closed lanes for CASE I.

**URBAN LANE CLOSURE,  
MULTILANE, 2W WITH  
BIDIRECTIONAL LEFT TURN LANE**

(Sheet 1 of 4)


**STANDARD 701602-10**

Illinois Department of Transportation


APPROVED January 1, 2019  
  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2019  
  
 ENGINEER OF DESIGN AND ENVIRONMENT




ISSUED 1-1-13








**CASE III**

 Illinois Department of Transportation  
 APPROVED January 1, 2019  
  
 ENGINEER OF SAFETY PROG. AND ENGINEERING  
 APPROVED January 1, 2019  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-13

**URBAN LANE CLOSURE,  
 MULTILANE, 2W WITH  
 BIDIRECTIONAL LEFT TURN LANE**  
 (Sheet 3 of 4)  
**STANDARD 701602-10**



**CASE IV**

Illinois Department of Transportation


APPROVED January 1, 2019  
*Cynthia Watt*  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2019  
*J. E. ...*  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-13

**URBAN LANE CLOSURE,  
 MULTILANE, 2W WITH  
 BIDIRECTIONAL LEFT TURN LANE**  
 (Sheet 4 of 4)

**STANDARD 701602-10**



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

- SYMBOLS**
- Arrow board
  - Cone, drum or barricade
  - Sign on portable or permanent support
  - Work area
  - Barricade or drum with flashing light
  - Flagger with traffic control sign.

- ① Refer to SIGN SPACING TABLE for distances.
- ② Required for speeds > 40 mph.
- ③ Use flagger sign only when flagger is present.
- ④ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ⑤ Cones, drums or barricades at 20' (6 m) centers in taper.

**GENERAL NOTES**

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of one traffic lane in an Urban area.

Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L = (W)(S)$	$L = 0.65(W)(S)$

W = Width of offset in feet (meters).

S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

PASSED January 1, 2015  
  
 ENGINEER OF SAFETY ENGINEERING


APPROVED January 1, 2015  
  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

DATE	REVISIONS
1-1-15	Renamed standard. Moved case on Sheet 2 to new Highway Standard.
1-1-14	Revised workers sign number to agree with current MUTCD.

**URBAN SINGLE LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN**

**STANDARD 701606-10**



SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)

- W1-3L(O)-48  
Speeds 30 mph (50 km/h) or less
- W13-1(O)-2424
- Or
- W1-4L(O)-48
- W13-1(O)-2424

- SYMBOLS**
- Arrow board
  - Cone, drum or barricade
  - Sign on portable or permanent support
  - Work area
  - Barricade or drum with flashing light
  - Type III barricade with flashing lights
  - Flagger with traffic control sign.

- ① Refer to SIGN SPACING TABLE for distances.
- ② Required for speeds > 40 mph.
- ③ Use flagger sign only when flagger is present.
- ④ For approved sideroad closures.
- ⑤ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ⑥ Cones, drums or barricades at 20' (6 m) centers in taper.
- ⑦ Repeat every 1 mile (1.6 km).

**GENERAL NOTES**

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement requiring the closure of more than one traffic lane in an Urban area.

Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L = (W)(S)$	$L = 0.65(W)(S)$

W = Width of offset in feet (meters).  
S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
4-1-16	Moved first reverse curve/turn sign to middle of tangent.
1-1-15	New Standard.

**URBAN HALF ROAD CLOSURE,  
MULTILANE, 2W WITH  
MOUNTABLE MEDIAN**

**STANDARD 701611-01**

Illinois Department of Transportation


PASSED April 1, 2016

*[Signature]*  
ENGINEER OF SAFETY ENGINEERING

APPROVED April 1, 2016

*[Signature]*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-15



**LEFT TURN LANE OR CENTER MEDIAN OPERATIONS**


- ① Refer to SIGN SPACING TABLE for distance.
- ② Required for speed > 40 mph.
- ③ Cones at 25' (8 m) centers for 250' (75 m). Additional cones may be placed at 50' (15 m) centers. When drums or Type I or Type II barricades are used, the interval between devices may be doubled.
- ④ Use flagger sign only when flagger is present.
- ⑤ Omit this sign when median is less than 10' (3 m) or for bi-directional turn lanes.
- ⑥ Cones, drums or barricades at 20' (6 m) centers in taper.
- ⑦ Advanced arrow board required for speeds > 45 mph.
- ⑧ Three Type II barricades, drums or vertical barricades at 50' (15 m) centers.

SIGN SPACING	
Posted Speed	Sign Spacing
55	500' (150 m)
50-45	350' (100 m)
<45	200' (60 m)


**SYMBOLS**

- Work area
- Cone, drum or barricade
- Sign on portable or permanent support
- Arrow board
- Barricade or drum with flashing light
- Flagger with traffic control sign

**SHOULDER OPERATIONS**



**CORNER ISLAND OPERATIONS**



**GENERAL NOTES**

This Standard is used where at any time, day or night, any vehicle, equipment, workers or their activities encroach on the pavement during shoulder operations or where construction requires lane closures in an urban area.

Calculate L as follows:

SPEED LIMIT	FORMULAS	
	English	(Metric)
40 mph (70 km/h) or less:	$L = \frac{WS^2}{60}$	$L = \frac{WS^2}{150}$
45 mph (80 km/h) or greater:	$L = (W)(S)$	$L = 0.65(W)(S)$

W = Width of offset in feet (meters).

S = Normal posted speed mph (km/h).

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
4-1-16	Corrected sign number for LEFT TURN LANE CLOSED AHEAD.
1-1-14	Added devices at arrow board upstream from taper.
	Rev. workers sign number.

**URBAN LANE CLOSURE, MULTILANE INTERSECTION**


**STANDARD 701701-10**

Illinois Department of Transportation

PASSED April 1, 2016  
  
 ENGINEER OF SAFETY ENGINEERING

APPROVED April 1, 2016  
  
 ENGINEER OF DESIGN AND ENVIRONMENT


ISSUED 1-1-97



① ROAD CONSTRUCTION AHEAD  
W20-1103(0)-48 for contract construction projects

Or  
① ROAD WORK AHEAD  
W20-1(0)-48 for maintenance and utility projects

**SIDEWALK DIVERSION**



① ROAD CONSTRUCTION AHEAD  
W20-1103(0)-48 for contract construction projects

Or  
① ROAD WORK AHEAD  
W20-1(0)-48 for maintenance and utility projects

SIDEWALK CLOSED  
←  
USE OTHER SIDE  
R11-1102-2430

SIDEWALK CLOSED  
R11-1101-2418

SIDEWALK CLOSED  
→  
USE OTHER SIDE  
R11-1102-2430

**SIDEWALK CLOSURE**

① Omit whenever duplicated by road work traffic control.

**GENERAL NOTES**

This Standard is used where, at any time, pedestrian traffic must be rerouted due to work being performed.

This Standard must be used in conjunction with other Traffic Control & Protection Standards when roadway traffic is affected.

Temporary facilities shall be detectable and accessible.

The temporary pedestrian facilities shall be provided on the same side of the closed facilities whenever possible.

The SIDEWALK CLOSED / USE OTHER SIDE sign shall be placed at the nearest crosswalk or intersection to each end of the closure. Where the closure occurs at a corner, the signs shall be erected on the corners across the street from the closure. The SIDEWALK CLOSED signs shall be used at the ends of the actual closures.

Type III barricades and R11-2-4830 signs shall be positioned as shown in "ROAD CLOSED TO ALL TRAFFIC" detail on Standard 701901.

All dimensions are in inches (millimeters) unless otherwise shown.

**SYMBOLS**

- Work area
- Sign on portable or permanent support
- Barricade or drum
- Cone, drum or barricade
- Type III barricade
- Detectable pedestrian channelizing barricade

Illinois Department of Transportation

PASSED April 1, 2016  
*[Signature]*  
ENGINEER OF SAFETY ENGINEERING

APPROVED April 1, 2016  
*[Signature]*  
ENGINEER OF DESIGN AND ENVIRONMENT


ISSUED 1-1-97

DATE	REVISIONS
4-1-16	Omitted orange safety fence from standard as this is covered in the std. spec.
1-1-12	Added SIDEWALK DIVERSION. Modified appearance of plan views. Renamed Std.


**SIDEWALK, CORNER OR CROSSWALK CLOSURE**

(Sheet 1 of 2)

**STANDARD 701801-06**



**CORNER CLOSURE**



**CROSSWALK CLOSURE**

① ROAD CONSTRUCTION AHEAD  
Or  
① ROAD WORK AHEAD

W20-I103(0)-48 for contract construction projects  
W20-1(0)-48 for maintenance and utility projects

① ROAD CONSTRUCTION AHEAD  
Or  
① ROAD WORK AHEAD

W20-I103(0)-48 for contract construction projects  
W20-1(0)-48 for maintenance and utility projects

**SIDEWALK, CORNER OR CROSSWALK CLOSURE**

(Sheet 2 of 2)

**STANDARD 701801-06**

Illinois Department of Transportation


PASSED April 1, 2016

*[Signature]*  
ENGINEER OF SAFETY ENGINEERING


APPROVED April 1, 2016

*[Signature]*  
ENGINEER OF DESIGN AND ENVIRONMENT


ISSUED 1-1-97




**DAYTIME USE**




**DAY OR NIGHTTIME USE**



**TUBULAR MARKER**




**VERTICAL PANEL  
POST MOUNTED**




**DRUM**


**CONES**




**TYPE I BARRICADE**




**TYPE II BARRICADE**




**TYPE III BARRICADE**



**DIRECTION INDICATOR  
BARRICADE**



**VERTICAL BARRICADE**



**DETECTABLE PEDESTRIAN  
CHANNELIZING BARRICADE**

\* Warning lights (if required)

**GENERAL NOTES**

All heights shown shall be measured above the pavement surface.

All dimensions are in inches (millimeters) unless otherwise shown.

DATE	REVISIONS
1-1-19	Revised cone usage and added cones >36" (900 mm) height.
1-1-18	Revised END WORK ZONE SPEED LIMIT sign from orange to white background.

**TRAFFIC CONTROL DEVICES**

(Sheet 1 of 3)

**STANDARD 701901-08**


Illinois Department of Transportation

APPROVED January 1, 2019  
  
 ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2019  
  
 ENGINEER OF DESIGN AND ENVIRONMENT


ISSUED  
 ET-1-1 (08/05)






**POST MOUNTED SIGNS**

\*\* When curb or paved shoulder are present this dimension shall be 24 (600) to the face of curb or 6' (1.8 m) to the outside edge of the paved shoulder.




**SIGNS ON TEMPORARY SUPPORTS**

\*\*\* When work operations exceed four days, this dimension shall be 5' (1.5 m) min. If located behind other devices, the height shall be sufficient to be seen completely above the devices.




**HIGH LEVEL WARNING DEVICE**



W12-I103-4848

**WIDTH RESTRICTION SIGN**

XX'-XX" width and X miles are variable.



FRONT SIDE

REVERSE SIDE

**FLAGGER TRAFFIC CONTROL SIGN**

ROAD CONSTRUCTION NEXT X MILES	END CONSTRUCTION
G20-I104(0)-6036	G20-I105(0)-6024

This signing is required for all projects 2 miles (3200 m) or more in length.

ROAD CONSTRUCTION NEXT X MILES sign shall be placed 500' (150 m) in advance of project limits.

END CONSTRUCTION sign shall be erected at the end of the job unless another job is within 2 miles (3200 m).

Dual sign displays shall be utilized on multi-lane highways.

**WORK LIMIT SIGNING**

WORK ZONE	W21-III5(0)-3618
SPEED LIMIT XX	R2-1-3648
PHOTO ENFORCED	R10-I108p-3618 ****
\$XXX FINE MINIMUM	R2-I106p-3618

Sign assembly as shown on Standards or as allowed by District Operations.

END WORK ZONE SPEED LIMIT	G20-I103-6036
---------------------------	---------------

This sign shall be used when the above sign assembly is used.

**HIGHWAY CONSTRUCTION SPEED ZONE SIGNS**

\*\*\*\* R10-I108p shall only be used along roadways under the jurisdiction of the State.

Illinois Department of Transportation

APPROVED January 1, 2019  
*Cynthia Watt*  
 ENGINEER OF SAFETY PROG. AND ENGINEERING


APPROVED January 1, 2019  
*J. E. ...*  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-13





**TRAFFIC CONTROL DEVICES**

(Sheet 2 of 3)


**STANDARD 701901-08**



**ARROW BOARDS**




**TEMPORARY RUMBLE STRIPS**



**ROAD CLOSED TO ALL TRAFFIC**

Reflectorized striping may be omitted on the back side of the barricades. If a Type III barricade with an attached sign panel which meets NCHRP 350 is not available, the sign may be mounted on an NCHRP 350 temporary sign support directly in front of the barricade.



**ROAD CLOSED TO THRU TRAFFIC**

Reflectorized striping shall appear on both sides of the barricades. If a Type III barricade with an attached sign panel which meets NCHRP 350 is not available, the signs may be mounted on NCHRP 350 temporary sign supports directly in front of the barricade.

**TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD**

**TRAFFIC CONTROL DEVICES**

(Sheet 3 of 3)

**STANDARD 701901-08**

Illinois Department of Transportation


APPROVED January 1, 2019

*Cynthia Watt*  
ENGINEER OF SAFETY PROG. AND ENGINEERING

APPROVED January 1, 2019


*Joe E. ...*  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUES: E1-1-1




Reduce to 40' (12.2 m) o.c. on curves with posted or advisory speeds of 45 mph (70 km/h) or less.

**TWO-LANE / TWO-WAY**




**LANE REDUCTION TRANSITION**




\*,\*\* See MULTI LANE DIVIDED detail for lane marker notes.

**TWO-WAY LEFT TURN**



\*,\*\* See MULTI LANE DIVIDED detail for lane marker notes.


**MULTI-LANE UNDIVIDED**





\* Reduce to 40' (12.2 m) o.c. on curves where advisory speeds are 10 mph (15 km/h) lower than posted speeds.

\*\* Where double lane line markers are specified, they shall be spaced as shown.


**MULTI-LANE DIVIDED**



**FREEWAY EXIT RAMP**



**RURAL LEFT TURN**



**SYMBOLS**

- Yellow stripe
- White stripe
- One-way amber marker
- One-way crystal marker
- Two-way amber marker

All dimensions are in inches (millimeters) unless otherwise shown.

Illinois Department of Transportation

PASSED April 1, 2016  
*Amy Eller*  
 ENGINEER OF OPERATIONS


APPROVED April 1, 2016  
*[Signature]*  
 ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-97

DATE	REVISIONS
4-1-16	Revised LANE ENDS sign
	W4-2 to agree with current MUTCD.
1-1-09	Switched units to English (metric).

**TYPICAL APPLICATIONS  
RAISED REFLECTIVE  
PAVEMENT MARKERS**

**STANDARD 781001-04**



**NOTES:**

- SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
  - ONE "ROAD CONSTRUCTION AHEAD" SIGN 36 x 36 (900x900) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
  - THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
  - ONE "ROAD CONSTRUCTION AHEAD" SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
  - THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
- CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
- SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).
- WHEN WORK IS BEING PERFORMED ON A SIDE ROAD OR DRIVEWAY, FOLLOW THE APPLICABLE STANDARD(S). THE DIRECTIONAL ARROW (M6-1 OR M6-4) SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE TRAFFIC CONTROL SET-UP.
- ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAYS UNLESS OTHERWISE SPECIFIED IN THE PLANS OR BY THE ENGINEER.
- THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in inches (millimeters) unless otherwise shown.

MODEL: Default  
FILE NAME: p:\1108\EBID\NTEG\Illinois.gov\PIV\DOT\Documents\DOT\_Offices\District\_1\Projects\DH5422\31\CADD\Draw\CAD\sheet\10.dgn

USER NAME = footemj	DESIGNED - L.H.A.	REVISED - A. HOUSEH 10-15-96
PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED - T. RAMMACHER 01-06-00
PLOT DATE = 3/4/2019	DATE - 06-89	REVISED - A. SCHUETZE 07-01-13
		REVISED - A. SCHUETZE 09-15-16


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC CONTROL AND PROTECTION FOR  
SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS**


SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	<b>TC-10</b>			
		CONTRACT NO.		
ILLINOIS FED. AID PROJECT				






**2-LANE ROADWAY**




**MULTI-LANE UNDIVIDED**




**MULTI-LANE DIVIDED WITH MEDIAN**

**TYPICAL LANE AND EDGE LINE MARKING**




**TYPICAL CROSSWALK MARKING**


\* MARKINGS SHALL BE INSTALLED PARALLEL TO THE CENTERLINE OF THE ROAD WHICH IT CROSSES




**4' (1.2 m) WIDE MEDIANS ONLY**



**MEDIANS OVER 4' (1.2 m) WIDE**




**TYPICAL PAINTED MEDIAN MARKING**



**MEDIAN WITH TWO-WAY LEFT TURN LANE**


**TYPICAL PAINTED MEDIAN MARKING**




FULL SIZE LETTERS 8' (2.4 m) AND ARROWS SHALL BE USED.  
 AREA = 15.6 SQ. FT. (1.5 m<sup>2</sup>) ONLY AREA = 20.8 SQ. FT. (1.9 m<sup>2</sup>)  
 \* TURN LANES IN EXCESS OF 400' (120 m) IN LENGTH MAY HAVE AN ADDITIONAL SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF ARROW - "ONLY".

**TYPICAL LEFT (OR RIGHT) TURN LANE**

**TYPICAL TURN LANE MARKING**




**ISLAND OFFSET FROM PAVEMENT EDGE**




**ISLAND AT PAVEMENT EDGE**

**TYPICAL ISLAND MARKING**



**COMBINATION LEFT AND U-TURN**



**U-TURN**

**LANE REDUCTION TRANSITION**

\* LANE REDUCTION ARROWS REQUIRED AT SPEEDS OF 45 MPH OR GREATER OR WHEN SPECIFIED IN PLANS.

D(FT)	SPEED LIMIT
345	30
425	35
500	40
580	45
665	50
750	55

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING / REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVIDED PAVEMENT	2 @ 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 @ 4 (100)	SOLID SOLID	YELLOW YELLOW	5 1/2 (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MEDIANS IN YELLOW
TURN LANE MARKINGS	6 (150) LINE: FULL SIZE LETTERS & SYMBOLS (8' (2.4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	2 @ 4 (100) EACH DIRECTION 8' (2.4m) LEFT ARROW	SKIP-DASH AND SOLID IN PAIRS	YELLOW WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5 1/2 (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 12 (300) @ 45° 12 (300) @ 90°	SOLID SOLID SOLID	WHITE WHITE WHITE	NOT LESS THAN 6' (1.8 m) APART 2' (600) APART 2' (600) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT. OTHERWISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE.
PAINTED MEDIANS	2 @ 4 (100) WITH 12 (300) DIAGONALS @ 45° NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS	SOLID	YELLOW: TWO WAY TRAFFIC WHITE: ONE WAY TRAFFIC	11 (280) C-C FOR THE DOUBLE LINE SEE TYPICAL PAINTED MEDIAN MARKING.
GORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS @ 45°	SOLID	WHITE	DIAGONALS: 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h) 30' (9 m) C-C (OVER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES: "RR" 15 6' (1.8 m) LETTERS; 16 (400) LINE FOR "X"	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: "R"=3.6 SQ. FT. (0.33 m <sup>2</sup> ) EACH "X"=54.0 SQ. FT. (5.0 m <sup>2</sup> )
SHOULDER DIAGONALS (REQUIRED FOR SHOULDERS > 8')	12 (300) @ 45°	SOLID	WHITE - RIGHT YELLOW - LEFT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h)) 150' (45 m) C-C (OVER 45MPH (70 km/h))
U TURN ARROW	SEE DETAIL	SOLID	WHITE	16.3 SF
2 ARROW COMBINATION LEFT AND U TURN	SEE DETAIL	SOLID	WHITE	30.4 SF

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

All dimensions are in inches (millimeters) unless otherwise shown.

MODEL: D:\default...  
 FILE NAME: p:\u0008\EBID\NTEC...  
 PROJECT: D:\projects\1145422\2341\CAD\Drawings\CAD\sheet\13.dwg


USER NAME	DESIGNED	REVISED
= footemj	- EVERS	- C. JUCIUS 09-09-09
	- DRAWN	- C. JUCIUS 07-01-13
	- CHECKED	- C. JUCIUS 12-21-15
	- DATE	- C. JUCIUS 04-12-16

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

DISTRICT ONE TYPICAL PAVEMENT MARKINGS			
SCALE: NONE	SHEET 1 OF 2 SHEETS	STA.	TO STA.


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	TC-13			
		CONTRACT NO.		
		ILLINOIS FED. AID PROJECT		

# TURN BAY ENTRANCE AT START OF LANE CLOSURE TAPER










**FIGURE 1**

# TURN BAY ENTRANCE WITHIN A LANE CLOSURE




**FIGURE 2**

## LEGEND

-  WORK AREA
-  LANE OPEN TO TRAFFIC
-  ARROW BOARD
-  TYPE I OR II BARRICADE OR DRUM WITH STEADY BURN LIGHT
-  DRUM WITH STEADY BURN LIGHT
-  SIGN ASSEMBLY
-  TYPE I OR II CHECK BARRICADE WITH FLASHING LIGHT

## NOTES:

1. A) WHEN "L" IS  $\leq$  THE STORAGE LENGTH OF THE TURN LANE (AS SHOWN IN FIG. 1), USE FIGURE 1.  
B) WHEN "L" IS  $>$  THE STORAGE LENGTH OF THE TURN LANE OR THE TURN LANE IS WITHIN THE LANE CLOSURE, USE FIGURE 2.
2. CONES MAY BE SUBSTITUTED FOR BARRICADES OR DRUMS AT HALF THE SPACING DURING DAY OPERATIONS. CONES SHALL BE A MINIMUM OF 28 (710) IN HEIGHT.
3. LIGHTS WILL NOT BE REQUIRED ON BARRICADES OR DRUMS FOR DAY OPERATIONS. ALL LIGHTS SHALL BE MONODIRECTIONAL.
4. REFLECTIVE TEMPORARY PAVEMENT MARKINGS SHALL BE PLACED THROUGHOUT THE BARRICADED AREAS OF EACH TURN BAY AS SHOWN WHERE THE CLOSURE TIME IS GREATER THAN FOURTEEN (14) DAYS.
5. THIS APPLICATION ALSO APPLIES WHEN WORK IS BEING PERFORMED IN THE RIGHT LANE(S) AND THE RIGHT TURN BAY IS TO REMAIN OPEN. UNDER THIS CONDITION, "RIGHT TURN LANE" R3-1100R 24 x 24 (600 x 600) AND M6-2R 21 x 15 (530 x 380) SHALL BE USED.
6. THESE CONTROLS SHALL SUPPLEMENT MAINLINE TRAFFIC CONTROL FOR LANE CLOSURES.
7. THE SIGNS SHALL BE MOUNTED ABOVE THE BARRICADES/DRUMS ON SEPARATE SIGN SUPPORTS THAT MEET NCHRP 350 OR MASH REQUIREMENTS.
8. TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC) SHALL BE INCLUDED IN THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.



**DETAIL A**

All dimensions are in inches (millimeters) unless otherwise shown.

MODEL: Default  
FILE NAME: p:\1108\EBID\NTEG\Illinois.gov\PIV\DOT\Documents\DOT\_Offices\District\_1\Projects\DH\5422\31\CADD\Draw\CAD\Sheet\TC14.dgn

USER NAME = footemj	DESIGNED - T. RAMMACHER 09-08-94	REVISED - R. BORO 09-14-09
	DRAWN - A. HOUSEH 11-07-95	REVISED - A. SCHUETZE 07-01-13
PLOT SCALE = 50.0000' / in.	CHECKED - A. HOUSEH 10-12-96	REVISED - A. SCHUETZE 09-15-16
PLOT DATE = 3/4/2019	DATE - T. RAMMACHER 01-06-00	REVISED -


**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**TRAFFIC CONTROL AND PROTECTION AT TURN BAYS  
(TO REMAIN OPEN TO TRAFFIC)**

SCALE: NONE SHEET 1 OF 1 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	TC-14			
ILLINOIS FED. AID PROJECT			CONTRACT NO.	


# RECESSED PAVEMENT MARKER



## Notes

1. The reflector holder shall be made of a polycarbonate and shall be a MarkerOne Series R100 or Engineer approved equivalent.
2. The adhesive used shall meet the requirements of AASHTO M237 specification for adhesives to be used in cementing asphalt surfaces.
3. For 1-way markers heading uphill, uphill grind taper may be omitted.
4. Markers shall be placed at 80' intervals on lane lines and painted medians and 40' intervals on curves and approaching intersections.

Breakaway tab to fix the reflector depth to 0.10" below the pavement



Reflector Holder Detail



# PAVEMENT MARKINGS AND PAVEMENT MARKERS

## MATERIALS FOR PAVEMENT MARKINGS:

<u>LOCATION</u>	<u>MATERIAL</u>
ALL MARKINGS ON BITUMINOUS PAVEMENT	THERMOPLASTIC PAVEMENT MARKINGS
ALL MARKINGS ON CONCRETE SURFACES	URETHANE PAVEMENT MARKINGS

## INSTALLATION OF PAVEMENT MARKINGS:

<u>LOCATION</u>	<u>TYPE OF MARKING</u>
PAINTED MEDIANS	4" DOUBLE YELLOW; 11" c-c AND 12" YELLOW @ 45°; 30' c-c 4" YELLOW
BARRIER MEDIANS	6" WHITE, 2' LONG, 6' SPACE (DOTTED WHITE)
TURN BAY TAPERS ALONG THRU LANES	ARROW AND "ONLY"
START OF TURN BAYS	ADDITIONAL ARROW 10' FROM END
END OF TURN BAYS 150'-200' LONG	ADDITIONAL "ONLY"
TURN BAYS > 200' LONG	

ALL OTHER MARKINGS PER MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES OF ILLINOIS.

## INSTALLATION OF RECESSED REFLECTIVE PAVEMENT MARKERS:

<u>LOCATION</u>	<u>SPACING</u>
DOUBLE YELLOW CENTERLINE, & SKIP-DASH WHITE LANE LINES	40'
SOLID LANE LINES (TURN BAYS)	40'
END OF PAINTED MEDIANS	3 @ 3' LATERAL

<u>LOCATION</u>	<u>TYPE</u>
DOUBLE YELLOW CENTERLINE	2-WAY YELLOW
PAINTED MEDIANS ≤ 4' WIDE	2-WAY YELLOW
PAINTED MEDIANS >4' WIDE	1-WAY YELLOW
YELLOW LINE ALONG BARRIER MEDIANS	NONE **

\*\* EXCEPT IN SPECIAL CIRCUMSTANCES

SKIP-DASH WHITE LANE LINES, SOLID LANE LINES (TURN BAYS)  
2-WAY, UNDIVIDED ROADWAY  
1-WAY ROADWAY, OR DIVIDED WITH BARRIER MEDIAN

1-WAY WHITE  
2-WAY WHITE / RED